

ENGINEERING EVALUATION AND COST ANALYSIS (EE/CA) FOR DEUL'S MOUNTAIN WESTINGHOUSE FORMER FUEL CYCLE FACILITY SITE FESTUS, MO

Westinghouse Electric Company LLC 3300 State Road P Festus, Missouri 63028

August 2004

TABLE OF CONTENTS

ACRO	NYMS	.III
EXECU	UTIVE SUMMARY	.IV
1.0	INTRODUCTION	6
2.0	SITE CHARACTERIZATION	6
2.1	SITE DESCRIPTION AND BACKGROUND	6
2.2	PREVIOUS REMOVAL ACTIONS	7
2.3	SOURCE, NATURE, AND EXTENT OF CONTAMINATION	7
2.4	Analytical Data	
2.5	SITE CONDITIONS JUSTIFYING A REMOVAL ACTION	
2.6	STREAMLINED RISK EVALUATION	
	2.6.1 Human Health Risks	
	2.6.2 Proposed Cleanup Levels	
3.0	IDENTIFICATION OF REMOVAL ACTION OBJECTIVES	. 10
3.1	STATUTORY LIMITS	. 10
3.2	SCOPE AND PURPOSE	
3.3	REMOVAL ACTION SCHEDULE	
3.4	PLANNED REMEDIAL ACTIVITIES	
3.5	APPLICABLE OR RELEVANT AND APPROPRIATE REQUIREMENTS	. 11
4.0	IDENTIFICATION OF REMOVAL ACTION ALTERNATIVES	. 16
4.1	ALTERNATIVE 1: NO ACTION WITH ENGINEERING CONTROLS	. 16
4.2	ALTERNATIVE 2: RELOCATION AND OPEN STORAGE ON-SITE	
4.3	ALTERNATIVE 3: RELOCATION AND CONTAINERIZED STORAGE ON-SITE	
4.4	ALTERNATIVE 4: EXCAVATION AND OFF-SITE DISPOSAL OF SOIL	
4.5	ALTERNATIVE 5: EXCAVATION, CONSOLIDATION FOR VOLUMETRIC CLEARANCE FOR	
	DISPOSAL	. 17
5.0	ANALYSIS OF REMOVAL ACTION ALTERNATIVES	. 17
5.1	Effectiveness	. 18
	5.1.1 Overall Protection of Human Health and the Environment	
	5.1.2 Compliance with ARARs	
5.2	IMPLEMENTABILITY	
3.2	5.2.1 Technical Feasibility	
	5.2.2 Administrative Feasibility	23
5.3	COST	
5.4	SUMMARY OF REMOVAL ACTION ALTERNATIVES	
	5.4.1 Alternative 1 in Summary	
	5.4.2 Alternative 2 in Summary	
	- · · · · · · · · · · · · · · · · · · ·	



	5 1 1	Altanuation Air Communica	26
	5.4.4 5.4.6	Alternative 4 in SummaryAlternative 5 in Summary	26 26
6.0	COMPAR	ATIVE ANALYSIS OF REMOVAL ACTION ALTERNATIVES	27
7.0	RECOMN	MENDED REMOVAL ACTION ALTERNATIVE	29
8.0		TION OF POST-REMOVAL SITE CONTROL ACTIVITIES NECESSARY TO THE INTEGRITY OF THE REMOVAL ACTION	29
9.0	REFERE	NCES	29

APPENDICES

Appendix A: Westinghouse Electric Co. Analytical Results

Appendix B: Contractor Analytical Results

Appendix C: Contractor Soil Sample Location Map

ACRONYMS

AEC Atomic Energy Commission ALARA As low as reasonably achievable

ARAR Applicable or Relevant and Appropriate Requirements
BEIR Committee on the Biological Effects of Ionizing Radiation

CERCLA Comprehensive Environmental Response, Compensation, and Liability Act

CFR U.S. Code of Federal Regulations

COC Constituents of concern
DOE U.S. Department of Energy

DOT U. S. Department of Transportation
EE/CA Engineering Evaluation and Cost Analysis
EPA U.S. Environmental Protection Agency

FFCF Former Fuel Cycle Facility

FSS Final Status Survey

ICRP International Commission on Radiological Protection

MARSSIM Multi-Agency Radiation Survey and Site Investigation Manual

MDNR Missouri Department of Natural Resources

NCP National Oil and Hazardous Substances Pollution Contingency Plan

NCRP National Council on Radiation Protection

NRC Nuclear Regulatory Commission

OSHA Occupational Safety and Health Administration

PPE Personal Protective Equipment

RI Remedial Investigation

RI/FS WP Remedial Investigation / Feasibility Study Work Plan

TBC To Be Considered

VCD Volumetric Clearance for Disposal

WAC Waste Acceptance Criteria

EXECUTIVE SUMMARY

Westinghouse Electric Company LLC (Westinghouse) has prepared this Engineering Evaluation and Cost Analysis (EE/CA) to evaluate potential removal action alternatives for "Deul's Mountain," a soil pile at the Hematite Former Fuel Cycle Facility (FFCF). This pile contains an estimated 1,100 cubic yards of uranium-impacted soils generated from previous remediation efforts at the site and from the earlier installation of a loading dock. Relocation of this pile is needed to allow for the investigation of possible burial pits located beneath the current location of the pile. Identification and characterization of these pits is an integral part of the RI/FS Work Plan being implemented at the FFCF Site. In addition, given the fact that the soil pile itself contains uranium-impacted soils, it is likely that a response action to address these impacts will be required. This EE/CA will address both of these objectives.

The FFCF Site is located in the east portion of Missouri, in Jefferson County, near the town of Hematite. It fronts the eastbound lane of Missouri State Road P, between the hills to the northwest and a terrace/floodplain of Joachim Creek to the southeast. The topography slopes gently to the southeast eventually blending with the alluvial floodplain deposits of the Joachim Creek, which runs along the southeastern edge of the Site property and flows into the Mississippi River.

An investigation of Deul's Mountain was conducted in September 2002. Westinghouse tasked US Ecology to perform a limited characterization. Based on historical information, the soils contained in Deul's mountain were expected to contain U238, U-235, and U234. Analytical results from samples collected during the characterization confirmed the presence of U-238, U-235, and U-234. No other isotopes were detected.

The result of the EE/CA process provides a recommendation for a response action based on the evaluation of the alternatives considered. Preparation of this EE/CA fulfills the Comprehensive Environmental Response, Compensation, and Liability Act (CERCLA) requirement for documenting selection of a response action. As noted above, the goal of this EE/CA is to develop an alternative for Deul's Mountain that is protective of human health and the environment and that allows for the timely implementation of the site-wide Remedial Investigation, including the investigation of possible burial pits.

This EE/CA discusses the results of the evaluation of five Removal Action Alternatives regarding the final disposition of impacted soil in Deul's Mountain. Westinghouse developed the removal action alternatives for Deul's Mountain after evaluating applicable technologies capable of protecting human health and the environment. The evaluated alternatives are the following:

- Alternative 1: No Action with Engineering Controls;
- Alternative 2: Relocation and Storage for Evaluation during Future Site Response Activities;



- Alternative 3: Excavation and On-Site Storage of Soil;
- Alternative 4: Excavation and Off-Site Disposal of Soils; and
- Alternative 5: Excavation, Consolidation for Volumetric Clearance for Disposal

The recommended alternative is Alternative 5, which allows for the excavation and off-site disposal of impacted materials in Deul's Mountain and the complete and timely characterization of burial pits located beneath the soil pile. All five alternatives were evaluated with respect to effectiveness, implementability, cost, and other relevant factors.

1.0 INTRODUCTION

Westinghouse Electric Company (Westinghouse) has prepared this Engineering Evaluation and Cost Analysis (EE/CA) to evaluate potential response options for "Deul's Mountain" at the Former Fuel Cycle Facility (FFCF) Site. This response action is required to mitigate both a human health and environmental risk and to remove interferences with the site-wide Remedial Investigation (RI). Investigation of historical operations at the site indicates that the footprint beneath Deul's Mountain may contain burial pits.

2.0 SITE CHARACTERIZATION

Site characterization includes discussion of both the site description and background information; previous removal actions; the source, nature, and extent of contamination; summary of analytical data; the site conditions justifying a removal action; and a streamlined risk evaluation.

2.1 Site Description and Background

The FFCF Site is located in the eastern portion of Missouri in Jefferson County near the town of Hematite. It fronts the eastbound lane of Missouri State Road P, between the hills to the northwest and a terrace/floodplain of Joachim Creek to the southeast. The topography slopes gently to the southeast eventually blending with the alluvial floodplain deposits of the Joachim Creek, which runs along the southeastern edge of the Site property and flows into the Mississippi River.

Within four miles of the Site more than 11,000 people are served by public wells in the area, and nearly 1,000 are served by private wells. The surrounding area is mainly suburban residential.

The FFCF Site is privately owned by Westinghouse and was acquired from ABB in April of 2000. The FFCF Site has been commercially owned and operated since manufacturing operations began in 1956. The U.S. Department of Energy (DOE) and its predecessors were the primary customers of the FFCF Site between 1956 and 1974. There are currently no manufacturing operations being performed at the FFCF Site.

Primary functions at the FFCF Site throughout its history have included the manufacture of uranium compounds from natural and enriched uranium for use as nuclear fuel. Specifically, operations included the conversion of uranium hexafluoride gas of various ²³⁵U enrichments to uranium oxide, uranium carbide and uranium metal. These products were manufactured for use by the Federal government and government contractors and by commercial and research reactors approved by the Atomic Energy Commission (AEC). Research and development was also conducted at the FFCF Site, as were uranium scrap recovery processes.

2.2 Previous Removal Actions

A number of previous investigations and removal actions have been conducted at the FFCF Site relating to both on-site and off-site impacts. Specifically, in 2002, Westinghouse, in conjunction with the Missouri Department of Natural Resources (MDNR), determined that a time-critical removal action was appropriate to mitigate potential risks associated with groundwater impacts in the vicinity of the FFCF Site. Westinghouse prepared an Action Memorandum to document its response (bottled water, filtration units, as needed and additional investigation) to address the potential risk. This Action Memorandum was subsequently approved by MDNR and implemented. As a follow up to this response action, Westinghouse submitted an EE/CA to MDNR in January 2003. The evaluation of groundwater conditions and potential alternatives to address these conditions was conducted as a non-time critical removal action in accordance with the Comprehensive Environmental Response, Compensation and Liability Act (CERCLA), 42 U.S.C. § 9601 et seq., the National Contingency Plan (NCP), 40 C.F.R. § 300.1 et seq., and resulted in an extension of the existing water supply to residents in the vicinity of the FFCF Site. These removal action documents are available in the information repository established for the FFCF Site.

With respect to Deul's Mountain, routine sampling has been conducted; however no subsurface soil sampling has been performed below three (3) feet. Soil samples were taken to a depth of three (3) feet from the top of Deul's Mountain to characterize the soil. Westinghouse's sampling results of Deul's Mountain are provided in Appendix A. In addition, a contractor was hired to perform sampling of Deul's Mountain and these results are found in Appendix B with a corresponding map in Appendix C.

2.3 Source, Nature, and Extent of Contamination

Deul's Mountain consists of approximately 1,100 cubic yards of soil located within the current facility security fencing. The soil pile is believed to have originated from the construction of a truck bay associated with Building 256, on the far north side of the FFCF Site, by a previous owner/operator of the facility. Although the shape is not uniform, the footprint is approximately 90 feet by 68 feet in plan, with an average height of 7.5 feet. Seasonally, the pile supports heavy vegetation, which consists primarily of brush and poison oak.

Current characterization data indicates U-235 enrichment between 2.5% and 12%. The pile appears to be primarily native soil, but also includes some debris. During the characterization, it was determined that there is a significant quantity of debris, concrete, and asphalt approximately three (3) feet below the top surface which hindered characterization efforts below the three (3) foot depth.

Based on information gathered for the preparation of the Remedial Investigation and Feasibility Study Work Plan (RI/FS WP), it is possible that Deul's Mountain is atop an

area that was used for subsurface burial of waste in the past. These burial pits have been identified as an area of concern and will be studied in detail as part of the RI/FS for the FFCF Site.

2.4 Analytical Data

An investigation of Deul's Mountain was conducted in September 2002. US Ecology was tasked to perform a limited characterization of the soil pile. Based on historical information, Deul's Mountain was expected to contain U-238, U-235, and U-234.

Analytical data resulting from routine Westinghouse surveys and the characterization performed by US Ecology are provided in Appendix A. Two discrete techniques, gamma spectroscopy and alpha spectroscopy, generated radiological results. Analytical results from samples collected during the characterization confirmed the presence of U-238, U-235, and U-234. No other isotopes were detected.

2.5 Site Conditions Justifying a Removal Action

Section 300.415(b)(2) of the NCP provides several criteria for evaluating the need for and selection of removal actions under the CERCLA. If conditions satisfy the conditions of one or more of these criteria, the NCP suggests that it is appropriate to consider conducting a removal action.

A removal action at Deul's Mountain is justified given that the conditions at Deul's Mountain, as addressed in this EE/CA, satisfy several of the criteria set forth in the NCP, including the following:

- Impacted soils at Deul's Mountain could present an actual or potential exposure to nearby human populations, animals, or food chain from hazardous substances or pollutants or contaminants
- Impacted soils at Deul's Mountain could present an actual or potential contamination of drinking water supplies or sensitive ecosystems
- The presence of the impacted soils may interfere with conducting a complete and timely RI, thereby posing a long-term threat to human health and the environment
- The excavation and ultimate removal of the soil pile will mitigate potential human health and environmental risks posed by the constituents of concern (COC) present within the soils by reducing the spread of, or direct contact with, COCs present in the soil pile
- The removal of the soil pile in a timely manner will allow for timely implementation of the long-term remedial action for the FFCF Site as set forth in the approved RI/FS WP for the FFCF Site.

2.6 Streamlined Risk Evaluation

The streamlined risk evaluation discussion is presented in three sections: human health risks, ecological risks, and proposed cleanup levels.

2.6.1 Human Health Risks

There is a potential human health risk via direct contact with the radiological constituents present in the soil in Deul's Mountain. Deul's Mountain is located in the general work area of the FFCF Site that is accessed by Westinghouse employees, contractors, subcontractors, security personnel and visitors on routine basis. This soil pile is adjacent to railroad and natural gas pipeline rights-of-way that Westinghouse does not control access. Because this soil pile currently is located within a fenced in area, the potential for such exposure to the public at this time is minimized.

Although the pile is not covered and is exposed to weather, sampling results indicate that radiological contamination is not currently migrating laterally from Deul's Mountain. Westinghouse has monitored for migration in the soil and local groundwater and has determined that there currently is no significant radiological impact.

However, the current position of the pile hinders complete characterization of the burial pits located beneath the soil pile. The existence of these burial pits at the FFCF Site represents a potential human health risk if further characterization is not completed, and in order to perform such characterization in an orderly, complete and effective manner, the soil pile must be removed. Currently there is no practical or feasible approach that would allow identification and characterization of pits with the soil pile in place. The configuration of the pile, does not allow drilling, direct push or manual sampling to any needed depth.

Ecological Risks

Because of its location within the security fence in the general work area of the FFCF Site, potential ecological risks posed by the soil pile are currently minimized. However, materials underlying the soils have not been fully characterized and therefore potential adverse effects to ecological receptors exist. The full effect on ecological receptors, if any, will not be known until the FFCF Site is fully characterized in accordance with the approved RI/FS WP.

2.6.2 Proposed Cleanup Levels

The removal action addresses all above-grade soil that was previously excavated and stockpiled in Deul's Mountain. The basic concept for managing exposures to ionizing radiation and releases of radioactive materials to reduce collective doses as far below

regulatory limits as is reasonably achievable is the driver for the proposed cleanup levels. Reducing the exposure on-site to ALARA includes performing cleanup to limits that are as low as possible through additional planning and management, remediation and the use of additional resources to achieve a collective dose level.

3.0 IDENTIFICATION OF REMOVAL ACTION OBJECTIVES

Removal action objectives are media-specific goals that are established to protect human health and the environment. The specific components of the objectives are defined in Sections 3.1 through 3.5.

Selection of a course of action is accomplished by a series of steps designed to reduce potential alternatives to a group of viable alternatives from which a final alternative may be selected. The development of alternatives includes consideration of the constituents of interest, associated media, potential exposure pathways, and potential receptors. The objectives of the removal action for Deul's Mountain are as follows:

- Eliminate Deul's Mountain as a potential hazard to human health and the environment;
- Minimize potential health hazards to on-site personnel performing the removal action; and
- Remove the interference, Deul's Mountain, to facilitate the site-wide RI.

3.1 Statutory Limits

Authority for responding to releases or threats of releases from an impacted site is addressed in Section 104(a) of CERCLA, 42 U.S.C. § 9604(a). CERCLA, Section 104 and Section 300.415 of the NCP, 40 C.F.R. § 300.415, specifically address non time-critical removal actions. It should be noted that statutory limits under CERCLA and the NCP regarding duration and funding apply only to removal actions paid for with Superfund monies and are not applicable to responses undertaken by private parties.

3.2 Scope and Purpose

The primary purpose of the removal action is to mitigate potential human health and environmental risks posed by the COCs present within the soils in Deul's Mountain. The complementary objective is to facilitate implementation of the RI/FS WP by allowing for adequate characterization of the burial pits located beneath the soil pile.

3.3 Removal Action Schedule

The schedule for removal activities will be determined by Westinghouse with input from the MDNR and U.S. Nuclear Regulatory Commission (NRC). The removal action

schedule will be designed within a time frame that ensures adequate protection of public health and the environment and supports the RI activities under the approved RI/FS WP.

3.4 Planned Remedial Activities

Westinghouse is currently evaluating the FFCF Site pursuant to the procedures and schedules established in the Remedial Investigation/Feasibility Study Work Plan and the Hematite Decommissioning Plan, and future remedial steps for the Site will be implemented through the process identified in those plans. The removal action selected within the scope of this EE/CA will, to the extent practicable under the circumstances, be consistent with any future remedial steps taken at the FFCF Site.

3.5 Applicable or Relevant and Appropriate Requirements

Applicable or Relevant and Appropriate Requirements (ARARs) are Federal and state human health and environmental requirements used to define the appropriate extent of site cleanup, identify sensitive land areas or land uses, develop remedial alternatives, and direct site remediation. CERCLA and the NCP require that remedial actions comply with State ARARs that are more stringent than Federal ARARs, are legally enforceable, and are consistently enforced state-wide. Although not directly applicable to removal actions under CERCLA, the NCP indicates that such actions should attain ARARs to the extent practicable under the circumstances.

The NCP defines two ARAR components: applicable requirements and relevant and appropriate requirements. Applicable requirements are cleanup standards, standards of control, and other substantive requirements, criteria, or limitations promulgated under Federal or state environmental or facility siting laws that specifically address a hazardous substance, pollutant, contaminant, remedial action, or other circumstance found at a CERCLA site. State standards that may be applicable are only those which have been identified by the State in a timely manner, are consistently enforced, and are more stringent than Federal requirements.

Relevant and appropriate requirements are those cleanup standards, standards of control, and other substantive requirements under Federal and state environmental and facility siting laws that, while not "applicable" to a hazardous substance, pollutant, contaminant, or remedial action, address situations sufficiently similar to those encountered at the CERCLA site so that their use is well suited to the particular site. Only those state standards that are identified in a timely manner and are more stringent than Federal requirements may be relevant and appropriate.

Other requirements to be considered (TBC) are Federal and state non-promulgated advisories or guidance that are not legally binding and do not have the status of potential ARARs (i.e., they have not been promulgated in statute or regulations). However, if there are no specific ARARs for a chemical or site condition, or if ARARs are deemed

insufficiently protective, then guidance or advisory criteria should be identified and used to ensure the protection of human health and the environment.

Under the description of ARARs set forth in the U. S. Environmental Protection Agency (EPA) guidance documents, State and Federal ARARs are categorized as follows:

- Chemical-specific governing the extent of site remediation with regard to specific contaminants and pollutants.
- Location-specific governing site features such as wetland, floodplains, and sensitive ecosystems and pertaining to existing natural and manmade site features such as historical or archaeological sites.
- Action-specific pertaining to the proposed site remedies and governing the implementation of the selected site remedy.

As described in the "CERCLA Compliance with other Laws Manual" (EPA/520/G-89/009), several agencies potentially have authority over the cleanup of sites impacted with radioactive materials, including the DOE, NRC, EPA and state agencies. The standards and guidance of the various groups are designed to be consistent with one another and they often overlap in scope and purpose and incorporate the same basic provisions. The regulatory agencies rely on reports and models developed by health physics organizations including the International Commission on Radiological Protection (ICRP), the National Council on Radiation Protection (NCRP), and the committee on the Biological Effects of Ionizing Radiation (BEIR) when radiological contaminants are present. In general, public health standards and guidelines are developed to protect individuals, future generations, and populations from unnecessary exposure to radiation. The basic concept is that all radiation may be harmful to human tissue and therefore exposure must be reduced to As Low As Reasonably Achievable (ALARA).

Chemical-specific ARARs and TBCs for Deul's Mountain are summarized in Table 3-1, and action-specific ARARs and TBCs are summarized in Table 3-2. There are no location-specific ARARs or TBCs associated with the proposed removal action. During the analysis of removal action alternatives in Section 5.0, each alternative will be analyzed to determine its compliance with ARARs.

Table 3-1
Potential Chemical-Specific ARARs/TBCs

Standard, Requirement,	Citation	Description of Requirements	Status	Comment
Criteria, or Limitation				
NRC Radiological Criteria for	10 CFR 20 Subpart	This rule provides consistent standards to NRC licensees	Applicable	These standards apply
License Termination	E, specifically 10	for determining the extent to which lands must be		
	CFR §20.1402	remediated before decommissioning and demolition		
		(D&D) can be considered complete and the license		
		terminated. For unrestricted use, the standard is 25		
		millirem per year (mrem/year) and ALARA.		
Guidelines for Decontamination	FC-83-23	This guideline provides consistent standards to NRC	Applicable	This Guide applies to
of Facilities and Equipment Prior		licensees for decontamination and survey of surfaces or		work at the Hematite
to Release for Unrestricted Use		premises and equipment prior to release for unrestricted		Site and is a license
or Termination of Licenses for		use.		requirement
Byproduct, Source or Special				
Nuclear Material				
Criteria for Release of	Regulatory Guide	This NRC guidance sets default surface radioactivity	TBC	This Guide is a TBC for
Equipment and Materials	1.86	guidelines for release of equipment and non-environmental		equipment used during
		materials (e.g., walls, floors, etc.).		remediation.

Table 3-2 Potential Action-Specific ARARs

Standard, Requirement, Criteria, or LimitationCitationDescription of RequirementsStatusCommentGeneral construction standards – site preparation, demolition, and any land-disturbing activitiesSpecifies the 8-hour time -weighted average concentration for various organic compounds. Training requirements for workers at hazardous waste operations are specified in 20 CFR 1910.120.Relevant and Appropriate Safety Plan (HASP) will contain applicable information.Health and Safety Requirements for Requirements for the protection of the p	
General construction standards – site preparation, demolition, and any land-disturbing activities OSHA - General Industry Standards Specifies the 8-hour time - weighted average concentration for various organic compounds. Training requirements for workers at hazardous waste operations are specified in 20 CFR 1910.120. Health and Safety 29 CFR Part Specifies the 8-hour time - weighted average concentration for various organic compounds. Training requirements for workers at hazardous waste operations are specified in 20 contain applicable information. Applicable Applicable to all alternative definitions.	, -
OSHA - General Industry Standards St	,
Standards various organic compounds. Training requirements for workers at hazardous waste operations are specified in 20 contain applicable information. Health and Safety 29 CFR Part Establishes construction standards Appropriate Safety Plan (HASP) will contain applicable information. Applicable Applicable to all alternative applicable to all alternative applicable to all alternative applicable to all alternative applicable applicable to all alternative applicable to all alternative applicable applicable to all alternative applicable applicable applicable to all alternative applicable applica	
workers at hazardous waste operations are specified in 20 contain applicable information. Health and Safety 29 CFR Part Establishes construction standards Applicable Applicable to all alternative Applicable A	- 1
CFR 1910.120. information. Health and Safety 29 CFR Part Establishes construction standards Applicable Applicable to all alternative Applicable A	Standards
Health and Safety 29 CFR Part Establishes construction standards Applicable Applicable to all alternative	
Requirements for 1926 for the protection of	
	Requirements for
Construction Activities decommissioning/	Construction Activities
Remediation Workers	
Control of Fugitive Dust CSR Title 10 When conducting remedial activities, reasonable Relevant and This rule is considered	Control of Fugitive Dust
precautions have to be taken to prevent particulate matter Appropriate relevant and appropriate to	-
from becoming airborne. No visible particulate may be the extent necessary to	
emitted beyond the boundary of the right of entry or so as to ensure control of fugitive	
cause a nuisance. Dust Emissions.	
Clean Air Act – 20 CFR 61 Emission levels shall not exceed an effective dose Relevant and Emissions levels are limit	Clean Air Act –
National Emission Subpart I equivalent of 10 mrem/year Appropriate via the Hematite Materials	National Emission
Standards for License to 5x10 (-12)	Standards for
Radionuclide Emissions uCi./ml alpha, not to exce	Radionuclide Emissions
From Facilities 150 uCi/qtr	From Facilities
Licensed by the NRC	Licensed by the NRC
and Federal Facilities	•
Not Covered by Subpart	
H T T	• •
General transportation or worker protection standards	General transportation or w
Hazardous Materials 29 CFR 173 The U.S. Department of Transportation (DOT) definition of Applicable Applicable to radioactive	
Transportation Subpart I (1992) "radioactive material" set forth in this Subpart is any materials.	Transportation
Regulations material having a specific activity greater than 0.002	
milliCuries per gram (mCi/g), or 2,000 picocuries per gram	
(pCi/g). This minimum specific activity number includes all	
U, Ra, and Th daughter products. Radionuclides that	
surpass minimum A, quantity (and allowable specific	
activity) requirements are DOT-regulated low specific	
activity materials.	
Hazardous Materials 29 CFR 171 – Part 171 establishes basic definitions and provisions for Applicable Specific Subparts or	Hazardous Materials



Standard, Requirement, Criteria, or Limitation	Citation	Description of Requirements	Status	Comment
Transportation Regulations	179	transporting any hazardous materials, as listed on the HMTA Table in Part 172. Part 172 also contains marking, labeling, placarding, and training requirements. Part 173 contains general requirements for shipments and packaging. Part 172 governs carriage by rail and Part 177 governs carriage by public highway.		Sections of these regulations set out radioactive waste transportation requirements.
OSHA - Record keeping, Reporting, and Related Regulations	29 CFR 1902	Outlines the record keeping and reporting requirements for an employer under the Occupational Safety and Health Administration (OSHA).	Relevant and Appropriate	These requirements apply to all site contractors and subcontractors and must be followed during all site work under 20 CFR 300.150.
Notices, Instructions and Reports to Workers: Inspection and Investigations	10 CFR 19	The regulation apply to all persons who receive, possess, use, or transfer material licensed by the NRC.	Applicable	These requirements apply to all site contractors and subcontractors and must be followed during all site work
Domestic Licensing of Special Nuclear material	10 CFR 70	The regulation establishes procedures and criteria for the issuance of licenses to receive title to, own, acquire, deliver, receive, possess, use, and transfer special nuclear material.	Applicable	Sets out radioactive waste transportation requirements.
Packaging and Transportation of Radioactive Material	10 CFR 71	The regulation establishes requirements for packaging, preparation for shipment, and transportation of licensed material.	Applicable	Sets out radioactive waste transportation requirements.
Physical Protection of Plants and Material	10 CFR 73	Prescribes requirements for the establishment and maintenance of a physical protection system which will have capabilities for the protection of special nuclear material at fixed sites and in transit	Applicable	Sets out radioactive waste transportation requirements, which are incorporated in the Project Transportation Plan.
NRC (Standards for Protection Against Radiation), Transfer for Disposal and Manifests	10 CFR 20.2006	Provides that transfer of radioactive waste intended for land disposal is accompanied by a manifest and be conducted in accordance with specified regulations.	Applicable	Applicable only to commercial disposal.

4.0 IDENTIFICATION OF REMOVAL ACTION ALTERNATIVES

Removal action alternatives should accomplish the identified removal action objectives. Alternatives that meet these objectives will be further evaluated according to the criteria of effectiveness, implementability, and cost. For the purposes of this EE/CA, several removal action alternatives were considered as discussed below.

Initially, an entomb ment on-site alternative was considered. This alternative would allow for the removal of soil from the present location and subsequent storage in a secure, engineered containment cell on-site. However, through the initial steps of the screening process, it became clear that the selection of this alternative would be inconsistent with the Remedial Action Objectives set forth in this EE/CA and with site-wide objectives insofar as: (1) the engineering and design costs alone for this alternative could outstrip the ultimate costs of off-site disposal; (2) significant administrative hurdles (i.e., lengthy government approvals (if even attainable), public opposition, etc.) would need to be overcome; (3) significant post-remedial monitoring and other long-term care requirements would be triggered; and (4) the overall site objective of unrestricted future use would not be met. As a result, this entombment alternative was screened out, and will not be considered further in this EE/CA. The remaining five alternatives are presented in detail below.

4.1 Alternative 1: No Action with Engineering Controls

A "no-action" alternative would allow Deul's Mountain to remain in place. Engineering controls (e.g., restrictive fencing and warning signs) would be included in this Alternative. As discussed below, the "no-action" alternative does not achieve the primary objectives of the removal action insofar as the impacted soils would continue to present a threat to human health and the environment and it does not reduce doses to as far below the regulatory limits as possible. In addition, because Deul's Mountain would remain in place, it would continue to interfere with the identification and characterization of burial pits in the area. This alternative is carried through the analysis for comparative purposes.

4.2 Alternative 2: Relocation and Open Storage On-Site

A relocation and storage for future use alternative allows for the removal of soil from the present location and the storage of the soils in a non-containerized fashion. Under Alternative 2, the removal action would remove impacted soil from the immediate area suspected of containing additional burial pits and would allow for adequate characterization of such burial pits. However, by relocating the soil, the risk exists for homogenization of soil and an increased contaminated soil volume requiring ultimate disposal. In addition, Alternative 2 may not address the potential risks posed by the presence of the impacted soils at the FFCF Site in the longer-term.

4.3 Alternative 3: Relocation and Containerized Storage On-Site

An excavation and on-site storage alternative allows for the removal of soil from the present location and subsequent storage in locked inter-modal containers or other suitable containers on site. Under Alternative 3, the removal action would remove impacted soil from accessible areas sufficient to adequately perform the RI and would allow for adequate characterization of burial pits beneath the soil pile. Impacted soil would be containerized and stored on-site. Post-remedial activities include a site-specific plan to monitor the inter-modal containers for eventual degradation or other breach for release of radioactivity. However, by relocating the soil, the risk exists for homogenization of soil and an increased contaminated soil volume requiring ultimate disposal. In addition, Alternative 3 may not address the potential risks posed by the presence of the impacted soils at the FFCF Site in the longer-term.

4.4 Alternative 4: Excavation and Off-Site Disposal of Soil

An excavation and off-site disposal alternative allows for the removal of soil from the present location and subsequent transport to an off-site, permitted disposal facility (e.g., Envirocare of Utah). Alternative 4 accomplishes the primary removal objective by relocating impacted soil from accessible areas, reducing doses to ALARA and also facilitates implementation of the RI/FS WP by allowing for adequate characterization of the burial pits located beneath the soil pile.

4.5 Alternative 5: Excavation, Consolidation for Volumetric Clearance for Disposal.

An excavation and consolidation for Volumetric Clearance for Disposal (VCD) allows for the removal of soils from the present location, consolidation with additional waste, and subsequent transport to an off-site, licensed disposal facility. VCD is the process of monitoring volumetrically contaminated materials of low activity to certify them as non-radioactive for release to an out-of-state industrial landfill. This process results in significant cost savings over Alternative 4 which disposes the material as low-level radioactive waste regardless of its volumetric activity. Alternative 5 accomplishes the removal objective of relocating impacted soils from inaccessible areas, reduces doses to ALARA and also facilitates implementation of the RI/FS WP by allowing for adequate characterization of the burial pits located beneath the soil pile.

5.0 ANALYSIS OF REMOVAL ACTION ALTERNATIVES

The primary purpose of the removal action is to mitigate potential human health and environmental risks posed by the COCs present to ALARA within the soils in Deul's Mountain. The complementary objective is to facilitate implementation of the RI/FS WP by allowing for adequate characterization of the burial pits located beneath the soil pile.

The removal alternatives were evaluated using EPA's "Guidance on Conducting Non-Time-Critical Removal Actions under CERCLA" (August 1993) (the EE/CA Guidance).

This section evaluates the five removal alternatives identified in Section 4.0 based on their effectiveness, implementability, and cost in relation to site-specific conditions, consistent with the NCP and the EE/CA Guidance. The removal alternatives are evaluated to ensure that they effectively protect human health and the environment and satisfy the defined removal action objectives.

5.1 Effectiveness

The effectiveness of an alternative refers to its ability to meet the objective within the scope of the removal action. The effectiveness and reliability of the removal alternatives are evaluated with respect to the COCs and conditions at the site. Consideration is given to the protection each alternative affords to public health (Section 5.1.1); site workers (Section 5.1.1.2); the environment (Section 5.1.1.3, including compliance with applicable ARARs) and the useful life of the processes within a removal alternative (i.e., the length of time that it performs its intended function).

5.1.1 Overall Protection of Human Health and the Environment

5.1.1.1 Protective of Public Health and Community

This criterion addresses whether an alternative provides adequate protection of public health and the environment and describes how risks are eliminated, reduced, or controlled through treatment, engineering controls, or institutional controls.

Under Alternative 1, the risk of potential human exposure from contaminants at the site is not reduced to ALARA or eliminated. Although engineering and institutional controls would act to limit potential exposure to the COCs in the materials in Deul's Mountain, such controls would not facilitate the characterization of the ground beneath Deul's Mountain. Accordingly, Alternative 1 will not facilitate the identification and potentially the elimination of a source for potential human exposure from contaminants other than the currently known radiological contaminants in Deul's Mountain. Site-specific contamination would remain uncontrolled and, therefore, have the potential to spread to surrounding soils and water pathways allowing for potential human exposure.

Under Alternative 2, the risk of potential human exposure from contaminants at the site is reduced but not eliminated. Relocation of Deul's Mountain to a new location allows for the investigation of burial pits beneath the soil pile. Exposure to site workers during the handling of impacted materials would have to be monitored and proper personnel protective measures put in place. Even with intensive environmental and personnel monitoring, relocating the soil introduces some short-term risks associated with worker exposure and the potential for increased airborne dust releases. Under Alternative 2, these short-term impacts are not offset by any long-term decrease in human health or

environmental risk. The long-term risk to human health presented by the soil remains identical to Alternative 1.

Under Alternative 3, relocating Deul's Mountain to a new location allows for the investigation of burial pits beneath the soil pile. Impacted soil and waste materials would be removed from their present location, packaged in containers according to current industry standards, moved and stored in a secure on-site location. Exposure to site workers during the handling and repackaging of impacted materials would have to be monitored and proper personnel protective measures put in place. Because of additional handling and sorting to fill containers, the short-term risks for Alternative 3 may be slightly greater than those of Alternative 2. The higher short-term risks would be somewhat offset by the reduced longer-term risk due to the containerization of the impacted materials. Exposure to site workers near the storage containers would have to be monitored and the containers themselves would have to be monitored and inspected on a periodic basis for evidence of failure. Eventually, however, such materials would need to be placed in a permanent disposal facility or location.

Under Alternative 4, relocating Deul's Mountain to a new location and disposal off-site at an approved facility allows for the investigation of possible burial pits. Potential short-term risks would be similar to Alternative 3 with the addition of risks associated with the long-distance transport of these materials to the disposal facility. Public exposure would be minimized during transport by inspecting the vehicles before and after use, decontamination of exterior waste packages when needed, using only covered waste packages, observing safety protocols, and by following pre-designated routes. Transportation risks increase with distance and volume, although the potential for any spillage and resultant public exposure would be very low. The transport of wastes to an off-site disposal facility would comply with DOT regulations and directives as well as other applicable Federal regulations.

Potential risks associated with Alternative 5 would be similar to those described under Alternative 4. The exception would be the shorter distance required to transport the materials for disposal to Tennessee instead of Utah.

5.1.1.2 Protective of Workers during Implementation

This criterion addresses whether an alternative provides adequate protection of site workers, and describes how potential occupational doses and injuries are eliminated, reduced, or controlled through treatment, engineering controls, or institutional controls.

Under Alternative 1, no removal action would be taken; however, necessary maintenance and surveillance activities would require workers to work in proximity to Deul's Mountain on a routine basis. Appropriate personnel protection equipment (PPE) would be required and proper radiological controls and procedures would have to be implemented for all on-site work at and within the restrictive fence line.

Under Alternative 2, potential occupational doses to workers involved in removal activities would be due to direct exposure, inhalation, or ingestion of contaminants. Worker exposure and injuries would be reduced through implementation of a comprehensive health and safety program and radiological protection program including the proper use of safety protocols, PPE, and restrictions on access to impacted areas. In addition, machinery and equipment would be inspected after use, surveyed for contamination, and decontaminated if necessary. No occupational or safety barriers that would prevent the implementation of these activities are foreseen. In addition, workers would be provided adequate protection by implementing state and Federal health and safety requirements.

Under Alternative 3, potential occupational doses and injuries to workers involved in removal activities would be very similar to Alternative 2 with the possibility of a temporary increase in generation of fugitive dust containing site COCs resulting from filling containers. Appropriate measures and engineering controls would be used to mitigate the potential for an increase in risk to those in close proximity removal activities as they occur.

Under Alternative 4, potential occupational doses and injuries to workers involved in response activities would be very similar to Alternative 3 with the addition of a long transport route to the disposal facility. Worker exposure would be minimized during transport by inspecting the vehicle(s) before and after use, decontamination of the exterior of waste packages when needed, covering the transported waste, observing safety protocols, and by following pre-designated routes. Transportation risks increase with distance and volume, although the potential for any spillage and resultant worker exposure would be very low. The transport of wastes to an off-site disposal facility would comply with DOT regulations and directives as well as other applicable Federal regulations.

Alternative 5 would be similar to Alternative 3 and Alternative 4. The exception would be the reduced transportation risk associated with shorter transportation distances.

5.1.1.3 Protective of the Environment

This criterion addresses whether an alternative provides adequate protection of the environment. Exposure methods of most importance are direct exposure to the environment local to the site and also spread of contamination off-site.

Under Alternative 1, no removal action would be taken and hence no short-term adverse impacts would be created. However, Deul's Mountain would remain in place and burial pits beneath the soil pile, which may represent sources of soil and groundwater impacts would not be adequately investigated.

Under Alternatives 2, 3, 4 and 5, some short-term environmental damage could be caused by equipment used to perform removal activities. Emissions from cleanup activities

should be well within EPA guidelines regarding ambient air pollution concentrations and are expected to have a negligible effect on the air quality at the Site. Physical damage caused by removal activities would be minimal due to the fact that all remedial activities would be confined to the fenced area. Under Alternatives 3, 4 and 5, long-term environmental damage caused by either the spread of constituents associated with Deul's Mountain or by not identifying and addressing possible burial pits will be mitigated by the removal of Deul's Mountain waste material.

5.1.2 Compliance with ARARs

Alternative 1: Alternative 1 does not comply with chemical-specific or action-specific ARARs given that Alternative 1 does not eliminate the possibility of exposure to radiological impacts and reduce exposure to ALARA in and from the soil pile or allow for adequate characterization of burial pits located beneath the soil pile. There are no location-specific ARARs.

Alternative 2: Alternative 2 does not comply with chemical-specific or action-specific ARARs given that Alternative 2 does not eliminate the possibility of exposure to radiological impacts in and from the soil pile or reduce dose to ALARA. There are no location-specific ARARs.

Alternative 3: Alternative 3 complies with chemical-specific and action-specific ARARs. In addition, it could potentially trigger additional ARARs once the inter-modals are stored on Westinghouse property. There are no location-specific ARARs.

Alternative 4: Alternative 4 complies with chemical-specific and action-specific ARARs. Because it offers a long-term, permanent, off-site disposal solution, no additional ARARs will be triggered. There are no location-specific ARARs.

Alternative 5: Alternative 5 complies with chemical-specific and action-specific ARARs. Because it offers a long-term, permanent, off-site disposal solution, no additional ARARs will be triggered. There are no location-specific ARARs

5.1.3 Useful Life

Under Alternative 1, no up-front construction or remediation activities would be performed, and therefore, would not cause additional short-term risk. However, under Alternative 1, long-term effectiveness is significantly reduced by risks posed from the potential of waste remaining in place to spread contamination.

Under Alternative 2, long-term effectiveness is affected due to a reduced but present residual risk of material remaining on site in open outside storage. There would be a reduction of mobility due to contamination controls and monitoring that would be in place. The short-term effectiveness is reduced due to the potential for worker exposure

during the remedial action. However, this potential exposure is outweighed by the risk of not identifying burial pits beneath Deul's Mountain.

Under Alternatives 2, 3, 4 and 5, short-term effectiveness may be reduced by removal activities. However, under Alternatives 3, 4 and 5 the removal of impacted material would eliminate the potential spread of contamination throughout future years, manage doses to ALARA and allow for a high degree of long-term effectiveness.

In addition, given the fact that the soils in Deul's Mountain will need to be disposed of off-site in order to ensure the doses from the COCs are reduced to ALARA, the useful life of Alternatives 2 and 3 are significantly reduced. In essence, Alternative 2, and 3 simply postpone the ultimate response to address the environmental risks posed by Deul's Mountain, while adding short-term risks and costs associated with relocation/storage of the soil pile on-site.

5.2 Implementability

The implementability criterion encompasses both the technical and administrative feasibility and the availability of required services and materials.

5.2.1 Technical Feasibility

Three important aspects of technical feasibility are: (1) availability and reliability of the processes within a removal alternative; (2) construction and implementation timeframe; and (3) environmental conditions with respect to all relevant phases of the alternative. Implementation time and the period for beneficial results to be realized are critical factors in protecting public health and the environment.

Under Alternatives 1, 2 and 3, the long-term surveillance and/or final disposal of waste material containing long-lived radionuclides (i.e., uranium) may reduce the technical feasibility of these alternatives. Monitoring the effectiveness of these alternatives may be a long-term necessity in order to sustain technical feasibility.

Under Alternatives 1 and 2, maintenance and replacement of postings and fence repair are technically feasible. The timeframe to undertake Alternative 1 will not be an issue. Environmental conditions will play a large role in making Alternatives 1 and 2 not feasible in the long-term due to the potential spread of contamination over time. Severe weather systems would be an example of environmental conditions that could cause the spread of contamination.

Under Alternatives 2, 3, 4 and 5, removal of Deul's Mountain is technically feasible in terms of availability, proven reliability, and timeframe for receipt of necessary equipment and technologies. Potential methods for removal of waste do not require unacceptable levels of uncertainty. These methods have been proven in the industry to be reliable, and technical problems potentially leading to scheduling delays are not anticipated.

Westinghouse Westinghouse

EE/CA for Response Action at Deul's Mountain

Appropriately trained personnel, waste documentation, and tracking systems are also readily available. Environmental conditions may be avoided during remedial processes by working during certain times of the year and environmental conditions.

Under Alternative 3, on-site storage of impacted materials in containers can be accomplished using proper storage containers, engineering and design controls, which will prevent leakage and have sufficient density and thickness to shield gamma exposure, as necessary. Proper storage of material without affecting planned near-term investigation and remediation may complicate technical feasibility due to space limitations and the possibility of cell or containers to degrade over time.

Under Alternatives 4 and 5, commercial disposal of the excavated materials is technically feasible and would reduce potential contaminant mobility. Commercial disposal of the types of wastes that would be encountered is currently available. Appropriate commercial waste disposal facilities are required to maintain environmental monitoring and occupational health programs.

5.2.2 Administrative Feasibility

Administrative feasibility considerations include the potential of a proposed action to achieve response objectives and effectiveness. The administrative feasibility factor evaluates those activities needed to coordinate with other offices, agencies, and the public. These concerns include approval from government agencies and interagency cooperation, transportation factors, procurement of off–site permits, approval for on-site storage and disposal facilities, compliance with policies and requirements, and public acceptance.

Under Alternatives 1, 2, 3, 4, and 5 in order to facilitate overall administrative feasibility, communications with other government agencies and with the public regarding FFCF Site plans and activities will be performed under the direction of Westinghouse.

Under Alternative 1, administrative feasibility may be complicated by concerns of government officials and the public concerning groundwater impacts and the need to perform the site-wide RI.

Under Alternative 2, administrative feasibility may be complicated given that this Alternative requires that impacted material be moved in an uncontrollable fashion. Furthermore, under Alternative 3, administrative feasibility may be complicated by concerns for the long-term integrity of the storage containers and the need to shuffle a large quantity of containers to allow the remedial investigation and subsequent remediation. As the remediation progresses, there may not be sufficient space to store containers.

Under Alternative 4, the transport of wastes to an off-site disposal facility would comply with DOT regulations and directives as well as other applicable Federal regulations. This

would include compliance by subcontractors involved in the remediation and transportation of the waste. The schedule should not be affected if proper planning is performed prior to removal and transportation activities. The activities involved with Alternatives 2 and 4 are common activities and should not provide unforeseen and time-consuming circumstances.

Under Alternative 5, in order to facilitate overall administrative feasibility, communications with other government agencies and with the public regarding Site plans and activities will be performed under the direction of Westinghouse. The transport of wastes to an off-site disposal facility would comply with DOT regulations and directives as well as other applicable Federal regulations. This would include compliance by subcontractors involved in the removal and transportation of the waste.

The removal schedule should not be affected if proper upfront planning is performed. The activities involved with Alternative 5 are common activities and should not provide unforeseen and time-consuming circumstances.

5.3 Cost

The purpose of the EE/CA cost estimate is to compare the relative costs for the various Removal Action Alternatives. Relative capital costs and operational and maintenance costs are used rather than detailed estimates. The cost analysis is based on engineering judgment and each process is evaluated on its cost relative to the other alternative. The basis of this EE/CA cost estimate includes the conservative assumption that there are 1,100 cubic yards of soil to be addressed. Alternative 1 was not estimated for cost. A summary of the costs associated with Alternatives 2, 3, 4 and 5 is presented in Table 5-1.

5.4 Summary of Removal Action Alternatives

This section summarizes the results of the analysis of all Removal Action Alternatives. Each Removal Action Alternative is evaluated for its effectiveness, implementability, and relevant cost.

5.4.1 Alternative 1 in Summary

- Low rank in effectiveness with respect to long-term human and environmental protection.
- Low rank in implementability with respect to concerns of the public concerning groundwater contamination and the need to perform the site-wide RI.
- Low rank in ensuring exposure to ionizing radiation and release of radioactive materials is managed to reduce collective doses ALARA.
- High rank for cost in that the cost is the least expensive alternative at this present time. However, future disposal costs would be incurred thereby eliminating the potential short-term cost savings associated with this Alternative.



Table 5-1: Cost Analysis of Alternatives

Task	Description	Alternative 2 Relocation and Open Storage Onsite	Alternative 3 Relocation and Containerized Storage Onsite	Alternative 4 Excavation and Off-site Disposal	Alternative 5 Consolidation for Volumetric Clearance for Disposal
1	Mobilization	\$10,500	\$10,500	\$10,500	\$10,500
2	Site Preparation	\$1,500	\$1,500	\$1,500	\$1,500
3	Excavation, Waste Profiling, and Remediation Surveys	\$125,500	\$125,500	\$125,500	\$125,500
4	Sampling (including Independent Verification)	\$0	\$0	\$20,000	\$20,000
5	Establishment of Waste Packaging Area, including Barriers and Required Posting	\$5,000	\$5,000	\$5,000	\$5,000
6	Site Surveillance	\$80,000	\$80,000	\$8,000	\$8,000
7	Waste Containers and Transportation	\$103,840	\$507,040	\$94,400	\$18,500
8	Waste Disposal	Included in Task 9	Included in Task 9	\$950,400	\$303,750
9	Storage on Site, delayed disposal	\$1,045,440	\$1,045,440	\$0	\$0
10	Final Report/Waste Tracking	\$25,000	\$25,000	\$25,000	\$25,000
11	Project Management	\$20,000	\$20,000	\$10,000	\$10,000
	ESTIMATED COST	\$1,416,780	\$1,819,980	\$1,250,300	\$527,750

Task #7 Alternative 2 includes 3-month container rental plus transportation for disposal escalated by 10% Alternative 3 includes 7-year container rental plus transportation for disposal escalated by 10%

Alternative 3 includes 7-year container rental plus transportation for disposar escalated by Alternative 4 includes 3-month container rental plus current cost of transportation

Task #8 1100 Cubic yards at \$32.00/ft3 for Waste Disposal
Task #9 Delayed disposal results in a 10% disposal cost increase

On-site storage assumes 62 containers leased at \$150.00 per month for 7 years

Super sacks, B-12 and B-25 determined not to be cost effective

Disposal at alternate disposal site (VCD) assumed after 7 years at \$25

5.4.2 Alternative 2 in Summary

- Low rank in effectiveness with respect to long-term human and environmental protection. This Alternative allows the impacted soils for Deul's Mountain to remain on-site in an uncontained fashion.
- Low rank in implementability with respect to concerns of the public concerning groundwater contamination.
- Low rank in ensuring exposure to ionizing radiation and release of radioactive materials is managed to reduce collective doses ALARA.
- Medium rank for cost in that the cost is the second most expensive alternative at this present time. Future disposal costs would be incurred, thereby eliminating any cost savings associated with current non-disposal.

5.4.3 Alternative 3 in Summary

- High rank in effectiveness with respect to long-term human and environmental protection.
- High rank in ensuring exposure to ionizing radiation and release of radioactive materials is managed to reduce collective doses ALARA.
- Medium rank in implementability with respect to proper storage of material without affecting planned near-term investigation and remediation. Implementability may be affected due to space limitations and the possibility of containers to degrade over time.
- Low rank in cost due to the cost of container rental and the increased future unknown disposal cost that will be incurred, thereby eliminating any cost savings associated with current non-disposal.

5.4.4 Alternative 4 in Summary

- High rank in effectiveness with respect to long-term human and environmental protection.
- High rank in ensuring exposure to ionizing radiation and release of radioactive materials is managed to reduce collective doses ALARA.
- High rank in implementability with respect to technical and administrative feasibility.
- Medium rank for cost in that the cost is the second least expensive of the viable Alternatives.

5.4.6 Alternative 5 in Summary

• High rank in effectiveness with respect to long-term human and environmental protection.

- High rank in ensuring exposure to ionizing radiation and release of radioactive materials is managed to reduce collective doses ALARA.
- High rank in implementability with respect to technical and administrative feasibility.
- High rank for cost in that the cost is the least expensive of the viable Alternatives.

6.0 COMPARATIVE ANALYSIS OF REMOVAL ACTION ALTERNATIVES

Alternatives were independently evaluated in the preceding sections for effectiveness, implementability, and cost. A summary of alternative analyses is provided in Table 6.1. In this section, Alternatives 1, 2, 3, and 4 and 5 will be comparatively analyzed for effectiveness, implementability and cost.

With respect to long-term effectiveness, Alternatives 4 and 5 are the most effective alternative regarding long-term human health implications. This effectiveness results from the removal of impacted material and facilitation of the site-wide Remedial Investigation under Alternative 4 and 5.

Alternatives 2 and 3 are also effective alternatives regarding short-term human health implications. However, waste remaining on-site, the administrative controls and human health implications with surveillance and cell and container maintenance adversely affect the long-term effectiveness of these alternatives. The positive long-term results of Alternative 3 far outweigh positive short-term results of Alternative 1 and 2, regarding effectiveness.

With respect to implementability, Alternatives 1, 2, 3, 4 and 5 are technically feasible. The four alternatives are administratively feasible by following proper protocols and applicable guidance. However, Alternatives 1, 2 and 3 are likely to be met with resistance from government agencies and/or the public given that these alternatives allow material from Deul's Mountain to remain on-site.

With respect to relative total costs, Alternative 5 is the lowest cost alternative other than the "no-action" alternative, and is estimated to cost \$722,550 less than the next lowest alternative, Alternative 4. These costs are estimates and can be affected by unforeseen events and issues. Alternative 3 was estimated out to 7 years due to the anticipated duration of the project and schedule limitations that would require eventual disposal, at higher disposal rates, to complete the project.

Additionally Alternative 5 will reduce the cost of off-site disposal given that the long-term cost of off-site disposal will increase and by disposing of the soil with other impacted materials now (e.g., equipment), a cost benefit can be realized by taking advantage of volumetric disposal rates.

Table 6.1 Evaluation Comparison

Alternative	Description	Effectiveness Ranking	Implementability Ranking	Cost Ranking	Post-Action Monitoring Required	Current Off-site Disposal	Probability of Public and Regulatory Acceptance
1	No Action with	Low	Low	High	Yes	No	Low
	Engineering Controls						
2	Relocation and Open	Low	Low	Low	Yes	No	Low
	Storage On-Site						
3	Relocation and Containerized Storage On-Site	High	Medium	Low	Yes	No	Medium
4	Excavation and Off- Site Disposal of Soil	High	High	Medium	No	Yes	High
5	Excavation, Consolidation VCD	High	High	High	No	Yes	High



7.0 RECOMMENDED REMOVAL ACTION ALTERNATIVE

Based on the results of the comparison of remaining alternatives in Section 6.0, the recommended Removal Action Alternative is Alternative 5.

8.0 EVALUATION OF POST-REMOVAL SITE CONTROL ACTIVITIES NECESSARY TO SUSTAIN THE INTEGRITY OF THE REMOVAL ACTION

Post-removal Site control activities are not necessary to sustain the integrity of the preferred removal action. The removal action only includes above grade soil that was previously excavated. The conduct of a Final Status Survey (FSS) in compliance with guidance from Multi-Agency Radiation Survey and Site Investigation Manual (MARSSIM) is not a component of the removal action. A site wide FSS will be performed, at the appropriate time, to allow for release of the Site for unrestricted use.

9.0 REFERENCES

Comprehensive Environmental Response, Compensation and Liability Act (CERCLA), 42 U.S.C. § 9601 *et seq.*

EPA 1993, "Guidance on Conducting Non-Time-Critical Removal Actions Under CERCLA," EPA 520-R-93-057, August 1993.

National Contingency Plan (NCP), 40 C.F.R. § 300.1 et seq.

10 CFR 20.1402, Radiological Criteria for Unrestricted Use

DO-04-005, Rev. 0 29 August 31, 2004



Appendix A Westinghouse Electric Co. Analytical Data

Report of Analysis

7/26/02 8:24:27AM



RT N. HORTON

Sample ID: D-HILL 1

L18538

Collect Start: 06/14/02 10:30

Station: Description:

WESTINGHOUSE

Collect Stop: Received: 06/17/02

4S Number: L18538-1

AB018-3EREGXXPOMO

Matrix: Soil (S)

TI Number: 7	5256									Volu	me:				
adionuclide	SOP#	Activity Conc	Uncertainty (2 Sigma)	MDC	Units	Aliquot Volume	Aliquot Units	Reference Date	ce Count Count Time Fla				Flag Values		
33/234 (AS)	062-110	2.70E+001	3.20E+000		pCi/g				06/24/02			+			
35 (AS)	062-110	1.11E+000	2.30E-001		pCi/g			***************************************	06/24/02		<u>'</u>	+		<u>'</u>	
38 (AS)	062-110	4.54E+000	6.30E-001		pCi/g				06/24/02			+		1.	

nments:

Sample ID: D-HILL 1

L18538

Collect Start: 06/14/02 10:30

Station:

WESTINGHOUSE

Collect Stop:

Description: 4S Number: L18538-2

TI Number: 71071

Received: 06/17/02

AB018-3EREGXXPOMO

Matrix: Miscellaneous (Z)

Volume:

III (dilliool.)	1071												- 1
adionuclide	SOP#	Activity Conc	Uncertainty (2 Sigma)	MDC	Units	Aliquot Volume	Aliquot Units	Reference Date	Count Date	Count Time	Count Time Units	Flag Values	
CONTRACT		-Complete	d .										\neg

nments: TCLP VOC, SVOC, METALS

Sample ID: D-HILL 2

L18538

Collect Start: 06/14/02 10:30

Station: Description:

WESTINGHOUSE

Collect Stop:

AS Number: L18538-3

AB018-3EREGXXPOMO

Received: 06/17/02 Matrix: Soil (S)

TI Number:	75257									Volu	me:			
ıdionuclide	SOP#	Activity Conc	Uncertainty (2 Sigma)	MDC	Units	Aliquot Volume	Aliquot Units	Reference Date	Count Date	Count Time	Time Flag Values Units			
33/234 (AS)	062-110	1.19E+001	1.60E+000		pCi/g				06/24/02			+		
35 (AS)	062-110	4.46E-001	1.42E-001		pCi/g				06/24/02			+		
38 (AS)	062-110	1.53E+000	2.90E-001		pCi/g				06/24/02			+		i

nments:

! Values

Activity concentration exceeds MDC and 3 sigma and peak identified(gamma only)

Peak not identified, but forced activity concentration exceeds MDC and 3 sigma Activity concentration exceeds customer reporting value

MDC exceeds customer technical specification = Peak not identified in gamma spectrum =

Peak identified in gamma spectrum

Results are reported on an as received basis unless otherwise noted

1 of 2

ded text indicates reportable value.

Report of Analysis

7/26/02 9:00:52AM



Sample ID: D-HILL 2

L18538

Collect Start: 06/14/02 10:30

Station:

Description:

WESTINGHOUSE

Collect Stop: Received: 06/17/02

MS Number: L18538-4

AB018-3EREGXXPOMO

Matrix: Miscellaneous (Z)

Volume:

TI Number: 71072

adionuclide	SOP#	Activity Conc	Uncertainty (2 Sigma)	MDC	Units	Aliquot Volume	Aliquot Units	Reference Date	Count Date	Count Time	Count Time Units	Flag Values
3CONTRACT		-Complete	1 "									

nments: TCLP VOC, SVOC, METALS

g Values

Activity concentration exceeds MDC and 3 sigma and peak identified(gamma only)

Peak not identified, but forced activity concentration exceeds MDC and 3 sigma Activity concentration exceeds customer reporting value

MDC exceeds customer technical specification

Peak not identified in gamma spectrum

Peak identified in gamma spectrum

**** Results are reported on an as received basis unless otherwise noted

BROWN ENGINEERING, INC.

A Tots*yns 7IchnalD*s Comp ny 2505 Quality Lane Knoxville, TN 37931-3133

WESTINGHOUSE NUCLEAR FUEL 3300 STATE ROAD P FESTUS MO 63028 Attn: CORT N. HORTON

Report of Analysis/Certificate of Conformance

8/26/02

LIMS #: L18884

Project ID#: AB018-3EREGXXPOMO

Received: 8/8/02 Delivery Date: 9/7/02

P.O. #: SA20000050 L/I 1

Release #:

This is to certify that Teledyne Brown Engineering - Environmental Services located at 2508 Quality Lane, Knoxville, Tennessee, 37931, has analyzed, tested and documented samples as specified in the applicable purchase order.

This also certifies that requirements of applicable codes, standards and specifications have been fully met and that any quality assurance documentation which verified conformance to the purchase order is on file and may be examined upon request.

I hereby certify that the above statements are true and correct.

Keith Jeter

Operations Manager

Cross Reference Table

Client ID

Laboratory ID

TT#

REPORT OF AHAIYSIS

2:28:08PM 8/26/02



CORT N. HORTON

Sample ID: DH-3

L18884

Collect Start: 08/06/02 0:00

Station:

WESTINGHOUSE

Collect Stop:

Description:

LIMS Number: 1.18884-1

AB018-3EREGXXPOMO

Received: 08/08/02 Matrix: Soil (S)

Volume:

TI Number: 1	77138									Volu	me:		
Radionuclide	SOP#	Activity Conc	Uncertainty (2 Sigma)	MDC	Units	Aliquot Volume	Aliquot Units	Reference Date	Count Date	Count Time	Time Units	Fla	g Values
GR-A	032-15	1.93E+001	5.86E+000		pCi/g Dry	1.000	G		08/24/02	50	M	+	
GR-B	032-15	4.92E+001	3.38E+000		pCi/g Dry	1.000	G		08/24/02	50	M	+	

Comments:

Sample ID: DH-4

L18884

Collect Start: 08/06/02 0:00

Station: Description:

WESTINGHOUSE

Collect Stop:

LIMS Number: L18884-2

AB018-3EREGXXPOMO

Received: 08/08/02 Matrix: Soil (S)

TI Number: 77139 Volume:													
Radionuclide	SOP#	Activity Cone	Uncertainty (2 Sigma)	MDC	Units	Aliquot Volume	Aliquot Units	Reference Date	Count Date	Count Time	Count Time Units	Fla	g Values
GR-A	032-15	<		3.87E+000	pCi/g Dry	1.000	G	-	08/24/02	50	M		
GR-B	032-15	9.11E+000	1.75E+000		pCi/g Dry	1.000	G		08/24/02	50	M	+	İ

Comments:

Flag Values

Activity concentration exceeds MDC and 3 sigma and peak identified(gamma only) =

Peak not identified, but forced activity concentration exceeds MDC and 3 sigma Activity concentration exceeds customer reporting value High =

MDC exceeds customer technical specification Spec = Peak not identified in gamma spectrum No

Yes Peak identified in gamma spectrum

Bolded text indicates reportable value.

**** Results are reported on an as received basis unless otherwise noted

1 of 1

PACKING LIST

Ship To:	Teledyne Rad Analyt 2508 Quality Lane Knoxville, TN 37931-:		E-200		
Date:	8/6/02				
Send Report	t To: Westinghouse Electric	Co.			
Address:	3300 State Road P, P.O. Box		1985 FM . St		
City,State:	Festus, Mo.		63028		
Attention:	Bill Sharkey		937-4691 x 399		
Purchase Or	rder No.	FAX Number (314)	937-7955		
Turn around	d Time: (X)28 Day ()	14 Day () 5 Day			
Sample ID	Collection Date	_ ` ^	Collection Date		
DH-	3 8/10/02	<u>77138</u>			
DH-4	4 816107	<u> 17139</u>			
			T		
	9-10-1-1-1-1-1-1-1-1-1-1-1-1-1-1-1-1-1-1				
	yze samples for the following;	(Check by use of an "X" for your re	equirements)		
	ater Samples For:	~~			
(X) Gross	Alpha & Gross Beta (X) Filto)Kin g			
	ì O	(Norma	· (n		
Additional A	lawe				
Additional A			als per Con		
- Itosto	n Jelephone Conc	Krsation 8/27/02			
			01/1		
X/c/-		A Minula	Lite		
~/ 8/0 =	<u>ک</u> ح	Authorized Signature			
VJ	h. c) orden				

WESTINGHOUSE NUCLEAR FUEL 3300 STATE ROAD P FESTUS MO 63028 Atta; CORT N. HORTON

Report of Analysis/Certificate of Conformance

9/3/02

LIMS #: L19015

Project ID#: AB018-3EREGXXPOMO

Received: 8/27/02

Delivery Date: 9/3/02

P.O. #: SA20000050 L/I 1

Release #:

This is to certify that Teledyne Brown Engineering - Environmental Services located at 2508 Quality Lane, Knoxville, Tennessee, 37931, has analyzed, tested and documented samples as specified in the applicable purchase order.

This also certifies that requirements of applicable codes, standards and specifications have been fully met and that any quality assurance documentation which verified conformance to the purchase order is on file and may be examined upon request.

I hereby certify that the above statements are true and correct.

Keith Jeter ()

Operations Manager

Cross Reference Table

Client ID	Laboratory ID	T T#
DH-3	L19015-1	77827
DH-4	L19015-2	77828

Report of Analysis

9/3/02 4:51:44PM



CORT N. HORTON

Sample ID: DH-1

L19015

Collect Stop:

Station: Description:

WESTINGHOUSE

Received: 08/27/02 Matrix: Soil (S)

Collect Start: 08/06/02 0:00

LIMS Number: L19015-1

AB018-3EREGXXPOMO

Volume

TI Number:	77827									A OII				
Radionuclide	SOP #	Activity Cone	Uncertainty (2 Sigma)	MDC	Units	Aliquot Volume	Aliquot Units	Reference Date	Count Date	Count Time	Time Units	Fla	g Values	-
U-233/234 (AS)	062-110	8.45E+000	1.38E+000		pCi/g				08/30/02	60,007	seconds	+		
U-235 (AS)	062-110	2.80E-001	1.66E-001		pCi/g				08/30/02	60,007	seconds	+		
U-238 (AS)	1062-110	1.99E+000	4.73E-00!		pCi/g				08/30/02	60,007	seconds	+		

Comments:

Sample ID: DH-4

L19015

Collect Start: 08/06/02 0:00

WESTINGHOUSE

Collect Stop:

Description: LIMS Number: L19015-2

Station:

AB018-3EREGXXPOMO

Received: 08/27/02 Matrix: Soil (S)

Volume

TI Number:	77828									4 010	une.	
Radionuclide	SOP#	Activity Cone	Uncertainty (2 Sigma)	MDC	Units	Aliquot Volume	Aliquot Units	Reference Date	Count Date	Count Time	Time Units	Flag Values
U-233/234 (AS)	062-110	9.20E+000	1.51E+000		pCi/g				08/30/02	60,001	seconds	+
U-235 (AS)	062-110	3.78E-001	2.12E-001		pCi/g				08/30/02	60,001	seconds	+
U-238 (AS)	062-110	1.75E+000	4.43E-001		pCi/g	1			08/30/02	60,001	seconds	+

Comments:

Flag Values

Spec

Activity concentration exceeds MDC and 3 sigma and peak identified(gamma only)

Peak not identified, but forced activity concentration exceeds MDC and 3 sigma Activity concentration exceeds customer reporting value High MDC exceeds customer technical specification

Peak not identified in gamma spectrum No Yes Peak identified in gamma spectrum

**** Results are reported on an as received basis unless otherwise noted

A Teledyne Technologies Company 2508 Quality Lane Knoxville, TN 37931-3133

WESTINGHOUSE NUCLEAR FUEL 3300 STATE ROAD P FESTUS MO 63028 Attn: CORT N. HORTON

Report of Analysis/Certificate of Conformance

9/27/02

LIMS #: L19061

Project ID#: AB018-3EREGXXPOMO

Received: 8/30/02

Delivery Date: 9/27/02

P.O. #: SA20000050 L/I 1

Release #:

SDG #: N/A

This is to certify that Teledyne Brown Engineering - Environmental Services located at 2508 Quality Lane, Knoxville, Tennessee, 37931, has analyzed, tested and documented samples as specified in the applicable purchase order.

This also certifies that requirements of applicable codes, standards and specifications have been fully met and that any quality assurance documentation which verified conformance to the purchase order is on file and may be examined upon request.

I hereby certify that the above statements are true and correct.

Keith Jeter

Operations Manager

Cross Reference Table

Client ID	Laboratory ID	TI#
DH5	L19061-1	78015
DH6	L19061-2	78016
7: DH7	L19061-3	78017
, DH8	L19061-4	78018

Report of Analysis

9/27/02 1:15:18PM



CORT N. HORTON

Sample ID: DH5

Station:

Description: LIMS Number: L19061-1

(78015)

L19061

WESTINGHOUSE

AB018-3EREGXXPOMO

Collect Start: 08/28/02 0:00

Collect Stop:

Received: 08/30/02 Matrix: Soil (S)

% Moisture:		(70015)								Volu	ıme:			
Radionuclide	SOP#	Activity Conc	Uncertainty (2 Sigma)	MDC	Units	Aliquot Volume	Aliquot Units	Reference Date	Count Date	Count Time	Time Units	Fia	g Values	s
GR-A	032-15	3.70E+001	8.08E+000	·····	pCi/g Dry	1.000	G		09/10/02	50	M	+		
GR-B	032-15	6.57E+001	3.94E+000	······································	pCi/g Dry	1.000	G		09/10/02	50	M	+		
U-233/234 (AS)	062-110	5.52E+001	4.62E+000		pCi/g Dry	0.500	g Dry		09/18/02	60,000	seconds	+	i	
U-235 (AS)	062-110	2.51E+000	3.57E-001		pCi/g Dry	0.500	g Dry		09/18/02	60,000	seconds	+	İ	
U-238 (AS)	062-110	1.12E+001	1.06E+000		pCi/g Dry	0.500	g Dry		09/18/02	60,000	seconds	+	İ	

Comments:

Sample ID: DH6

Station:

Description: LIMS Number: L19061-2

(78016)

L19061

WESTINGHOUSE

AB018-3EREGXXPOMO

Collect Start: 08/28/02 0:00

Collect Stop:

Received: 08/30/02 Matrix: Soil (S)

% Moisture:														
Radionuclide	SOP#	Conc	Uncertainty (2 Sigma)	MDC	Units	Aliquot Volume	Aliquot Units	Reference Date	Count Date	Count Time	Count Time Units	Fla	g Values	
GR-A	032-15	3.81E+001	8.19E+000	· · · · · · · · · · · · · · · · · · ·	pCi/g Dry	1.000	G	 	09/10/02	50	M	+		
GR-B	032-15	6.96E+001	4.04E+000		pCi/g Dry	1.000	G		09/10/02	50	M	+	İ	
J-233/234 (AS)	062-110	4.42E+001	3.79E+000		pCi/g Dry	0.500	g Dry		09/18/02	60,000	seconds	+		
J-235 (AS)	062-110	1.77E+000	2.91E-001		pCi/g Dry	0.500	g Dry		09/18/02	60,000	seconds	+		
J-238 (AS)	062-110	7.21E+000	7.45E-001		pCi/g Dry	0.500	g Dry		09/18/02	60,000	seconds	+		_

Comments:

Flag Values

Activity concentration exceeds MDC and 3 sigma and peak identified(gamma only)

Peak not identified, but forced activity concentration exceeds MDC and 3 sigma Activity concentration exceeds customer reporting value High

Spec = MDC exceeds customer technical specification

No Peak not identified in gamma spectrum Peak identified in gamma spectrum Yes

Bolded text indicates reportable value.

**** Results are reported on an as received basis unless otherwise noted

1 of 2

Report of Alialysis

9/27/02 1:15:19PM



Sample ID: DH7

L19061

Collect Start: 08/28/02 0:00

Station:

WESTINGHOUSE

Collect Stop:

Description:

LIMS Number: L19061-3 (78017) AB018-3EREGXXPOMO

Received: 08/30/02 Matrix: Soil (S)

% Moisture:		(,,,,,								Volu	me:			
Radionuclide	SOP#	Activity Conc	Uncertainty (2 Sigma)	MDC	Units	Aliquot Volume	Aliquot Units	Reference Date	Count Date	Count Time	Count Time Units	Fla	g Values	i
GR-A	032-15	2.31E+001	6.62E+000		pCi/g Dry	1.000	G		09/10/02	50	M	+		
GR-B	032-15	1.69E+001	2.25E+000		pCi/g Dry	1.000	G		09/10/02	50	M	+		
U-233/234 (AS)	062-110	2.13E+001	1.86E+000		pCi/g Dry	0.500	g Dry		09/18/02	60,000	seconds	+		
U-235 (AS)	062-110	9.59E-001	1.95E-001		pCi/g Dry	0.500	g Dry		09/18/02	60,000	seconds	+	İ	
U-238 (AS)	062-110	2.09E+000	2.91E-001		pCi/g Dry	0.500	g Dry		09/18/02	60,000	seconds	+		

Comments:

Sample ID: DH8

L19061

Collect Start: 08/28/02 0:00

Station:

Description:

WESTINGHOUSE

Collect Stop:

LIMS Number: L19061-4 % Moisture:

(78018)

AB018-3EREGXXPOMO

Received: 08/30/02 Matrix: Soil (S)

Volume:

/ Ivioistare.										A OIR	iiic.			
Radionuclide	SOP#	Activity Conc	Uncertainty (2 Sigma)	MDC	Units	Aliquot Volume	Aliquot Units	Reference Date	Count Date	Count Time	Time Units	Fla	g Values	-
GR-A	032-15	4.39E+001	8.71E+000	· · · · · · · · · · · · · · · · · · ·	pCi/g Dry	1.000	G		09/10/02	50	M	+		*******
GR-B	032-15	6.17E+001	3.83E+000		pCi/g Dry	1.000	G		09/10/02	50	M	+		
U-233/234 (AS)	062-110	7.96E+001	7.46E+000		pCi/g Dry	0.500	g Dry		09/18/02	60,000	seconds	+	İ	
U-235 (AS)	062-110	3.03E+000	4.59E-001		pCi/g Dry	0.500	g Dry		09/18/02	60,000	seconds	+		
U-238 (AS)	062-110	9.20E+000	1.02E+000		pCi/g Dry	0.500	g Dry		09/18/02	60,000	seconds	+		

Comments:

Flag Values

Activity concentration exceeds MDC and 3 sigma and peak identified(gamma only) =

Peak not identified, but forced activity concentration exceeds MDC and 3 sigma Activity concentration exceeds customer reporting value High

MDC exceeds customer technical specification Spec

Peak not identified in gamma spectrum No = Peak identified in gamma spectrum Yes

Bolded text indicates reportable value.

**** Results are reported on an as received basis unless otherwise noted

2 of 2

PACKING LIST

Teledyne Rad Analytical 2508 Quality Lane Knoxville, TN 37931-3133 R-210

Send Report To: Westinghouse Electric Co. Address: 3300 State Road P, P.O. Box 107 City, State: Festus, Mo. Zip: 63028 Attention: Bill Sharkey Telephone Number (314) 937-4691 x 399 Purchase Order No. FAX Number (314) 937-7955 Turn around Time: (X) 28 Day () 14 Day () 5 Day Sample ID Collection Date Sample ID Collection Date State	Date:	8/28/02	-	
City, State: Festus, Mo. Zip: 63028 Attention: Bill Sharkey Telephone Number (314) 937-4691 x 399 Purchase Order No. FAX Number (314) 937-7955 Turn around Time: (X) 28 Day () 14 Day () 5 Day Sample ID Collection Date Sample ID Collection Date	Send Report	To: Westinghouse Electric C	co.	
Attention: Bill Sharkey Telephone Number (314) 937-4691 x 399 Purchase Order No. FAX Number (314) 937-7955 Turn around Time: (X) 28 Day () 14 Day () 5 Day Sample ID Collection Date Sample ID Collection Date ### 18015 ### 18015 Please analyze samples for the following; (Check by use of an "X" for your requirements) Analyze Soil Samples For: (X) Gross Alpha & Gross Beta	Address:	3300 State Road P, P.O. Box 1	07	
Purchase Order No. FAX Number (314) 937-7955 Turn around Time: (X) 28 Day () 14 Day () 5 Day Sample ID Collection Date \$128/02 78016 \$128/02 78016 \$128/02 78016 \$128/02 78017 \$128/02 78018 Please analyze samples for the following; (Check by use of an "X" for your requirements) Analyze Soil Samples For: (X) Gross Alpha & Gross Beta	City,State:	Festus, Mo.	Zip:	63028
Turn around Time: (X) 28 Day () 14 Day () 5 Day Sample ID Collection Date Sample ID Collection Date State Day 18015 18016	Attention:	Bill Sharkey	_Telephone Number (314)	937-4691 x 399
Sample ID Collection Date 8/28/02 7/8015 7/8019 7/8017 7/8018 Please analyze samples for the following; (Check by use of an "X" for your requirements) Analyze Soil Samples For: (X) Gross Alpha & Gross Beta	Purchase Or	der No.	_ FAX Number (314)	937-7955
Analyze Soil Samples For: (X) Gross Alpha & Gross Beta		Collection Date	Sample ID 78015 78016 78017	Collection Date
8/3000 Monost October Daniel A. Hlet	Analyze Soi (X) Gross	I Samples For: Alpha & Gross Beta malysis I Solopic A	nalysis	uirements)



A Teledyne Technologies Company 2508 Quality Lane Knoxville, TN 37931-3133

WESTINGHOUSE
NUCLEAR FUEL
3300 STATE ROAD P
FESTUS MO 63028
Atm: CORT N. HORTON

Report of Analysis/Certificate of Conformance

9/27/02

LIMS #: L19081

Project ID#: AB018-3EREGXXPOMO

Received: 9/4/02

Delivery Date: 10/4/02

P.O. #: SA20000050 L/I 1

Release #:

SDG #: N/A

This is to certify that Teledyne Brown Engineering - Environmental Services located at 2508 Quality Lane, Knoxville, Tennessee, 37931, has analyzed, tested and documented samples as specified in the applicable purchase order.

This also certifies that requirements of applicable codes, standards and specifications have been fully met and that any quality assurance documentation which verified conformance to the purchase order is on file and may be examined upon request.

I hereby certify that the above statements are true and correct.

Keith Jeter

Operations Manager

Cross Reference Table

Client ID	Laboratory ID	TI#
DH10	L19081-1	78076
DH9	L19081-2	78077

Report of Analysis

9/27/02 1:15:19PM



CORT N. HORTON

% Moisture:

Sample ID: DH10

Station:

Description: LIMS Number: L19081-1

(78076)

L19081

WESTINGHOUSE

AB018-3EREGXXPOMO

Collect Start: 08/29/02 0:00

Collect Stop:

Received: 09/04/02 Matrix: Soil (S)

Volume:

70 112010turo.										¥ OIU	anc.			
Radionuclide	SOP#	Activity Conc	Uncertainty (2 Sigma)	MDC	Units	Aliquot Volume	Aliquot Units	Reference Date	Count Date	Count Time	Time Units	Fla	g Values	\$
3R-A	032-15	3.00E+001	7.31E+000		pCi/g Dry	1.000	G		09/10/02	50	M	+		
GR-B	032-15	4.49E+001	3.28E+000	-	pCi/g Dry	1.000	G		09/10/02	50	M	+		
J-233/234 (AS)	062-110	4.60E+001	3.75E+000		pCi/g Dry	0.500	g Dry		09/19/02	60,002	seconds	+		
J-235 (AS)	062-110	1.81E+000	2.81E-001		pCi/g Dry	0.500	g Dry		09/19/02	60,002	seconds	+	İ	
J-238 (AS)	062-110	5.68E+000	5.87E-001		pCi/g Dry	0.500	g Dry		09/19/02	60,002	seconds	+		

Comments:

Sample ID: DH9

Station:

Description:

LIMS Number: L19081-2 % Moisture:

(78077)

L19081

WESTINGHOUSE

AB018-3EREGXXPOMO

Collect Start: 08/29/02 0:00

Collect Stop:

Received: 09/04/02 Matrix: Soil (S)

Volume:

70 WOISTUIC.										VOIU	ine:				
Radionuclide	SOP#	Activity Conc	Uncertainty (2 Sigma)	MDC	Units	Aliquot Volume	Aliquot Units	Reference Date	Count Count Time Flag Values Date Time Units						
JR-A	032-15	1.93E+001	6.06E+000		pCi/g Dry	1.000	G		09/10/02	50	M	+			
R-B	032-15	2.10E+001	2.37E+000		pCi/g Dry	1.000	G		09/10/02	50	М	+			
J-233/234 (AS)	062-110	2.19E+001	1.72E+000		pCi/g Dry	0.500	g Dry		09/19/02	60,001	seconds	+			
	t .	8.79E-001	4 1		pCi/g Dry	0.500	g Dry		09/19/02	60,001	seconds	+			
J-238 (AS)	062-110	2.35E+000	2.84E-001		pCi/g Dry	0.500	g Dry		09/19/02	60,001	seconds	+			

lomments:

'lag Values

= Activity concentration exceeds MDC and 3 sigma and peak identified(gamma only)

= Peak not identified, but forced activity concentration exceeds MDC and 3 sigma

Reference = Peak not identified, but forced activity concentration exceeds MDC and 3 sigma

Activity concentration exceeds customer reporting value

pec = MDC exceeds customer technical specification

lo = Peak not identified in gamma spectrum

Peak identified in gamma spectrum

'ded text indicates reportable value.

**** Results are reported on an as received basis unless otherwise noted

PACKING LIST

Ship To:

Teledyne Rad Analytical 2508 Quality Lane Knoxville, TN 37931-3133 LIW81 E-240

Date:			_		
Send Report 1	o: West	inghouse Electric Co	0.		
Address:	3300 State F	Road P, P.O. Box 10	07		
City,State:	Festus, Mo.			Zip:	63028
Attention:	Bill Sharkey		Telephon	e Number (314)	937-4 691 x 399
Purchase Ord	er No		_	FAX Number (314)	937-7955
Turn around	Time: (X) 28 Day () 14	Day () 5 Day	
Sample ID		Collection Date	,	Sample ID	Collection Date
DHD		3128100 de	11102	78076	
DHY		81781008/2	3/02	78077	
•			-	***************************************	
	· · · · · · · · · · · · · · · · · · ·		-		
			-		
			-		
			_		<u> </u>
 			_	,	
	 	W	-	1	
			_	· · · · · · · · · · · · · · · · · · ·	
			<u>.</u>		
-	•	or the following;	(Check b	y use of an "X" for your re	equirements)
Analyze Soil	•				
(X) Gross A	Alpha & Gros	s Beta			
			•		
	دسلم.	Λ	/*		
Additional An	alysis	sold to	Velley,		
		ş			
			-,-		And the second s
				· 1 1	
Q/.,	٥٥	1 - 2 - 1 -		L . 11 /1/10	<u></u>
7/4/6	r mone	etsoln	<u> </u>	JANA H-V/	
, ,(Authoriz	ed Signature	

A Teledyne Technologies Company 2508 Quality Lane Knoxville, TN 37931-3133

WESTINGHOUSE NUCLEAR FUEL 3300 STATE ROAD P FESTUS MO 63028 Attn: CORT N. HORTON

Report of Analysis/Certificate of Conformance

10/19/02

LIMS #: L19178

Project ID#: AB018-3EREGXXPOMO

Received: 9/18/02

Delivery Date: 10/18/02

P.O. #: SA20000050 L/I 1

Release #:

SDG #: N/A

This is to certify that Teledyne Brown Engineering - Environmental Services located at 2508 Quality Lane, Knoxville, Tennessee, 37931, has analyzed, tested and documented samples as specified in the applicable purchase order.

This also certifies that requirements of applicable codes, standards and specifications have been fully met and that any quality assurance documentation which verified conformance to the purchase order is on file and may be examined upon request.

I hereby certify that the above statements are true and correct.

Keith Jeter

Operations Manager

Cross Reference Table

Client ID	Laboratory ID	11#
DH-11 +	L19178-1	78687
△ DH-12 *	L19178-2	78688
DH-13	L19178-3	78689
DH-14	L19178-4	78690

Report of Analysis

10/18/02 4:43:06PM



CORT N. HORTON

Description:

Sample ID: DH-11

LIMS Number: L19178-1

Station:

(78687)

L19178

WESTINGHOUSE

AB018-3EREGXXPOMO

Collect Start: 09/13/02 0:00

Collect Stop:

Received: 09/18/02 Matrix: Soil (S)

% Moisture:		(70007)								Volu	ıme:			
Radionuclide	SOP#	Activity Conc	Uncertainty (2 Sigma)	MDC	Units	Aliquot Volume	Aliquot Units	Reference Date	Count Date	Count Time	Count Time Units	Fla	g Value	\$
GR-A	032-15	3.50E+001	7.36E+000		pCi/g Dry	1.000	G		09/30/02	50	M	+		
GR-B	032-15	4.52E+001	3.26E+000		pCi/g Dry	1.000	G		09/30/02	50	M	+:		
U-233/234 (AS)	062-110	8.68E+001	8.86E+000		pCi/g	0.500	g		10/09/02	60,003	seconds	+		
U-235 (AS)	062-110	2.71E+000	4.64E-001		pCi/g	0.500	g		10/09/02	60,003	seconds	+		
U-238 (AS)	062-110	2.96E+000	4.66E-001		pCi/g	0.500	g		10/09/02	60,003	seconds	+	T	

Comments:

Sample ID: DH-12

Station: Description:

LIMS Number: L19178-2

(78688)

L19178

WESTINGHOUSE

AB018-3EREGXXPOMO

Collect Start: 09/13/02 0:00

Collect Stop:

Received: 09/18/02 Matrix: Soil (S)

% Moisture:		(70000)								Volu	me:			
Radionuclide	SOP#	Activity Conc	Uncertainty (2 Sigma)	MDC	Units	Aliquot Volume	Aliquot Units	Reference Date	Count Date	Count Time	Count Time Units	Fla	g Value	s
GR-A	032-15	2.71E+001	6.53E+000		pCi/g Dry	1.000	G		09/30/02	50	М	+		
GR-B	032-15	5.41E+001	3.53E+000		pCi/g Dry	1.000	G		09/30/02	50	М	+		
U-233/234 (AS)	062-110	2.87E+001	3.06E+000		pCi/g	0.500	g		10/09/02	60,002	seconds	+		
U-235 (AS)	062-110	9.48E-001	2.42E-001		pCi/g	0.500	g		10/09/02	60,002	seconds	+		•
U-238 (AS)	062-110	2.03E+000	3.56E-001		pCi/g	0.500	g		10/09/02	60,002	seconds	+		

Comments:

Flag Values

Activity concentration exceeds MDC and 3 sigma and peak identified(gamma only)

Peak not identified, but forced activity concentration exceeds MDC and 3 sigma Activity concentration exceeds customer reporting value High

MDC exceeds customer technical specification Spec =

Peak not identified in gamma spectrum No Peak identified in gamma spectrum Yes

Bolded text indicates reportable value.

**** Results are reported on an as received basis unless otherwise noted

1 of 2

Report of Analysis

10/18/02 4:48:47PM



Sample ID: DH-13

Station:

L19178

Collect Start: 09/13/02 0:00

WESTINGHOUSE

Collect Stop:

Description:

LIMS Number: L19178-3

AB018-3EREGXXPOMO

Received: 09/18/02 Matrix: Soil (S)

Volume:

% Moisture:										V Olu	11110.			
Radionuclide	SOP#	Activity Conc	Uncertainty (2 Sigma)	MDC	Units	Aliquot Volume	Aliquot Units	Reference Date	Count Date	Count Time	Count Time Units	Fla	g Values	
GR-A	032-15	2.94E+001	6.77E+000		pCi/g Dry	1.000	G		09/30/02	50	M	+		
GR-B	032-15	4.57E+001	3.27E+000		pCi/g Dry	1.000	G		09/30/02	50	M	+		
U-233/234 (AS)	062-110	3.44E+001	3.00E+000		pCi/g	0.500	g		10/09/02	60,000	seconds	+		
U-235 (AS)	062-110	1.23E+000	2.32E-001		pCi/g	0.500	g		10/09/02	60,000	seconds	+]
U-238 (AS)	062-110	2.32E+000	3.22E-001		pCi/g	0.500	g		10/09/02	60,000	seconds	+		J

Comments:

Sample ID: DH-14

Station:

Description:

LIMS Number: L19178-4

(78690)

(78689)

L19178

WESTINGHOUSE

AB018-3EREGXXPOMO

Collect Start: 09/13/02 0:00

Collect Stop:

Received: 09/18/02 Matrix: Soil (S)

Volume

% Moisture:	SOP#	Activity Conc	Uncertainty (2 Sigma)	MDC	Units	Aliquot Aliquot Reference Count Count Time Flag Value Volume Units Date Date Time Units							g Values	1
GR-A	032-15	2.19E+001	5.90E+000		pCi/g Dry	1.000	G		09/30/02	50	M	+		
GR-B	032-15	3.79E+001	3.01E+000		pCi/g Dry	1.000	G		09/30/02	50	М	+		
U-233/234 (AS)	062-110	2.74E+001	2.05E+000		pCi/g	0.500	g		10/09/02	60,000	seconds	+		
U-235 (AS)	062-110	8.05E-001	1.55E-001		pCi/g	0.500	g		10/09/02	60,000	seconds	+		
U-238 (AS)	062-110	3.69E+000	3.78E-001		pCi/g	0.500	g		10/09/02	60,000	seconds	+		

Comments:

Flag Values

Activity concentration exceeds MDC and 3 sigma and peak identified(gamma only)

Peak not identified, but forced activity concentration exceeds MDC and 3 sigma Activity concentration exceeds customer reporting value High

MDC exceeds customer technical specification Spec

Peak not identified in gamma spectrum No

Peak identified in gamma spectrum Yes

**** Results are reported on an as received basis unless otherwise noted

2 of 2

Ship To:

Teledyne Brown Engineering 2508 Quality Lane

Knoxville, TN 37931-3133

L1 E-20c

Date:		13-Sep	-02		
Send Report	Го:	Westinghouse Ele	ectric Corp		
Address:	3300	State Road P			
City,State:	Festus	s, MO		Zip: _	63028
Attention:	Kevin	Hayes		Telephone Number	(314) 937-4691 x464
Purchase Ord	ler No.	9950021			
Purchase Order No. Turn around Time: Sample ID DH-11 DH-12 DH-13 DH-14		() 28 Day (Collection	-02 -02 -02	() 5 Day Sample ID 78687 78689 78690	Collection Date
Please analyz	ze sam	ples for the following	ng; (Check	by use of an "X" for you	r requirements)
ANALYZE SO	OIL SA	MPLES FOR,		-	
(X) Gross A			<u>S.</u>		
Comments :					
**************************************	••••	· · · · · · · · · · · · · · · · · · ·		, /	

Authorized Signature

HPF8057

WESTINGHOUSE NUCLEAR FUEL 3300 STATE ROAD P FESTUS MO 63028 Attn: CORT N. HORTON

Report of Analysis/Certificate of Conformance

10/15/02

LIMS #: L19304

Project ID#: AB018-3EREGXXPOMO

Received: 10/4/02

Delivery Date: 10/18/02

P.O. #; SA20000050 L/I 1

Release #:

SDG #: N/A

This is to certify that Teledyne Brown Engineering - Environmental Services located at 2508 Quality Lane, Knoxville, Tennessee, 37931, has analyzed, tested and documented samples as specified in the applicable purchase order.

This also certifies that requirements of applicable codes, standards and specifications have been fully met and that any quality assurance documentation which verified conformance to the purchase order is on file and may be examined upon request.

I hereby certify that the above statements are true and correct.

Kéith Jeter

Operations Manager

Cross Reference Table

Client ID	Laboratory ID	TI#
DH15	L19304-2	80662
DH16	L19304-3	80663

Report of Analysis

10/15/02 1:28:35PM



CORT N. HORTON

Sample ID: DH15

L19304

Collect Start: 10/01/02 0:00

Station:

WESTINGHOUSE

Collect Stop: Received: 10/04/02

Description:

LIMS Number: L19304-2

AB018-3EREGXXPOMO (80662)

Matrix: Soil (S)

%

Moisture:			 					Volum	ne:
	Activity	Uncertainty	 TT-24.	Aliquot	Aliquet	Dafarence	Count	Count	Сопа

Radionuclide	SOP#	Activity Conc	Uncertainty (2 Sigma)	MDC	Units	Aliquot Volume	Aliquot Units	Reference Date	Count -Date	Count Time	Count Time Units	Fla	Flag Values	
GR-A	032-15	1.94E+001	5.58E+000		pCi/g Dry	1.000	G		10/11/02	50	M	+		
GR-B	032-15	5.13E+001	3.48E+000		pCi/g Dry	1.000	G		10/11/02	50	M	+:		
U-233/234 (AS)	062-110	9.54E+000	8.53E-001		pCi/g	0.500	g		10/10/02	60,002	seconds	+		
U-235 (AS)	062-110	3.15E-001	9.97E-002		pCi/g	0.500	g	_	10/10/02	60,002	seconds	+		7
U-238 (AS)	062-110	1.70E+000	2.38E-001		pCi/g	0.500	g		10/10/02	60,002	seconds	+		<u> </u>

Comments:

Sample ID: DH16 L1930 Station: WESTING Description: L19304-3 (80663) AB018-3EREG	GHOUSE Collect Stop: Received: 10/04/02	
--	---	--

% Moisture: Volume:														
Radionuciide	SOP#	Activity Conc	Uncertainty (2 Sigma)	MDC	Units	Aliquot Volume	Aliquot Units	Reference Date	Count Date	Count Time	Count Time Units	Fla	g Values	i
GR-A	032-15	9.19E+000	4.05E+000		pCi/g Dry	1.000	G		10/11/02	50	М	+		
GR-B	032-15	3.19E+001	2.86E+000		pCi/g Dry	1.000	G		10/11/02	50	М	+		
U-233/234 (AS)	062-110	3.92E+000	4.08E-001		pCi/g	0.500	g		10/10/02	60,000	seconds	+		
U-235 (AS)	062-110	1.46E-001	6.59E-002		pCi/g	0.500	g		10/10/02	60,000	seconds	+		
U-238 (AS)	062-110	9.44E-001	1.60E-001		pCi/g	0.500	g		10/10/02	60,000	seconds	+		

Comments:

Flag Values

Activity concentration exceeds MDC and 3 sigma and peak identified(gamma only)

Peak not identified, but forced activity concentration exceeds MDC and 3 sigma Activity concentration exceeds customer reporting value = High =

MDC exceeds customer technical specification Spec = Peak not identified in gamma spectrum No

Peak identified in gamma spectrum Yes

Bolded text indicates reportable value.

**** Results are reported on an as received basis unless otherwise noted



STL Knoxville

5815 Middlebrook Pike Knoxville, TN 37921-5947

Tel: 865-291-3000 Fax: 865-584-4315 www.stl-inc.com

ANALYTICAL REPORT

TCLP Samples

Lot #: H2F190244

Rebecca Charles

Teledyne Brown Engineering 2508 Quality Lane Knoxville, TN 37931-3133

SEVERN TRENT LABORATORIES, INC.

Jamie A. McKinney
Project Manager

July 17, 2002

ANALYTICAL METHODS SUMMARY

H2F190244

PARAMETER	ANALYTICAL METHOD
Inductively Coupled Plasma (ICP) Metals Mercury in Liquid Waste (Manual Cold-Vapor)	SW846 6010B SW846 7470A
Semivolatile Organic Compounds by GC/MS Volatile Organics by GC/MS	SW846 8270C SW846 8260B

References:

SW846

"Test Methods for Evaluating Solid Waste, Physical/Chemical Methods", Third Edition, November 1986 and its updates.

SAMPLE SUMMARY

H2F190244

WO # SAMPLE#	CLIENT SAMPLE ID	SAMPLED DATE	SAMP TIME
E3A3L 001 E3A3N 002		06/14/02 06/14/02	

NOTE(S):

- The analytical results of the samples listed above are presented on the following pages.
- All calculations are performed before rounding to avoid round-off errors in calculated results.
- Results noted as "ND" were not detected at or above the stated limit.
- This report must not be reproduced, except in full, without the written approval of the laboratory.
- Results for the following parameters are never reported on a dry weight basis: color, corrosivity, density, flashpoint, ignitability, layers, odor, paint filter test, pH, porosity pressure, reactivity, redox potential, specific gravity, spot tests, solids, solubility, temperature, viscosity, and weight.

PROJECT NARRATIVE H2F190244

The results reported herein are applicable to the samples submitted for analysis only.

This report shall not be reproduced except in full, without the written approval of the laboratory.

The original chain of custody documentation is included with this report.

Sample Receipt

There were no problems with the condition of the samples received.

Quality Control

Unless otherwise noted, all holding times and QC criteria were met and the test results shown in this report meet all applicable NELAC requirements.

Semivolatiles

Surrogate recoveries for sample 71071 were outside QC limits and a re-extraction and reanalysis were performed outside of the holding time. The results for the re-extraction indicated that the original recoveries were outside limits due to laboratory error; both sets of data are presented for compliance purposes.

STL Knoxville maintains the following certifications, approvals and accreditations: Arkansas DEQ, California DHS ELAP Cert. #2423, Connecticut DPH Cert. #PH-0223, Florida DOH Cert. #E87177, Georgia DNR Cert. #906 (SDWA, 5/14/01-6/21/02), Hawaii DOH, Illinois EPA Cert. #000510, Indiana DOH Cert. #C-TN-02, Kentucky DEP Lab ID #90101, Louisiana DEQ Cert. #03079, Maryland DHMH Cert. #277, Massachusetts DEP Cert. #M-TN009, Michigan DEQ Lab ID #9933, New Jersey DEP Cert. #TN001, New York DOH Lab #10781, North Carolina DPH Lab ID #21705, North Carolina DEHNR Cert. #64, Oklahoma DEQ ID #9415, Pennsylvania DEP Cert. #68-576, South Carolina DHEC Lab ID #84001, Tennessee DOH Lab ID #02014, Virginia DGS Lab ID #00165, Washington DOE Lab #C120, Wisconsin DNR Lab ID #998044300, US Army Corps of Engineers, Naval Facilities Engineering Service Center, US EPA Perchlorate Approval and USDA Soil Permit #S-46424. This list of approvals is subject to change and does not imply that laboratory certification is available for all parameters reported in this environmental sample data report.

Client Sample ID: 71071

TCLP GC/MS Volatiles

Lot-Sample #: H2F190244-001	Work Order #: E3A3L1AA	Matrix: SOLID
Date Sampled: 06/14/02	Date Received: 06/19/02	
Leach Date: 06/24/02	Prep Date: 06/25/02	Analysis Date: 06/25/02
Leach Batch #: P217501	Prep Batch #: 2176315	

Dilution Factor: 1

% Moisture....: Method....: SW846 8260B

PARAMETER	RESULT	REPORTING LIMIT	UNITS
Benzene	ND	0.050	mg/L
Carbon tetrachloride	ND	0.050	mg/L
Chlorobenzene	ND	0.050	mg/L
Chloroform	ND	0.050	mg/L
1,2-Dichloroethane	ND	0.050	mg/L
1,1-Dichloroethylene	ND	0.050	mg/L
Methyl ethyl ketone	ND	0.20	mg/L
Tetrachloroethylene	ND	0.050	mg/L
Trichloroethylene	ND	0.050	mg/L
Vinyl chloride	ND	0.10	mg/L
	PERCENT	RECOVERY	
SURROGATE	RECOVERY	LIMITS	
Dibromofluoromethane	96	(77 - 123)	•
1,2-Dichloroethane-d4	103	(80 - 122)	
Toluene-d8	100	(80 - 120)	
Bromofluorobenzene	100	(74 - 137)	

NOTE(S):

Analysis performed in accordance with USEPA Toxicity Characteristic Leaching Procedure Method 1311

Client Sample ID: 71072

TCLP GC/MS Volatiles >

Lot-Sample #: H2F190244-002	Work Order #: E3A3N1AA	Matrix SOLID
Date Sampled: 06/14/02	Date Received: 06/19/02	
Leach Date: 06/24/02	Prep Date: 06/25/02	Analysis Date: 06/25/02
Leach Batch #: P217501	Prep Batch #: 2176315	, ,

Leach Batch #..: P217501

Dilution Factor: 1 % Moisture....:

NOTE(S):

Method....: SW846 8260B

		REPORTING	
PARAMETER	RESULT	LIMIT U	JNITS
Benzene	ND	0.050 m	ng/L
Carbon tetrachloride	ND	0.050 m	ng/L
Chlorobenzene	ND	0.050 π	ng/L
Chloroform	ND	0.050 π	ng/L
1,2-Dichloroethane	ND	0.050 π	ng/L
1,1-Dichloroethylene	ND	0.050 n	ng/L
Methyl ethyl ketone	ND	0.20 n	ng/L
Tetrachloroethylene	ND	0.050 n	ng/L
Trichloroethylene	ND	0.050 n	ng/L
Vinyl chloride	ND	0.10 π	ng/L
	PERCENT	RECOVERY	
SURROGATE	RECOVERY	LIMITS	
Dibromofluoromethane	104	(77 - 123)	
1,2-Dichloroethane-d4	114	(80 - 122)	
Toluene-d8	97	(80 - 120)	
Bromofluorobenzene	102	(74 - 137)	

Analysis performed in accordance with USEPA Toxicity Characteristic Leaching Procedure Method 1311

METHOD BLANK REPORT

TCLP GC/MS Volatiles

Client Lot #...: H2F190244 Work Order #...: E3KDG1AA Matrix.....: SOLID

MB Lot-Sample #: H2F240000-130

Leach Batch #..: P217501 Prep Batch #...: 2176315

Dilution Factor: 1

		REPORTING	}	
PARAMETER	RESULT	LIMIT	UNITS	METHOD
Benzene	ND	0.050	mg/L`	SW846 8260B
Carbon tetrachloride	ND	0.050	mg/L	SW846 8260B
Chlorobenzene	ND	0.050	mg/L	SW846 8260B
Chloroform	ND	0.050	mg/L	SW846 8260B
1,2-Dichloroethane	ND	0.050	mg/L	SW846 8260B
1,1-Dichloroethylene	ND	0.050	mg/L	SW846 8260B
Methyl ethyl ketone	ND	0.20	mg/L	SW846 8260B
Tetrachloroethylene	ND	0.050	mg/L	SW846 8260B
Trichloroethylene	ND	0.050	mg/L	SW846 8260B
Vinyl chloride	ND	0.10	mg/L	SW846 8260B
	PERCENT	RECOVERY		
SURROGATE	RECOVERY	LIMITS		
Dibromofluoromethane	98	(77 - 123)	
1,2-Dichloroethane-d4	103	(80 - 122)	
Toluene-d8	100	(80 - 120)	
Bromofluorobenzene	105	(74 - 137)	

NOTE(S):

Calculations are performed before rounding to avoid round-off errors in calculated results.

LABORATORY CONTROL SAMPLE EVALUATION REPORT

GC/MS Volatiles

Client Lot #...: H2F190244 Work Order #...: E3ML01AA Matrix.....: SOLID

LCS Lot-Sample#: H2F250000-315

Prep Date....: 06/25/02 Analysis Date..: 06/25/02

Prep Batch #...: 2176315

Dilution Factor: 1

PARAMETER Benzene Carbon tetrachloride Chlorobenzene Chloroform	PERCENT RECOVERY 102 99 104 100	RECOVERY LIMITS (74 - 120) (64 - 134) (76 - 120) (74 - 120)	METHOD SW846 8260B SW846 8260B SW846 8260B SW846 8260B
1,2-Dichloroethane	115	(70 - 125)	SW846 8260B
1,1-Dichloroethylene	104	(74 - 120)	SW846 8260B
Methyl ethyl ketone	106	(39 - 138)	SW846 8260B
Tetrachloroethylene	101	(74 - 120)	SW846 8260B
Trichloroethylene	106	(76 - 120)	SW846 8260B
Vinyl chloride	119	(66 - 120)	SW846 8260B
		PERCENT	RECOVERY
SURROGATE		RECOVERY	LIMITS
Dibromofluoromethane		96	(77 - 123)
1,2-Dichloroethane-d4		102	(80 - 122)
Toluene-d8		101	(80 - 120)
Bromofluorobenzene		98	(74 - 137)

NOTE(S):

Calculations are performed before rounding to avoid round-off errors in calculated results.

Bold print denotes control parameters

LABORATORY CONTROL SAMPLE DATA REPORT

GC/MS Volatiles

Client Lot #...: H2F190244 Work Order #...: E3ML01AA Matrix.....: SOLID

LCS Lot-Sample#: H2F250000-315

Prep Date....: 06/25/02 Analysis Date..: 06/25/02

Prep Batch #...: 2176315

Dilution Factor: 1

	SPIKE	MEASURED		PERCENT	
PARAMETER	AMOUNT	AMOUNT	UNITS	RECOVERY	METHOD
Benzene	0.200	0.203	mg/L	102	SW846 8260B
Carbon tetrachloride	0.200	0.198	mg/L	99	SW846 8260B
Chlorobenzene '	0.200	0.209	mg/L	104	SW846 8260B
Chloroform	0.200	0.200	mg/L	100	SW846 8260B
1,2-Dichloroethane	0.200	0.229	mg/L	115	SW846 8260B
1,1-Dichloroethylene	0.200	0.208	mg/L	104	SW846 8260B
Methyl ethyl ketone	0.800	0.852	mg/L	106	SW846 8260B
Tetrachloroethylene	0.200	0.202	mg/L	101	SW846 8260B
Trichloroethylene	0.200	0.212	mg/L	106	SW846 8260B
Vinyl chloride	0.200	0.238	mg/L	119	SW846 8260B
		PERCENT	RECOVERY		
SURROGATE		RECOVERY	LIMITS		

	PERCENI	RECOVERI
SURROGATE	RECOVERY	LIMITS
Dibromofluoromethane	96	(77 - 123)
1,2-Dichloroethane-d4	102	(80 - 122)
Toluene-d8	101	(80 - 120)
Bromofluorobenzene	98	(74 - 137)

NOTE(S):

Calculations are performed before rounding to avoid round-off errors in calculated results.

Bold print denotes control parameters

Client Sample ID: 71071

TCLP GC/MS Semivolatiles

Lot-Sample #...: H2F190244-001 Work Order #...: E3A3L1AC Matrix.....: SOLID

Leach Batch #..: P217502 Prep Batch #...: 2177374

Dilution Factor: 1

% Moisture....: Method.....: SW846 8270C

		REPORTIN	Ġ
PARAMETER	RESULT	LIMIT	UNITS _
o-Cresol	ND	0.050	mg/L
m-Cresol & p-Cresol	ND	0.10	mg/L
1,4-Dichlorobenzene	ND	0.050	mg/L
2,4-Dinitrotoluene	ND	0.050	mg/L
Hexachlorobenzene	ND	0.050	mg/L
Hexachlorobutadiene	ND	0.050	mg/L
Hexachloroethane	ND	0.050	mg/L
Nitrobenzene	ND	0.050	mg/L
Pentachlorophenol	ND	0.25	mg/L
Pyridine	ND	0.10	mg/L
2,4,5-Trichloro- phenol	ND	0.050	mg/L
2,4,6-Trichloro- phenol	ND	0.050	mg/L

	PERCENT	RECOVERY
SURROGATE	RECOVERY	LIMITS
2-Fluorophenol	2.4 *	(19 - 100)
Phenol-d5	2.4 *	(15 - 124)
Nitrobenzene-d5	66	(35 ~ 122)
2-Fluorobiphenyl	39	(34 - 115)
2,4,6-Tribromophenol	3.4 *	(33 - 130)
Terphenyl-dl4	76	(28 - 132)

NOTE(S):

Analysis performed in accordance with USEPA Toxicity Characteristic Leaching Procedure Method 1311

^{*} Surrogate recovery is outside stated control limits.

Client Sample ID: 71071

GC/MS Semivolatiles

Lot-Sample #: H2F190244-001	Work Order #: E3A3L3AC	Matrix: SOLID
-----------------------------	------------------------	---------------

Prep Batch #...: 2190331

Dilution Factor: 1

% Moisture....: Method....: SW846 8270C

PARAMETER	RESULT	REPORTING LIMIT	G UNITS
o-Cresol	ND ND	0.050	mg/L
m-Cresol & p-Cresol	ND	0.10	mg/L
1,4-Dichlorobenzene	ND	0.050	mg/L
2,4-Dinitrotoluene	ND	0.050	mg/L
Hexachlorobenzene	ND	0.050	mg/L
Hexachlorobutadiene	ND	0.050	mg/L
Hexachloroethane	ND	0.050	mg/L
Nitrobenzene	ND	0.050	mg/L
Pentachlorophenol	ND	0.25	mg/L
Pyridine	ND	0.10	mg/L
2,4,5-Trichloro- phenol	ND	0.050	mg/L
2,4,6-Trichloro- phenol	ND	0.050	mg/L
	PERCENT	RECOVERY	

	PERCENT	RECOVERY
SURROGATE	RECOVERY	LIMITS
2-Fluorophenol	86	(19 - 100)
Phenol-d5	94	(15 - 124)
Nitrobenzene-d5	102	(35 - 122)
2-Fluorobiphenyl	95	(34 - 115)
2,4,6-Tribromophenol	93	(33 - 130)
Terphenyl-d14	102	(28 - 132)

Client Sample ID: 71072

TCLP GC/MS Semivolatiles

Lot-Sample #: H2F190244-002	Work Order #: E3A3N1AC	Matrix SOLID
-----------------------------	------------------------	--------------

Date Sampled...: 06/14/02 Date Received..: 06/19/02 Leach Date....: 06/24/02 Prep Date....: 06/26/02 Analysis Date..: 07/01/02

Leach Batch #..: P217502 Prep Batch #...: 2177374

Dilution Factor: 1 % Moisture....:

Method.....: SW846 8270C

REPORTING	•

PARAMETER	RESULT	LIMIT	UNITS
o-Cresol	ND	0.050	mg/L
m-Cresol & p-Cresol	ND	0.10	mg/L
1,4-Dichlorobenzene	ND	0.050	mg/L
2,4-Dinitrotoluene	ND	0.050	mg/L
Hexachlorobenzene	ND	0.050	mg/L
Hexachlorobutadiene	ND	0.050	mg/L
Hexachloroethane	ND	0.050	mg/L
Nitrobenzene	ND	0.050	mg/L
Pentachlorophenol	MD	0.25	mg/L
Pyridine	ND	0.10	mg/L
2,4,5-Trichloro~ phenol	ND	0.050	mg/L
2,4,6-Trichloro- phenol	ND	0.050	mg/L

	PERCENT	RECOVERY
SURROGATE	RECOVERY	LIMITS
2-Fluorophenol	52	(19 - 100)
Phenol-d5	59	(15 - 124)
Nitrobenzene-d5	89	(35 - 122)
2-Fluorobiphenyl	100	(34 - 115)
2,4,6-Tribromophenol	75	(33 - 130)
Terphenyl-d14	91	(28 - 132)

NOTE(S):

Analysis performed in accordance with USEPA Toxicity Characteristic Leaching Procedure Method 1311

METHOD BLANK REPORT

TCLP GC/MS Semivolatiles

Client Lot #...: H2F190244

MB Lot-Sample #: H2F240000-138

Leach Date....: 06/24/02

Leach Batch #..: P217502

Dilution Factor: 1

Work Order #...: E3KD11AK

Prep Date....: 06/26/02

Prep Batch #...: 2177374

Matrix....: SOLID

Analysis Date..: 07/01/02

REPORTING

PARAMETER	RESULT	LIMIT	UNITS	METHOD
o-Cresol	ND	0.050	mg/L	SW846 8270C
m-Cresol & p-Cresol	ND	0.10	mg/L	SW846 8270C
1,4-Dichlorobenzene	ND	0.050	mg/L	SW846 8270C
2,4-Dinitrotoluene	ND	0.050	mg/L	SW846 8270C
Hexachlorobenzene	ND	0.050	mg/L	SW846 8270C
Hexachlorobutadiene	ND	0.050	mq/L	SW846 8270C
Hexachloroethane	ND	0.050	mg/L	SW846 8270C
Nitrobenzene	ND	0.050	mg/L	SW846 8270C
Pentachlorophenol	ND	0.25	mg/L	SW846 8270C
Pyridine	ND	0.10	mg/L	SW846 8270C
2,4,5-Trichloro- phenol	ND	0.050	mg/L	SW846 8270C
2,4,6-Trichloro- phenol	ND	0.050	mg/L	SW846 8270C

	PERCENT	RECOVERY
SURROGATE	RECOVERY	LIMITS
2-Fluorophenol	70	(19 - 100)
Phenol-d5	63	(15 - 124)
Nitrobenzene-d5	97	(35 - 122)
2-Fluorobiphenyl	76	(34 - 115)
2,4,6-Tribromophenol	78	(33 - 130)
Terphenyl-d14	91	(28 - 132)

NOTE(S):

Calculations are performed before rounding to avoid round-off errors in calculated results.

LABORATORY CONTROL SAMPLE EVALUATION REPORT

GC/MS Semivolatiles

Client Lot #...: H2F190244 Work Order #...: E3QJP1AA Matrix.....: SOLID

LCS Lot-Sample#: H2F260000-374

Prep Date....: 06/26/02 Analysis Date..: 07/01/02

Prep Batch #...: 2177374

Dilution Factor: 1

	PERCENT	RECOVERY	
PARAMETER	RECOVERY	<u>LIMITS</u>	METHOD
o-Cresol	77	(34 - 118)	SW846 8270C
m-Cresol & p-Cresol	80	(29 - 134)	SW846 8270C
1,4-Dichlorobenzene	83	(34 - 104)	SW846 8270C
2,4-Dinitrotoluene	95	(47 - 122)	SW846 8270C
Hexachlorobenzene	88	(42 - 139)	SW846 8270C
Hexachlorobutadiene	77	(28 - 105)	SW846 8270C
Hexachloroethane	81	(24 - 103)	SW846 8270C
Nitrobenzene	92	(30 - 135)	SW846 8270C
Pentachlorophenol	95	(29 - 124)	SW846 8270C
Pyridine	68	(10 - 128)	SW846 8270C
2,4,5-Trichloro-	77	(43 - 124)	SW846 8270C
phenol			
2,4,6-Trichloro-	77	(42 - 114)	SW846 8270C
phenol			
		PERCENT	RECOVERY
SURROGATE		RECOVERY	LIMITS
2-Fluorophenol	_	59	(19 - 100)
Phenol-d5		75	(15 - 124)
Nitrobenzene-d5		86	(35 - 122)
2-Fluorobiphenyl		83	(34 - 115)
2,4,6-Tribromophenol		90	(33 - 130)
Terphenyl-d14		92	(28 - 132)
•			•

Calculations are performed before rounding to avoid round-off errors in calculated results.

Bold print denotes control parameters

NOTE(S):

LABORATORY CONTROL SAMPLE DATA REPORT

GC/MS Semivolatiles

Client Lot #...: H2F190244 Work Order #...: E3QJP1AA Matrix.....: SOLID

LCS Lot-Sample#: H2F260000-374

Prep Date....: 06/26/02 Analysis Date..: 07/01/02

Prep Batch #...: 2177374

Dilution Factor: 1

PARAMETER	SPIKE AMOUNT	MEASURED AMOUNT	UNITS	PERCENT RECOVERY	METHOD
o-Cresol	0.500	0.383	mg/L	77	SW846 8270C
m-Cresol & p-Cresol	1.00	0.797	mg/L	80	SW846 8270C
1,4-Dichlorobenzene	0.500	0.414	mg/L	83	SW846 8270C
2,4-Dinitrotoluene	0.500	0.474	mg/L	95	SW846 8270C
Hexachlorobenzene	0.500	0.442	mg/L	88	SW846 8270C
Hexachlorobutadiene	0.500	0.385	mg/L	77	SW846 8270C
Hexachloroethane	0.500	0.407	mg/L	81	SW846 8270C
Nitrobenzene	0.500	0.458	mg/L	92	SW846 8270C
Pentachlorophenol	0.500	0.477	mg/L	95	SW846 8270C
Pyridine	0.500	0.339	mg/L	68	SW846 8270C
2,4,5-Trichloro- phenol	0.500	0.387	mg/L	77	SW846 8270C
2,4,6-Trichloro- phenol	0.500	0.384	mg/L	77	SW846 8270C

	PERCENT RECOVERY LIMIT	
SURROGATE		
2-Fluorophenol	59	(19 - 100)
Phenol-d5	75	(15 - 124)
Nitrobenzene-d5	86	(35 - 122)
2-Fluorobiphenyl	83	(34 - 115)
2,4,6-Tribromophenol	90	(33 - 130)
Terphenyl-d14	92	(28 - 132)

NOTE(S):

Calculations are performed before rounding to avoid round-off errors in calculated results.

Bold print denotes control parameters

METHOD BLANK REPORT

GC/MS Semivolatiles

Client Lot #...: H2F190244 Matrix....: SOLID Work Order #...: E4EGL1AA

MB Lot-Sample #: H2G090000-331

Prep Date....: 07/09/02

Analysis Date..: 07/15/02

Prep Batch #...: 2190331

Dilution Factor: 1

NOTE(S):

REPORTING

		REFORTING		
PARAMETER	RESULT	LIMIT	UNITS	METHOD
o-Cresol	ND	0.050	mg/L	SW846 8270C
m-Cresol & p-Cresol	ND	0.10	mg/L	SW846 8270C
1,4-Dichlorobenzene	ND	0.050	mg/L	SW846 8270C
2,4-Dinitrotoluene	ND	0.050	mg/L	SW846 8270C
Hexachlorobenzene	ND	0.050	mg/L	SW846 8270C
Hexachlorobutadiene	ND	0.050	mg/L	SW846 8270C
Hexachloroethane	ND	0.050	mg/L	SW846 8270C
Nitrobenzene	ND	0.050	mg/L	SW846 8270C
Pentachlorophenol	ND	0.25	mg/L	SW846 8270C
Pyridine	ND	0.10	mg/L	SW846 8270C
2,4,5-Trichloro- phenol	ND	0.050	mg/L	SW846 8270C
2,4,6-Trichloro- phenol	ND	0.050	mg/L	SW846 8270C
	PERCENT	RECOVERY	č	
SURROGATE	RECOVERY	LIMITS		
2-Fluorophenol	75	(19 - 10	00)	
Phenol-d5	87	(15 - 12	24)	
Nitrobenzene-d5	89	(35 - 12	22)	
2-Fluorobiphenyl	87	(34 - 11	L5)	
2,4,6-Tribromophenol	84	(33 - 13	30)	
Terphenyl-d14	98	(28 - 13	32)	

Calculations are performed before rounding to avoid round-off errors in calculated results.

LABORATORY CONTROL SAMPLE EVALUATION REPORT

GC/MS Semivolatiles

Client Lot #...: H2F190244 Work Order #...: E4EGL1AC-LCS Matrix.....: SOLID

LCS Lot-Sample#: H2G090000-331 E4EGL1AD-LCSD

Prep Date....: 07/09/02 Analysis Date..: 07/15/02

Prep Batch #...: 2190331

Dilution Factor: 1

	PERCENT	RECOVERY	RPD	
PARAMETER	RECOVERY	LIMITS	RPD LIMITS	METHOD
o-Cresol	88	(34 - 118)		SW846 8270C
	93	(34 - 118)	5.5 (0-24)	SW846 8270C
m-Cresol & p-Cresol	93	(29 - 134)		SW846 8270C
-	97	(29 - 134)	4.3 (0-32)	SW846 8270C
1,4-Dichlorobenzene	88	(34 - 104)		SW846 8270C
	90	(34 - 104)	2.2 (0-30)	SW846 8270C
2,4-Dinitrotoluene	99	(47 - 122)		SW846 8270C
	100	(47 - 122)	1.2 (0-34)	SW846 8270C
Hexachlorobenzene	91	(42 - 139)		SW846 8270C
	90	(42 - 139)	1.5 (0-34)	SW846 8270C
Hexachlorobutadiene	78	(28 - 105)		SW846 8270C
	78	(28 - 105)	0.25 (0-39)	SW846 8270C
Hexachloroethane	92	(24 - 103)		SW846 8270C
	93	(24 - 103)	1.3 (0-37)	SW846 8270C
Nitrobenzene	97	(30 ~ 135)		SW846 8270C
	99	(30 - 135)	2.0 (0-27)	SW846 8270C
Pentachlorophenol	84	(29 - 124)		SW846 8270C
	86	(29 - 124)	2.8 (0-31)	SW846 8270C
Pyridine	77	(10 - 128)		SW846 8270C
	65	(10 - 128)	17 (0-28)	SW846 8270C
2,4,5-Trichloro-	91	(43 - 124)		SW846 8270C
phenol				
	93	(43 - 124)	2.4 (0-31)	SW846 8270C
2,4,6-Trichloro-	91	(42 - 114)		SW846 8270C
phenol				
	93	(42 - 114)	2.0 (0-27)	SW846 8270C
		PERCENT	RECOVERY	
SURROGATE		RECOVERY	LIMITS	
2-Fluorophenol		85	(19 - 100)	
5 Tradiophenor		91	(19 - 100)	
Phenol-d5		96	(15 - 124)	
11101101 43		101	(15 - 124)	
Nitrobenzene-d5		96	(35 - 122)	
The same and the same same same same as the same same as the same same as the same same same same same same same sam		99	(35 - 122)	
2-Fluorobiphenyl		90	(34 - 115)	
		92	(34 - 115)	
2,4,6-Tribromophenol		102	(33 - 130)	
· · ·			- · ·	

(Continued on next page)

LABORATORY CONTROL SAMPLE EVALUATION REPORT

GC/MS Semivolatiles

Client Lot #...: H2F190244 Work Order #...: E4EGL1AC-LCS Matrix.....: SOLID

LCS Lot-Sample#: H2G090000-331 E4EGL1AD-LCSD

 SURROGATE
 PERCENT
 RECOVERY
 LIMITS

 105
 (33 - 130)

 Terphenyl-d14
 98
 (28 - 132)

 98
 (28 - 132)

NOTE (S):

Calculations are performed before rounding to avoid round-off errors in calculated results.

Bold print denotes control parameters

LABORATORY CONTROL SAMPLE DATA REPORT

GC/MS Semivolatiles

Client Lot #...: H2F190244 Work Order #...: E4EGL1AC-LCS Matrix.....: SOLID

LCS Lot-Sample#: H2G090000-331 E4EGL1AD-LCSD

Prep Date....: 07/09/02 Analysis Date..: 07/15/02

Prep Batch #...: 2190331

Dilution Factor: 1

	SPIKE	MEASURED		PERCENT		
PARAMETER	AMOUNT	AMOUNT	UNITS	RECOVERY	RPD	METHOD
o-Cresol	0.500	0.438	mg/L	88		SW846 8270C
	0.500	0.463	mg/L	93	5.5	SW846 8270C
m-Cresol & p-Cresol	1.00	0.927	mg/L	93		SW846 8270C
_	1.00	0.968	mg/L	97	4.3	SW846 8270C
1,4-Dichlorobenzene	0.500	0.438	mg/L	88		SW846 8270C
	0.500	0.448	mg/L	90	2.2	SW846 8270C
2,4-Dinitrotoluene	0.500	0.494	mg/L	99		SW846 8270C
	0.500	0.500	mg/L	100	1.2	SW846 8270C
Hexachlorobenzene	0.500	0.456	mg/L	91		SW846 8270C
	0.500	0.449	mg/L	90	1.5	SW846 8270C
Hexachlorobutadiene	0.500	0.392	mg/L	78		SW846 8270C
	0.500	0.391	mg/L	78	0.25	SW846 8270C
Hexachloroethane	0.500	0.458	mg/L	92		SW846 8270C
	0.500	0.464	mg/L	93	1.3	SW846 8270C
Nitrobenzene	0.500	0.485	mg/L	97		SW846 8270C
	0.500	0.495	mg/L	99	2.0	SW846 8270C
Pentachlorophenol	0.500	0.420	mg/L	84		SW846 8270C
_	0.500	0.432	mg/L	86	2.8	SW846 8270C
Pyridine	0.500	0.384	mg/L	77		SW846 8270C
	0.500	0.325	mg/L	65	17	SW846 8270C
2,4,5-Trichloro-	0.500	0.456	mg/L	91		SW846 8270C
phenol						
	0.500	0.467	mg/L	93	2.4	SW846 8270C
2,4,6-Trichloro-	0.500	0.455	mg/L	91		SW846 8270C
phenol						
	0.500	0.464	mg/L	93	2.0	SW846 8270C
			PERCENT	RECOVERY		
SURROGATE	_		RECOVERY	LIMITS		
2-Fluorophenol			85	(19 - 100		
			91	(19 - 100		
Phenol-d5			96	(15 - 124		
			101	(15 - 124		
Nitrobenzene-d5			96	(35 - 122		
			99	(35 - 122		
2-Fluorobiphenyl			90	(34 - 115		
			92	(34 - 115		
2,4,6-Tribromophenol			102	(33 - 130	,	

(Continued on next page)

LABORATORY CONTROL SAMPLE DATA REPORT

GC/MS Semivolatiles

Client Lot #...: H2F190244 Work Order #...: E4EGL1AC-LCS Matrix.....: SOLID

LCS Lot-Sample#: H2G090000-331 E4EGL1AD-LCSD

	PERCENT	RECOVERY	
SURROGATE	RECOVERY	LIMITS	
	105	(33 - 130)	
Terphenyl-d14	98	(28 - 132)	
	98	(28 - 132)	

NOTE(S):

Calculations are performed before rounding to avoid round-off errors in calculated results.

Bold print denotes control parameters

Client Sample ID: 71071

TCLP Metals

Lot-Sample #...: H2F190244-001

Date Sampled...: 06/14/02 Leach Date....: 06/24/02 Date Received..: 06/19/02

Matrix....: SOLID

Leach Batch #..: P217502

		REPORTIN	REPORTING			PREPARATION-	WORK
PARAMETER	RESULT	LIMIT	UNITS	METHOD		ANALYSIS DATE	ORDER #
Prep Batch #	: 2175168						
Mercury	ND	0.0020	mg/L	SW846 7470A		06/25/02	E3A3L1AL
		Dilution Fac	tor: 1	Analysis Time:	15:02	. ,	
Prep Batch #	: 2176179						
Arsenic	ND	0.50	mg/L	SW846 6010B		06/25~06/27/02	E3A3L1AD
		Dilution Fac	tor: 1	Analysis Time:	15:12		
Barium	ND	10.0	mg/L	SW846 6010B		06/25-06/27/02	E3A3L1AE
		Dilution Fac	tor: 1	Analysis Time:	15:12		
Cadmium	ND	0.10	mg/L	SW846 6010B		06/25-06/27/02	E3A3L1AF
		Dilution Fac	tor: 1	Analysis Time:	15:12		
Chromium	ND	0.50	mg/L	SW846 6010B		06/25-06/27/02	E3A3L1AG
		Dilution Fac	tor: 1	Analysis Time:	15:12		
Lead	ND	0.50	mg/L	SW846 6010B		06/25-06/27/02	E3A3L1AH
		Dilution Fac	tor: 1	Analysis Time:	15:12		
Selenium	ND	0.25	mg/L	SW846 6010B		06/25-06/27/02	E3A3L1AJ
		Dilution Fact	tor: 1	Analysis Time:	15:12		
Silver	ND	0.50	mg/L	SW846 6010B		06/25-06/27/02	E3A3L1AK
		Dilution Fac	tor: 1	Analysis Time:	15:12		
NOTE(S):							

Analysis performed in accordance with USEPA Toxicity Characteristic Leaching Procedure Method 1311

TELEDYNE BROWN ENGINEERING

Client Sample ID: 71072

TCLP Metals

rot-sampre #:	H2F190244-002		Matrix: SOLID
Date Sampled:	06/14/02	Date Received: 06/19/02	
T L TO - L -	0010100	T 3	

Leach Date	: 06/24/02	Leach	Batch #.	.: P217502		
PARAMETER	RESULT	REPORTIN	IG UNITS	METHOD	PREPARATION- ANALYSIS DATE	WORK ORDER #
Prep Batch #	: 2175168					
Mercury	ND	0.0020 Dilution Fac	mg/L tor: 1	SW846 7470A Analysis Time: 15:0	06/25/02 8	E3A3N1AL
Prep Batch #	: 2176179					
Arsenic	ИD	0.50 Dilution Fac	mg/L tor: 1	SW846 6010B Analysis Time: 15:1	06/25-06/27/02 6	E3A3N1AD
Barium	ND	10.0 Dilution Fac	mg/L tor: 1	SW846 6010B Analysis Time: 15:1	06/25-06/27/02 6	E3A3N1AE
Cadmium	ИD	0.10 Dilution Fac	mg/L tor: 1	SW846 6010B	06/25-06/27/02 6	E3A3N1AF
Chromium	ND	0.50 Dilution Fac	mg/L tor: 1	SW846 6010B Analysis Time: 15:1	06/25-06/27/02 6	E3A3N1AG
Lead	ND	0.50 Dilution Fac	mg/L tor: 1	SW846 6010B Analysis Time: 15:1	06/25-06/27/02 6	E3A3N1AH
Selenium	ND	0.25 Dilution Fac	mg/L tor: 1	SW846 6010B Analysis Time: 15:1	06/25-06/27/02 6	E3A3N1AJ
Silver	ND	0.50 Dilution Fac	mg/L tor: 1	SW846 6010B Analysis Time: 15:1	06/25-06/27/02 6	E3A3N1AK

Analysis performed in accordance with USEPA Toxicity Characteristic Leaching Procedure Method 1311

NOTE(S):

METHOD BLANK REPORT

TCLP Metals

Matrix..... SOLID

06/25/02

E3KD11AJ

Client Lot #...: H2F190244

REPORTING PREPARATION-WORK PARAMETER LIMIT RESULT UNITS METHOD ANALYSIS DATE ORDER # MB Lot-Sample #: H2F240000-138 Prep Batch #...: 2176179 Leach Date....: 06/24/02 Leach Batch #..: P217502 Arsenic ND0.50 mg/L SW846 6010B 06/25-06/26/02 E3KD11AA Dilution Factor: 1 Analysis Time..: 13:52 Barium ND 10.0 mg/L SW846 6010B 06/25-06/26/02 E3KD11AC Dilution Factor: 1 Analysis Time..: 13:52 Cadmium ND 0.10 mg/L SW846 6010B 06/25-06/26/02 E3KD11AD Dilution Factor: 1 Analysis Time..: 13:52 Chromium ND 0.50 mg/L SW846 6010B 06/25-06/26/02 E3KD11AE Dilution Factor: 1 Analysis Time..: 13:52 Lead ND 0.50 mg/L SW846 6010B 06/25-06/26/02 E3KD11AF Dilution Factor: 1 Analysis Time..: 13:52 Selenium ND 0.25 mg/L SW846 6010B 06/25-06/26/02 E3KD11AG Dilution Factor: 1 Analysis Time..: 13:52 Silver ND 0.50 mq/L SW846 6010B 06/25-06/26/02 E3KD11AH Dilution Factor: 1 Analysis Time..: 13:52

MB Lot-Sample #: H2F240000-138 Prep Batch #...: 2175168 Leach Date....: 06/24/02 Leach Batch #...: P217502

Dilution Factor: 1

Analysis Time..: 14:55

NOTE(S):

LABORATORY CONTROL SAMPLE EVALUATION REPORT

TCLP Metals

Client Lot #:	H2F190244			Matrix	: SOLID
PARAMETER	PERCENT RECOVERY	RECOVERY LIMITS	METHOD	PREPARATION- ANALYSIS DATE	WORK ORDER #
LCS Lot-Sample#: Mercury	H2F240000- 99	168 Prep Ba (80 - 120) Dilution Facto Analysis Time		06/25/02	E3KE31AA
LCS Lot-Sample#: Arsenic	H2F250000- 106	179 Prep Ba (80 - 120) Dilution Facto Analysis Time	or: 10	06/25-06/26/02	E3LTK1AA
Barium	103	(80 - 120) Dilution Factor Analysis Time	or: 10	06/25-06/26/02	E3LTK1AC
Cadmium	106	(80 - 120) Dilution Factor Analysis Time		06/25-06/26/02	E3LTK1AD
Chromium	101	(80 - 120) Dilution Facto Analysis Time		06/25-06/26/02	E3LTK1AE
Lead	105	(80 - 120) Dilution Facto Analysis Time		06/25-06/26/02	E3LTK1AF
Selenium	104	(80 - 120) Dilution Factor Analysis Time		06/25-06/26/02	E3LTKIAG
Silver	100	(80 - 120) Dilution Factor Analysis Time		06/25-06/26/02	E3LTK1AH
NOTE(S):					

LABORATORY CONTROL SAMPLE DATA REPORT

TCLP Metals

Client Lot	#: H2F	190244					Matrix:	SOLID
	SPIKE	MEASURE	D	PERCNT			PREPARATION-	WORK
PARAMETER	TRUOMA	AMOUNT	UNITS	RECVRY	METHO	<u> </u>	ANALYSIS DATE	ORDER #
LCS Lot-Sam	mle#· H2F	240000-1	68 Prep Ba	tch #	: 2175	168		
Mercury	_	0.00494	_	99		7470A	06/25/02	E3KE31AA
			Dilution Facto	or: 1				
			Analysis Time	: 14:57				
LCS Lot-Sam	mle#· H2F	250000-1	79 Prep Ba	tch #	- 2176	179		
Arsenic	5.00	5.29	mg/L	106		6010B	06/25-06/26/02	E3LTK1AA
		•	Dilution Facto	or: 10	-	-	. ,	
			Analysis Time	: 13:56				
Barium	50.0	51.3	mg/L	103	SW846	6010B	06/25-06/26/02	E3LTK1AC
			Dilution Facto	or: 10			, , , , , , , , , , , , , , , , , , , ,	
			Analysis Time	: 13:56				
Cadmium	1.00	1.06	mq/L	106	SW846	6010B	06/25-06/26/02	E3LTK1AD
			Dilution Facto	or: 10			. , ,	
			Analysis Time	: 13:56				
Chromium	5.00	5.06	mg/L	101	SW846	6010B	06/25-06/26/02	E3LTK1AE
			Dilution Facto	or: 10			•	
			Analysis Time	: 13:56				
Lead	5.00	5.26	mg/L	105	SW846	6010B	06/25-06/26/02	E3LTK1AF
			Dilution Facto	or: 10				
			Analysis Time	: 13:56				
Selenium	1.00	1.04	mg/L	104	SW846	6010B	06/25-06/26/02	E3LTK1AG
			Dilution Facto	or: 10				
			Analysis Time	: 13:56				
Silver	1.00	0.996	mg/L	100	SW846	6010B	06/25-06/26/02	E3LTK1AH
			Dilution Facto	or: 10				
			Analysis Time	: 13:56				
NOTE(S):								
: (6/2104			www.t. t. W. data					



Appendix B Contractor Analytical Data



A Teledyna Technologies Company 2508 Quality Lane Knoxville, TN 37931-3133



US Ecology 109 Flint Road Oak Ridge TN 37830 Attn: Darrel Ray

Report of Analysis/Certificate of Conformance

10/22/02

LIMS #: L19308

Project ID#: US607-3EREGFS-02

Received: 10/4/02

Delivery Date: 10/19/02

1099 P.O. #:

FS-MO-02-06 Release #:

SDG #: N/A

This is to certify that Teledyne Brown Engineering - Environmental Services located at 2508 Quality Lane, Knoxville, Tennessee, 37931, has analyzed, tested and documented samples as specified in the applicable purchase order.

This also certifies that requirements of applicable codes, standards and specifications have been fully met and that any quality assurance documentation which verified conformance to the purchase order is on file and may be examined upon request.

I hereby certify that the above statements are true and correct.

Operations Manager

Cross Reference Table

Client ID	Laboratory ID	TI#
HEM-8-3FT	L19308-1	80701
HEM-4-3FT	L19308-2	80702
HEM-6-3FT	L19308-3	80703
HEM-5-3FT	L19308-4	80704

TELEDYNE BROWN ENGINEERING

Client Sample ID: 80701

TCLP Metals

Lot-Sample #...: H2J080251-001 Matrix....: SOLID

	•						
		REPORTING				PREPARATION-	WORK
PARAMETER	RESULT	LIMIT	UNITS	METHO	<u> </u>	ANALYSIS DATE	ORDER #
Prep Batch #			4-				
Arsenic	ND		mg/L		6010B	10/16-10/17/02	E9K051AA
		Dilution Factor	r: 1	Analysis	Time: 11:09		
Barium	ND	10.0	mg/L	SW846	6010B	10/16-10/17/02	E9K051AC
	I	ilution Facto	•		Time: 11:09	_ , , , ,	
				•			
Cadmium	ND	0.10	mg/L	SW846	6010B	10/16-10/17/02	E9K051AD
	r	Dilution Factor	r: 1	Analysis	Time: 11:09		
			÷				
Chromium	ND	0.50	mg/L	SW846	6010B	10/16-10/17/02	E9K051AE
	Ľ	Dilution Factor	r: 1	Analysis	Time: 11:09		
Lead	ND	0.50	mg/L	SW846	6010B	10/16-10/17/02	R9K051AF
Dead		Oilution Factor			Time: 11:09	10/10 10/1//02	25K03211
	<u>-</u>	oritation racto.		10.02,013	***************************************		
Selenium	ND	0.25	mg/L	SW846	6010B	10/16-10/17/02	E9K051AG
	T.	Dilution Factor	r: 1	Analysis	Time: 11:09		
			•		•		
Silver	ממ ַ		mg/L		6010B	10/16-10/17/02	E9K051AH
	. E	Dilution Factor	r: 1	Analysis	Time; 11:09		
Prep Batch #	2290257						
Mercury	ND	0.0020	mg/L	SW846	7470A	10/17/02	E9K051AJ
-		ilution Factor			Time: 15:21	• • • • •	

Analysis performed in accordance with USEPA Toxicity Characteristic Leaching Procedure Method 1311

NOTE (S):

TELEDYNE BROWN ENGINEERING

Client Sample ID: 80702

TCLP Metals

Lot-Sample #...: H2J080251-002 Matrix....: SOLID

Date Sampled...: 09/22/02 Date Received..: 10/08/02 Leach Date....: 10/14/02 Leach Batch #..: P228702

		REPORTIN	r G			PREPARATION-	WORK
PARAMETER	RESULT	LIMIT	UNITS	METHOI	· · · · · · · · · · · · · · · · · · ·	ANALYSIS DATE	ORDER #
Prep Batch #	: 2288367						
Arsenic	ND	0.50	mg/L	SW846	6010B	10/16-10/17/02	E9K1A1AA
		Dilution Fac	tor: 1	Analysis	Time: 11:27		
Barium	ND	10.0	mg/L	SW846	6010B	10/16-10/17/02	E9K1A1AC
		Dilution Fac	tor: 1	Analysis	Time: 11:27		
Cadmium	ND	0.10	mg/L	SW846	6010B	10/16-10/17/02	E9K1A1AD
		Dilution Fac	tor: 1	Analysis	Time: 11:27		
Chromium	ND	0.50	mg/L	SW846	6010B	10/16-10/17/02	E9K1A1AE
		Dilution Fac	tor: 1	Analysis	Time: 11:27		
Lead	ND	0.50	mg/L	SW846	6010B	10/16-10/17/02	E9K1A1AF
		Dilution Fac	tor: 1	Analysis	Time: 11:27		
Selenium	ND	0.25	mg/L	SW846	6010B	10/16-10/17/02	E9K1A1AG
		Dilution Fac	tor: 1	Analysis	Time: 11:27		
Silver	ND	0.50	mg/L	SW846	6010B	10/16-10/17/02	E9K1A1AH
		Dilution Fac	tor: 1	Analysis	Time: 11:27		
Prep Batch #.		0.0000	/T	0140 A.C	74707	10/17/00	******************************
Mercury	ND	0.0020 Dilution Fac	mg/L	SW846	74 /UA Time: 15:23	10/17/02	E9K1A1AJ

NOTE(S):

Analysis performed in accordance with USEPA Toxicity Characteristic Leaching Procedure Method 1311

TELEDYNE BROWN KNGINKERING

Client Sample ID: 80703

TCLP Metals

Matrix....: SOLID

10/16-10/17/02 E9K1C1AH

Date Sampled...: 09/22/02 Date Received..: 10/08/02 Leach Date....: 10/14/02 Leach Batch #..: P228702 REPORTING PREPARATION-WORK METHOD ANALYSIS DATE ORDER # LIMIT UNITS PARAMETER RESULT Prep Batch #...: 2288367 SW846 6010B 10/16-10/17/02 E9K1C1AA Arsenic ND 0.50 mg/L Analysis Time..: 11:31 Dilution Factor: 1 SW846 6010B 10/16-10/17/02 E9K1C1AC mq/L ND 10.0 Barium Analysis Time..: 11:31 Dilution Factor: 1 0.10 mg/L SW846 6010B 10/16-10/17/02 E9K1C1AD Cadmium ND Analysis Time..: 11:31 Dilution Factor: 1 SW846 6010B 10/16-10/17/02 E9K1C1AE 0.50 mg/L Chromium ND Dilution Factor: 1 Analysis Time..: 11:31 0.50 mq/L SW846 6010B 10/16-10/17/02 E9K1C1AF Lead ND Dilution Factor: 1 Analysis Time.:: 11:31 SW846 6010B 10/16-10/17/02 E9K1C1AG 0.25 mg/L Selenium ND

Prep Batch #...: 2290257

ND

Lot-Sample #...: H2J080251-003

Mercury ND 0.0020 mg/L SW846 7470A 10/17/02 E9K1C1AJ

Dilution Factor: 1 Analysis Time..: 15:29

mg/L

Dilution Factor: 1

Dilution Factor: 1

0.50

Analysis Time..: 11:31

Analysis Time..: 11:31

SW846 6010B

NOTE(S):

Silver

Analysis performed in accordance with USEPA Toxicity Characteristic Leaching Procedure Method 1311

TELEDYNE BROWN ENGINEERING

Client Sample ID: 80704

TCLP Metals

Lot-Sample # Date Sampled Leach Date	.: 09/22/02	Date I	Received. Batch #			Matrix:	SOLID
PARAMETER	RESULT	REPORTING) UNITS	METHO:	Ď	PREPARATION- ANALYSIS DATE	WORK ORDER #
			-	(· 	
Prep Batch #	.: 2288367						
Arsenic	ND	0.50	mg/L		6010B	10/16-10/17/02	E9K1D1AA
		Dilution Fact	or: 1	Analysis	Time: 11:36		
Barium	ND	10.0	mq/L	SW846	6010B	10/16-10/17/02	E9K1D1AC
2012 2 2 2011	***	Dilution Fact	<u> </u>		Time: 11:36		
				•			
Cadmium	ND	0.10	mg/L	SW846	6010B	10/16-10/17/02	E9K1D1AD
		Dilution Fact	or: 1	Analysis	Time: 11:36		
Chromium	ND	0.50	mg/L	SW846	6010B	10/16-10/17/02	E9K1D1AE
CIII OMIZUM	112	Dilution Fact	-		Time: 11:36	,,,,	
Lead	ND	0.50	mg/L	SW846	6010B	10/16-10/17/02	E9K1D1AF
		Dilution Fact	or: 1	Analysis	Time: 11:36		
a. 3	ND	0.25	mg/L	CTAO A C	6010B	10/16-10/17/02	ROK1D1 AG
Selenium	טא	0.23 Dilution Fact	- -	•	Time: 11:36	10/16-10/1//02	EJKIDING
•		Dilución Facc	V 1	MINITYDIS	11		
Silver	ND	0.50	mg/L	SW846	6010B	10/16-10/17/02	E9K1D1AH
		Dilution Fact	or: 1	Analysis	Time: 11:36		
Prep Batch #: 2290257							
Mercury	ND	0.0020	mg/L	SW846	7470A	10/17/02	E9K1D1AJ
HET CUL Y	110	Dilution Fact			Time: 15:31	,,	

Analysis performed in accordance with USEPA Toxicity Characteristic Leaching Procedure Method 1311

METHOD BLANK REPORT

TCLP Metals

Client Lot #	: H2J080251			Matrix SO	LID
	J	REPORTING		PREPARATION-	WORK
PARAMETER	RESULT	LIMIT UNITS	METHOD	ANALYSIS DATE	ORDER #
MB Lot-Sample #		-133 Prep Batch # Leach Batch #.			
Arsenic	ND	0.50 mg/L Dilution Factor: 1 Analysis Time: 11:00	SW846 6010B	10/16-10/17/02	E90AW1AA
Barium	ND	10.0 mg/L	SW846 6010B	10/16-10/17/02	E90AW1AC
		Dilution Factor: 1 Analysis Time: 11:00			
Cadmium	ND	0.10 mg/L Dilution Factor: 1	SW846 6010B	10/16-10/17/02	E90AW1AD
		Analysis Time. : 11:00			
Chromium	ND	0.50 mg/L Dilution Factor: 1 Analysis Time: 11:00	SW846 6010B	10/16-10/17/02	E90AW1AE
Lead	ND	0.50 mg/L Dilution Factor: 1 Analysis Time: 11:00	SW846 6010B	10/16-10/17/02	E90AW1AF
Selenium	ND	0.25 mg/L Dilution Factor: 1 Analysis Time: 11:00	SW846 6010B	10/16-10/17/02	E90AW1AG
Silver	ND	0.50 mg/L Dilution Factor: 1 Analysis Time: 11:00	SW846 6010B	10/16-10/17/02	E90AW1AH
MB Lot-Sample : Leach Date Mercury		-133 Prep Batch # Leach Batch #. 0.0020 mg/L Dilution Factor: 1 Analysis Time: 15:17	.: P228702 SW846 7470A	10/17/02	E90AW1AJ

LABORATORY CONTROL SAMPLE EVALUATION REPORT

TCLP Metals

Client Lot #:	H2J080251			Matrix	: SOLID
PARAMETER	PERCENT RECOVERY		ETHOD	PREPARATION- ANALYSIS DATE	WORK ORDER #
LCS Lot-Sample#: Arsenic	H2 J 150000- 97	(80 - 120) SV	h #: 2288367 W846 6010B 10 Analysis		E925T1AA
Barium	93		W846 6010B 10 Analysis		E925T1AC
Cadmium	97		W846 6010B 10 Analysis		E925T1AD
Chromium	96 .	•	W846 6010B 10 Analysis		E925T1AE
Lead	98		W846 6010B 10 Analysis		E925T1AF
Selenium	95	•	W846 6010B 10 Analysis		E925T1AG
Silver	93	=	W846 6010B 10 Analysis		E925T1AH
LCS Lot-Sample#: Mercury	H2J170000-	(80 - 120) SV	h #: 2290257 W846 7470A 1 Analysis	10/17/02	E97A71AA

NOTE(S):

LABORATORY CONTROL SAMPLE DATA REPORT

TCLP Metals

Client Lot #	:: H2J	r080251			2	Aatrix:	SOLID
PARAMETER	SPIKE AMOUNT	MEASUR AMOUNT		PERCNT RECVRY	METHOD	PREPARATION- ANALYSIS DATE	WORK ORDER #
LCS Lot-Samp	le#: H2J	150000-	367 Prep Bat	ch #	: 2288367		
Arsenic	5.00	4.83	mg/L	97	SW846 6010B	10/16-10/17/02	E925T1AA
			Dilution Factor	: 10	Analysis Time: 1	L:05	
Barium	50.0	46.7	mg/L	93	SW846 6010B	10/16-10/17/02	E925T1AC
			Dilution Factor	: 10	Analysis Time: 1	L:05	
Cadmium	1.00	0.973	mg/L	97	SW846 6010B	10/16-10/17/02	E925T1AD
			Dilution Factor	: 10	Analysis Time: 1	1:05	
Chromium	5.00	4.80	mg/L	96	SW846 6010B	10/16-10/17/02	E925T1AE
			Dilution Factor	: 10	Analysis Time: 1	L:05	
Lead	5.00	4.88	mg/L	98	SW846 6010B	10/16-10/17/02	E925T1AF
			Dilution Factor		Analysis Time: 1:	1:05	
Selenium	1.00	0.954	mq/L	95	SW846 6010B	10/16-10/17/02	E925T1AG
			Dilution Factor		Analysis Time: 1:		
Silver	1.00	0.934	mg/L	93	SW846 6010B	10/16-10/17/02	E925T1AH
52574-		*****	Dilution Factor		Analysis Time: 13		
T.CS Lot-Sam		F1 70000~	257 Prep Bat	ch #.	• 2290257		
Mercury			2 mg/L		SW846 7470A	10/17/02	E97A71AA
	3,2 200	3.2.20	- -		Analysis Time: 19		

A Teledyne Technologies Company 2508 Quality Lane Knoxville, TN 37931-3133

US Ecology 109 Flint Road Oak Ridge TN 37830 Attn: Darrel Ray

Report of Analysis/Certificate of Conformance

11/20/02

LIMS #: L19691

Project ID#: US607-3EREGFS-02

Received: 11/12/02

Delivery Date: 11/15/02

P.O. #: 1099

Release #: FS-MO-02-06

SDG #: N/A

This is to certify that Teledyne Brown Engineering - Environmental Services located at 2508 Quality Lane, Knoxville, Tennessee, 37931, has analyzed, tested and documented samples as specified in the applicable purchase order.

This also certifies that requirements of applicable codes, standards and specifications have been fully met and that any quality assurance documentation which verified conformance to the purchase order is on file and may be examined upon request.

I hereby certify that the above statements are true and correct.

Keith Jeter ()

Operations Manager

A Teledyne Technologies Company 2508 Quality Lane Knoxville, TN 37931-3133

Cross Reference Table

	Cross rejerence rable	
Client ID	Laboratory ID	TI#
HEM 1 1FT.	L19691-1	83290
HEM 1 2FT.	L19691-2	83291
HEM 1 3FT.	L19691-3	83292
HEM 2 1FT.	L19691-4	83293
HEM 2 2FT.	L19691-5	83294
HEM 2 3FT.	L19691-6	83295
HEM 3 1FT.	L19691-7	83296
HEM 3 3FT.	L19691-8	83297
HEM 3 5FT.	L19691-9	83298
HEM 4 1FT.	L19691-10	83299
HEM 4 2FT.	L19691-11	83300
HEM 4 3FT.	L19691-12	83301
HEM 5 1FT.	L19691-13	83302
HEM 5 2FT.	L19691-14	83303
HEM 5 3FT.	L19691-15	83304
HEM 6 1FT.	L19691-16	83305
HEM 6 2FT.	L19691-17	83306
HEM 6 3FT.	L19691-18	83307
HEM 7 1FT.	L19691-19	83308
HEM 7 2FT.	L19691-20	83309
HEM 7 3FT.	L19691-21	83310
HEM 8 1FT.	L19691-22	83311
HEM 8 2FT.	L19691-23	83312
HEM 8 3FT.	L19691-24	83313
HEM 9 1FT.	L19691-25	83314
HEM 9 2FT.	L19691-26	83315
HEM 9 3FT.	L19691-27	83316
HEM 10 1FT.	L19691-28	83317
HEM 10 2FT.	L19691-29	83318
HEM 10 3FT.	L19691-30	83319
HEM 11 1FT.	L19691-31	83320
HEM 11 2FT.	L19691-32	83321
HEM 11 3FT.	L19691-33	83322
HEM 12 1FT.	L19691-34	83323
HEM 12 2FT.	L19691-35	83324
HEM 12 3FT.	L19691-36	83325

11/20/02 10:54:11AM



Darrel Ray

Sample ID: HEM 1 1FT.

L19691

Collect Start: 11/12/02 0:00

Station:

US Ecology

Collect Stop: Received: 11/12/02

Description: LIMS Number: L19691-1

(83290)

(83291)

US607-3EREGFS-02

Matrix: Solids (SD)

% Moisture:										Volu	me:		
Radionuclide	SOP#	Activity Conc	Uncertainty (2 Sigma)	MDC	Units	Aliquot Volume	Aliquot Units	Reference Date	Count Date	Count Time	Count Time Units	Flag	g Values
K-40	042-5	1.38E+001	1.11E+000	2.21E-001	pCi/G	303.000	G wet	11/12/02 12:00	11/13/02	6,000	Seconds	+	Yes
CS-137	042-5	9.96E-002	3.98E-002	1.90E-002	pCi/G	303.000	G wet	11/12/02 12:00	11/13/02	6,000	Seconds	+	Yes
RA-226	042-5	6.26E-001	7.21E-002	4.33E-001	pCi/G	303.000	G wet	11/12/02 12:00	11/13/02	6,000	Seconds	+	Yes
TH-232	042-5	7.17E-001	6.67E-002	6.25E-002	pCi/G	303.000	G wet	11/12/02 12:00	11/13/02	6,000	Seconds	+	Yes
U-235	042-5	9.59E-001	2.46E-001	1.34E-001	pCi/G	303.000	G wet	11/12/02 12:00	11/13/02	6,000	Seconds	+	Yes
U-238	042-5	3.14E+000	2.61E+000	3.53E+000	pCi/G	303.000	G wet	11/12/02 12:00		6,000	Seconds		No

Comments:

Sample ID: HEM 1 2FT.

L19691

Collect Start: 11/12/02 0:00

Station: Description:

US Ecology

Collect Stop: Received: 11/12/02

LIMS Number: L19691-2 9/ Moieture

US607-3EREGFS-02

Matrix: Solids (SD)

Volume

% Moisture:								<u> </u>		Volu	me:		
Radionuclide	SOP#	Activity Conc	Uncertainty (2 Sigma)	MDC	Units	Aliquot Volume	Aliquot Units	Reference Date	Count Date	Count Time	Count Time Units	Fla	g Values
K-40	042-5	1.32E+001	1.33E+000	2.48E-001	pCi/G	312.100	G WET	11/12/02 12:00	11/13/02	6,000	Seconds	_+	Yes
CS-137	042-5	4.28E-002	2.74E-002	3.67E-002	pCi/G	312.100	G WET	11/12/02 12:00	11/13/02	6,000	Seconds	*	No
RA-226	042-5	8.10E-001	8.27E-002	6.87E-001	pCi/G	312.100	G WET	11/12/02 12:00	11/13/02	6,000	Seconds	+	Yes
TH-232	042-5	7.20E-001	8.53E-002	7.49E-002	pCi/G	312.100	G WET	11/12/02 12:00	11/13/02	6,000	Seconds	+	Yes
U-235	042-5	2.79E+000	3.41E-001	2.27E-001	pCi/G	312.100	G WET	11/12/02 12:00	11/13/02	6,000	Seconds	+	Yes
U-238	042-5	4.77E+000	3.23E+000	4.54E+000	pCi/G	312.100	G WET	11/12/02 12:00	11/13/02	6,000	Seconds		No

Comments:

Flag Values

Activity concentration exceeds MDC and 3 sigma and peak identified(gamma only) Peak not identified, but forced activity concentration exceeds MDC and 3 sigma Activity concentration exceeds customer reporting value

High

MDC exceeds customer technical specification Spec

= Peak not identified in gamma spectrum No Peak identified in gamma spectrum Yes

ble v es re Bok xt in

1 of 21

11/20/02 10:54:42AM

L19691



Sample ID: HEM 1 3FT.

Station:

US Ecology Description: US607-3EREGFS-02 LIMS Number: L19691-3 (83292)

Collect Start: 11/12/02 0:00

Collect Stop:

Received: 11/12/02 Matrix: Solids (SD)

% Moisture:									_	Volu	me:			
Radionuclide	SOP#	Activity Conc	Uncertainty (2 Sigma)	MDC	Units	Aliquot Volume	Aliquot Units	Reference Date	Count Date	Count Time	Count Time Units	Fla	g Values	,
K-40	042-5	1.33E+001	1.22E+000	3.82E-001	pCi/G	340.100	G WET	11/12/02 12:00	11/13/02	6,000	Seconds	+		Yes
CS-137	042-5	5.02E-002	7.12E-002	5.11E-002	pCi/G	340.100	G WET	11/12/02 12:00	11/13/02	6,000	Seconds			Yes
RA-226	042-5	6.72E-001	7.45E-002	1.11E+000	pCi/G	340.100	G WET	11/12/02 12:00	11/13/02	6,000	Seconds			Yes
TH-232	042-5	6.46E-001	7.21E-002	1.29E-001	pCi/G	340.100	G WET	11/12/02 12:00	11/13/02	6,000	Seconds	+	1 1	Yes
U-235	042-5	1.63E+000	3.20E-001	3.58E-001	pCi/G	340.100	G WET	11/12/02 12:00	11/13/02	6,000	Seconds	+		Yes
U-238	042-5	9.28E+000	6.01E+000	4.70E+000	pCi/G	340.100	G WET	11/12/02 12:00	11/13/02	6,000	Seconds	+		Yes
U-233/234 (AS)	062-110	2.20E+001	2.90E+000	7.72E-002	pCi/g	0.501	g		11/17/02	60,003	seconds	+	1 1	
U-235 (AS)	062-110	9.48E-001	2.89E-001	2.74E-002	pCi/g	0.501	g		11/17/02	60,003	seconds	+		
U-238 (AS)	062-110	3.95E+000	6.83E-001	5.46E-002	pCi/g	0.501	و		11/17/02	60,003	seconds	+		

Comments:

4 				
Sample ID:	HEM 2 1FT.	L19691	Collect Start: 11/12/02	0:00
Station		617071	Collect Stop:	

US Ecology

Received: 11/12/02 Description: US607-3EREGFS-02 LIMS Number: L19691-4 Matrix: Solids (SD) (83293)

Moisture:							'			Volu	me:		
Radionuclide	SOP#	Activity Conc	Uncertainty (2 Sigma)	MDC	Units	Aliquot Volume	Aliquot Units	Reference Date	Count Date	Count Time	Count Time Units	Fla	g Values
K-40	042-5	1.72E+001	2.02E+000	5.85E-001	pCi/G	253.200	G WET	11/12/02 12:00	11/13/02	6,000	Seconds	+	Yes
CS-137	042-5	2.73E-002	6.25E-002	1.07E-001	pCi/G	253.200	G WET	11/12/02 12:00	11/13/02	6,000	Seconds		No
RA-226	042-5	8.09E-001	1.30E-001	2.02E+000	pCi/G	253,200	G WET	11/12/02 12:00	11/13/02	6,000	Seconds		Yes
TH-232	042-5	9.28E-001	1.15E-001	2.72E-001	pCi/G	253.200	G WET	11/12/02 12:00	11/13/02	6,000	Seconds	+	Yes
U-235	042-5	3.61E+000	5.69E-001	6.64E-001	pCi/G	253.200	G WET	11/12/02 12:00	11/13/02	6,000	Seconds	+	Yes

Flag Values

Activity concentration exceeds MDC and 3 sigma and peak identified(gamma only)

Peak not identified, but forced activity concentration exceeds MDC and 3 sigma Activity concentration exceeds customer reporting value

High MDC exceeds customer technical specification Spec

Peak not identified in gamma spectrum No Peak identified in gamma spectrum

Yes ext in " les re l'hable volum Bol

11/20/02 10:54:42AM



Seconds

Collect Start: 11/12/02 0:00

Seconds

Seconds

Seconds

+

+

No

Yes

Yes

No

Sample ID: HEM 2 1FT. Collect Start: 11/12/02 0:00 L19691 Station: Collect Stop: **US Ecology** Received: 11/12/02 Description: US607-3EREGFS-02 Matrix: Solids (SD) LIMS Number: L19691-4 (83293)% Moisture: Volume: Count Activity Count Uncertainty Aliquot Aliquot Reference Count Flag Values MDC Units Time SOP# Radionuclide Conc (2 Sigma) Volume Time Units Date Date Units

G WET

T 10401

11/12/02 12:00

11/12/02 12:00

11/12/02 12:00

11/12/02 12:00

11/13/02

11/13/02

11/13/02

11/13/02

6.000

6.000

6.000

6.000

253.200

Comments:

042-5

042-5

042-5

042 - 5

Sample ID: HEM 2 2FT.

3.95E+000

1.10E+000

8.60E+000

1.42E+000 | 3.82E-001

U-238

Station: Description: LIMS Number: % Moisture:	L19691-5	(83294)	<i>:</i>		. · · · · · · · · · · · · · · · · · · ·	τ	US Ecology 7-3EREGFS				ved: 11/12/ rix: Solids			
Radionuclide	SOP#	Activity Conc	Uncertainty (2 Sigma)	MDC	Units	Aliquot Volume	Aliquot Units	Reference Date	Count Date	Count Time	Count Time Units	Flag	y Values	
K-40	042-5	1.97E+001	1.70E+000	5.55E-001	pCi/G	259.800	G WET	11/12/02 12:00	11/13/02	6,000	Seconds	÷	Y	es
CS-137	042-5	7.33E-002	4.56E-002	8.59E-002	pCi/G	259.800	G WET	11/12/02 12:00	11/13/02	6,000	Seconds		N	<u>。</u>
RA-226	042-5	7.88E-001	9.69E-002	1.27E+000	pCi/G	259.800	G WET	11/12/02 12:00	11/13/02	6,000	Seconds		Y	es

259.800 | G WET

259.800 | G WET

259,800 G WET

Comments:

TH-232

U-235

U-238

Sample ID: Station: Description: LIMS Number: % Moisture:		r. (83295)				τ	19691 JS Ecology 7-3EREGFS			Collect Se Receiv	top: ved: 11/12/ rix: Solids	
Radionuclide	SOP#	Activity Conc	Uncertainty (2 Sigma)	MDC	Units	Aliquot Volume	Aliquot Units	Reference Date	Count Date	Count Time	Count Time Units	Flag Values

Flag Values

Activity concentration exceeds MDC and 3 sigma and peak identified(gamma only)

6.47E+000

1.07E-001

5.14E+000

1.14E+001

2.05E-001

4.12E-001

9.70E+000 pCi/G

pCi/G

pCi/G

pCi/G

Peak not identified, but forced activity concentration exceeds MDC and 3 sigma Activity concentration exceeds customer reporting value

High

MDC exceeds customer technical specification = Spec

Peak not identified in gamma spectrum No Peak identified in gamma spectrum == Yes

ble v s re Bole xt in

3 of 21

11/20/02 10:54:42AM



Sample ID: HEM 2 3FT.

L19691

Collect Start: 11/12/02 0:00

Station: Description:

US Ecology

Collect Stop: Received: 11/12/02

LIMS Number: L19691-6

Matrix: Solids (SD)

US607-3EREGFS-02

% Moisture:								·		Volu	ine:		
Radionuclide	SOP#	Activity Conc	Uncertainty (2 Sigma)	MDC	Units	Aliquot Volume	Aliquot Units	Reference Date	Count Date	Count Time	Count Time Units	Flaț	g Values
K-40	042-5	1.57E+001	1.40E+000	2.10E-001	pCi/G	300.000	G WET	11/12/02 12:00	11/13/02	6,000	Seconds	+	Yes
CS-137	042-5	2.19E-001	7.73E-002	3.44E-002	pCi/G	300.000	G WET	11/12/02 12:00	11/13/02	6,000	Seconds	+	Yes
RA-226	042-5	6.16E-001	9.78E-002	8.37E-001	pCi/G	300.000	G WET	11/12/02 12:00	11/13/02	6,000	Seconds		Yes
TH-232	042-5	7.17E-001	1.08E-001	9.44E-002	pCi/G	300.000	G WET	11/12/02 12:00	11/13/02	6,000	Seconds	+	Yes
U-235	042-5	4.53E+000	4.98E-001	2.73E-001	pCi/G	300.000	G WET	11/12/02 12:00	11/13/02	6,000	Seconds	+	Yes
U-238	042-5	6.64E+000	6.05E+000	3.21E+000	pCi/G	300.000	G WET	11/12/02 12:00		6,000	Seconds		Yes

Comments:

Sample ID: Station: Description: LIMS Number: % Moisture:	HEM 3 1F7	r. (83296)	.	ŧ	1 9691 JS Ecology -3EREGFS		Collect Start: 11/12 Collect Stop: Received: 11/12 Matrix: Solids Volume:	/02
		4 -41-14		1 .			l Count	ľ

% Moisture:										Volu	me:		
Radionuclide	SOP#	Activity Conc	Uncertainty (2 Sigma)	MDC	Units	Aliquot Volume	Aliquot Units	Reference Date	Count Date	Count Time	Count Time Units	Flag	y Values
K-40	042-5	1.71E+001	1.85E+000	2.53E-001	pCi/G	279.000	G WET	11/12/02 12:00	11/13/02	6,000	Seconds	+	Yes
CS-137	042-5	7.43E-002	5.76E-002	9.49E-002	pCi/G	279.000	G WET	11/12/02 12:00	11/13/02	6,000	Seconds		Yes
RA-226	042-5	8.83E-001	1.21E-001	1.65E+000	pCi/G	279.000	G WET	11/12/02 12:00	11/13/02	6,000	Seconds		Yes
TH-232	042-5	9.11E-001	1.00E-001	1.84E-001	pCi/G	279.000	G WET	11/12/02 12:00	11/13/02	6,000	Seconds	+	Yes
U-235	042-5	3.00E-001	3.39E-001	5.87E-001	pCi/G	279.000	G WET	11/12/02 12:00	11/13/02	6,000	Seconds		No
U-238	042-5	-1.03E+000	5.74E+000	9.36E+000	pCi/G	279.000	G WET	11/12/02 12:00	11/13/02	6.000	Seconds	· · · · ·	No

Comments:

Flag Values

Activity concentration exceeds MDC and 3 sigma and peak identified(gamma only) Peak not identified, but forced activity concentration exceeds MDC and 3 sigma Activity concentration exceeds customer reporting value

High

(83295)

MDC exceeds customer technical specification Spec

Peak not identified in gamma spectrum No Peak identified in gamma spectrum

xt inclines reportable value

**** Results are reported on an as received basis unless otherwise noted

11/20/02 10:54:42AM



Sample ID: HEM 3 3FT.

L19691

Collect Start: 11/12/02 0:00

Station:

US Ecology

Collect Stop:

Description:

Received: 11/12/02 Matrix: Solids (SD)

LIMS Number: L19691-8 (83297) US607-3EREGFS-02

% Moisture:										Volu	me:		
Radionuclide	SOP#	Activity Conc	Uncertainty (2 Sigma)	MDC	Units	Aliquot Volume	Aliquot Units	Reference Date	Count Date	Count Time	Count Time Units	Flag	g Values
K-40	042-5	1.66E+001	1.28E+000	3.95E-001	pCi/G	331.000	G WET	11/12/02 12:00	11/13/02	6,000	Seconds	+	Yes
CS-137	042-5	1.06E-001	4.79E-002	5.39E-002	pCi/G	331.000	G WET	11/12/02 12:00	11/13/02	6,000	Seconds	+	Yes
RA-226	042-5	9.40E-001	7.62E-002	1.07E+000	pCi/G	331.000	G WET	11/12/02 12:00	11/13/02	6,000	Seconds		Yes
TH-232	042-5	8.36E-001	7.19E-002	1.29E-001	pCi/G	331.000	G WET	11/12/02 12:00	11/13/02	6,000	Seconds	+	Yes
U-235	042-5	7.63E-001	3.15E-001	3.44E-001	pCi/G	331.000	G WET	11/12/02 12:00	11/13/02	6,000	Seconds	+	Yes
U-238	042-5	5.36E+000	3.36E+000	6.35E+000	pCi/G	331.000	G WET	11/12/02 12:00	11/13/02	6,000	Seconds		No

Comments:

Sample ID: HEM 3 5FT.

L19691

Collect Start: 11/12/02 0:00

Station:

US Ecology

Collect Stop: Received: 11/12/02

Description: LIMS Number: L19691-9

US607-3EREGFS-02

Matrix: Solids (SD)

0/ Moieture

(83298)

Volume

% Moisture:										<u>voiu</u>	me:		
Radionuclide	SOP#	Activity Conc	Uncertainty (2 Sigma)	MDC	Units	Aliquot Volume	Aliquot Units	Reference Date	Count Date	Count Time	Count Time Units	Fla	g Values
K-40	042-5	1.56E+001	1.21E+000	4.28E-001	pCi/G	309.500	G WET	11/12/02 12:00	11/13/02	6,000	Seconds	+	Yes
CS-137	042-5	-2.90E-003	2.64E-002	4.76E-002	pCi/G	309.500	G WET	11/12/02 12:00	11/13/02	6,000	Seconds		No
RA-226	042-5	6.21E-001	7.17E-002	1.05E+000	pCi/G	309.500	G WET	11/12/02 12:00	11/13/02	6,000	Seconds		Yes
TH-232	042-5	8.18E-001	7.83E-002	1.30E-001	pCi/G	309.500	G WET	11/12/02 12:00	11/13/02	6,000	Seconds	+	Yes
U-235	042-5	1.58E+000	2.89E-001	3.37E-001	pCi/G	309.500	G WET	11/12/02 12:00	11/13/02	6,000	Seconds	+	Yes
U-238	042-5	-2.00E-001	3.48E+000	6.31E+000	pCi/G	309.500	G WET	11/12/02 12:00	11/13/02	6,000	Seconds		No

Comments:

Flag Values

Activity concentration exceeds MDC and 3 sigma and peak identified(gamma only)

Peak not identified, but forced activity concentration exceeds MDC and 3 sigma Activity concentration exceeds customer reporting value High

MDC exceeds customer technical specification Spec

Peak not identified in gamma spectrum No

Peak identified in gamma spectrum Yes xt in " 'es re; ' ble v '---Bole

11/20/02 10:54:42AM



Sample ID: HEM 4 1FT.

L19691

Collect Start: 11/12/02 0:00

Station: Description:

US Ecology

Collect Stop: Received: 11/12/02

LIMS Number: L19691-10 (83299) US607-3EREGFS-02

Matrix: Solids (SD)

% Moisture:						Volume								
Radionuclide	SOP#	Activity Conc	Uncertainty (2 Sigma)	MDC	Units	Aliquot Volume	Aliquot Units	Reference Date	Count Date	Count Time	Count Time Units	Flag	g Values	
K-40	042-5	1.17E+001	9.31E-001	1.82E-001	pCi/G	352.600	G wet	11/12/02 12:00	11/13/02	6,000	Seconds	+	Yes	
CS-137	042-5	8.20E-002	3.30E-002	1.76E-002	pCi/G	352.600	G wet	11/12/02 12:00	11/13/02	6,000	Seconds	+	Yes_	
RA-226	042-5	5.11E-001	6.12E-002	5.04E-001	pCi/G	352.600	G wet	11/12/02 12:00	11/13/02	6,000	Seconds	+	Yes	
TH-232	042-5	6.15E-001	6.52E-002	5.29E-002	pCi/G	352.600	G wet	11/12/02 12:00	11/13/02	6,000	Seconds	+	Yes	
U-235	042-5	7.44E+000	3.54E-001	1.86E-001	pCi/G	352.600	G wet	11/12/02 12:00	11/13/02	6,000	Seconds	+	Yes	
U-238	042-5	7.55E+000	5.67E+000	2.01E+000	pCi/G	352.600	G wet	11/12/02 12:00	11/13/02	6,000	Seconds		Yes_	

Comments:

Sample ID:	HEM	4	2F	T.
0				

L19691

Collect Start: 11/12/02 0:00

Station:

US Ecology

Collect Stop:

Description: LIMS Number: L19691-11

(83300)

US607-3EREGFS-02

Received: 11/12/02 Matrix: Solids (SD)

Worsture: Volume											me:	e:				
Radionuclide	SOP#	Activity Conc	Uncertainty (2 Sigma)	MDC	Units	Aliquot Volume	Aliquot Units	Reference Date	Count Date	Count Time	Count Time Units	Flag Values				
K-40	042-5	1.58E+001	1.49E+000	2.00E-001	pCi/G	257.400	G WET	11/12/02 12:00	11/13/02	6,000	Seconds	+	Yes			
CS-137	042-5	4.14E-002	3.40E-002	4.37E-002	pCi/G	257.400	G WET	11/12/02 12:00	11/13/02	6,000	Seconds		No			
RA-226	042-5	6.84E-001	9.81E-002	8.83E-001	pCi/G	257.400	G WET	11/12/02 12:00	11/13/02	6,000	Seconds		Yes			
TH-232	042-5	8.50E-001	1.14E-001	8.49E-002	pCi/G	257.400	G WET	11/12/02 12:00	11/13/02	6,000	Seconds	+	Yes			
U-235	042-5	4.87E+000	8.86E-001	6.37E-001	pCi/G	257.400	G WET	11/12/02 12:00	11/13/02	6,000	Seconds	+	Yes			
U-238	042-5	4.06E+000	3.47E+000	4.83E+000	pCi/G	257.400	G WET	11/12/02 12:00	11/13/02	6,000	Seconds		No			

Comments:

Flag Values

Activity concentration exceeds MDC and 3 sigma and peak identified(gamma only) = Peak not identified, but forced activity concentration exceeds MDC and 3 sigma

Activity concentration exceeds customer reporting value High

MDC exceeds customer technical specification Spec

Peak not identified in gamma spectrum No Peak identified in gamma spectrum

" xt indicates reportable value

**** Results are reported on an as received basis unless otherwise noted

11/20/02 10:54:42AM



Sample ID: HEM 4 3FT.

Station:

Description:

LIMS Number: L19691-12

(83301)

(83302)

L19691

US Ecology

US607-3EREGFS-02

Collect Start: 11/12/02 0:00

Collect Stop:

Received: 11/12/02 Matrix: Solids (SD)

% Moisture:		•								Volu					
Radionuclide	SOP#	Activity Conc	Uncertainty (2 Sigma)	MDC	Units	Aliquot Volume	Aliquot Units	Reference Date	Count Date	Count Time	Count Flag Values				
K-40	042-5	7.63E+000	9.04E-001	2.94E-001	pCi/G	423.300	G WET	11/12/02 12:00	11/13/02	6,000	Seconds	+	Yes_		
CS-137	042-5	1.39E-002	2.43E-002	4.24E-002	pCi/G	423.300	G WET	11/12/02 12:00	11/13/02	6,000	Seconds		No		
RA-226	042-5	4.45E-001	6.02E-002	8.25E-001	pCi/G	423.300	G WET	11/12/02 12:00	11/13/02	6,000	Seconds		Yes		
TH-232	042-5	4.08E-001	5.40E-002	1.16E-001	pCi/G	423.300	G WET	11/12/02 12:00	11/13/02	6,000	Seconds	+	Yes		
U-235	042-5	6.81E-001	3.47E-001	3.41E-001	pCi/G	423.300	G WET	11/12/02 12:00	11/13/02	6,000	Seconds	+	Yes		
U-238	042-5	5.00E+000	2.93E+000	5.63E+000	pCi/G	423,300	G WET	11/12/02 12:00	11/13/02	6,000	Seconds		No		

Comments:

Sample ID:	HEM 5 1FT.

Station:

Description:

LIMS Number: 1.19691-13

L19691 US Ecology

US607-3EREGFS-02

Collect Start: 11/12/02 0:00

Collect Stop:

Received: 11/12/02 Matrix: Solids (SD)

% Moisture: Volume:														
Radionuclide	SOP#	Activity Conc	Uncertainty (2 Sigma)	MDC	Units	Aliquot Volume	Aliquot Units	Reference Date	Count Count Time Flag Va Date Time Units					
K-40	042-5	1.73E+001	1.84E+000	6.49E-001	pCi/G	261.800	G WET	11/12/02 12:00	11/13/02	6,000	Seconds	+		Yes
CS-137	042-5	8.91E-003	6.07E-002	1.01E-001	pCi/G	261.800	G WET	11/12/02 12:00	11/13/02	6,000	Seconds	··		No
RA-226	042-5	9.59E-001	1.15E-001	1.68E+000	pCi/G	261.800	G WET	11/12/02 12:00	11/13/02	6,000	Seconds	·-		Yes
TH-232	042-5	8.74E-001	1.09E-001	2.28E-001	pCi/G	261.800	G WET	11/12/02 12:00	11/13/02	6,000	Seconds	+	1	Yes
U-235	042-5	8.28E-001	3.98E-001	5.44E-001	pCi/G	261.800	G WET	11/12/02 12:00	11/13/02	6,000	Seconds	+	<u> </u>	Yes
U-238	042-5	6.96E+000	6.45E+000	1.18E+001	pCi/G	261.800	G WET	11/12/02 12:00	11/13/02	6,000	Seconds			No

Comments:

Flag Values

Activity concentration exceeds MDC and 3 sigma and peak identified(gamma only) Peak not identified, but forced activity concentration exceeds MDC and 3 sigma Activity concentration exceeds customer reporting value

High MDC exceeds customer technical specification

Spec Peak not identified in gamma spectrum No

Peak identified in gamma spectrum Yes Bolded text indicates reportable value.

7 of 21

11/20/02 10:54:42AM



A Teledyne Technologies Company

Sample ID: HEM 5 2FT.

L19691

Collect Start: 11/12/02 0:00

Station:

US Ecology

Collect Stop: Received: 11/12/02

Description:

LIMS Number: L19691-14 (83303) US607-3EREGFS-02

Matrix: Solids (SD)

% Moisture:													
Radionuclide	SOP#	Activity Conc	Uncertainty (2 Sigma) MDC Units Aliquot Aliquot Reference Count Volume Units Date Date					Count Time	Count Time Units	Flag Values			
K-40	042-5	9.69E+000	1.02E+000	4.11E-001	pCi/G	342.000	G WET	11/12/02 12:00	11/13/02	6,000	Seconds	+	Yes
CS-137	042-5	5.92E-002	3.53E-002	6.67E-002	pCi/G	342.000	G WET	11/12/02 12:00	11/13/02	6,000	Seconds		No
RA-226	042-5	4.57E-001	6.97E-002	9.23E-001	pCi/G	342.000	G WET	11/12/02 12:00	11/13/02	6,000	Seconds		Yes
TH-232	042-5	4.99E-001	5.92E-002	1.48E-001	pCi/G	342.000	G WET	11/12/02 12:00	11/13/02	6,000	Seconds	+	Yes
U-235	042-5	3.92E+000	3.29E-001	3.68E-001	pCi/G	342.000	G WET	11/12/02 12:00	11/13/02	6,000	Seconds	+	Yes
U-238	042-5	9.55E+000	6.59E+000	4.87E+000	pCi/G	342.000	G WET	11/12/02 12:00	11/13/02	6,000	Seconds		Yes

Comments:

Sample ID: HEM 5 3FT.

L19691

Collect Start: 11/12/02 0:00

Station:

US Ecology

Collect Stop:

Description: LIMS Number: L19691-15

(83304)

US607-3EREGFS-02

Received: 11/12/02 Matrix: Solids (SD)

% Moisture:	SOP#	Activity Conc	Uncertainty (2 Sigma)	MDC	Units	Aliquot Volume	Aliquot Units	Reference Date	Count Date	Count Time	me: Count Time Units	Flag Values	
SAMPLE	NOT RECEIVED												

Aliquot

Volume

Units

Comments:

Sample ID: HEM 61FT.

L19691

Collect Start: 11/12/02 0:00

Station: Description:

Collect Stop:

Count

Date

Reference

Date

Received: 11/12/02 Matrix: Solids (SD)

LIMS Number: L19691-16

(83305)

Conc

US Ecology US607-3EREGFS-02

L	%	Moisture:
Γ		

Activity SOP# Radionuclide

Aliquot

Units

Volume:

YOIU	111C.	
Count Time	Count Time Units	Flag Values

Flag Values

Activity concentration exceeds MDC and 3 sigma and peak identified(gamma only)

Uncertainty

(2 Sigma)

MDC

Peak not identified, but forced activity concentration exceeds MDC and 3 sigma Activity concentration exceeds customer reporting value High

MDC exceeds customer technical specification Spec

Peak not identified in gamma spectrum Peak identified in gamma spectrum

Bolded text indicates reportable value

**** Results are reported on an as received basis unless otherwise noted

11/20/02 10:54:42AM



Sample ID: HEM 6 1FT.

Station:

Description:

LIMS Number: L19691-16

(83305)

(83306)

L19691

US Ecology

US607-3EREGFS-02

Collect Start: 11/12/02 0:00

Collect Stop:

Received: 11/12/02 Matrix: Solids (SD)

% Moisture: Volume:													
Radionuclide	SOP#	Activity Cone	Uncertainty (2 Sigma)	MDC	Units	Aliquot Volume	Aliquot Units	Reference Nate	Count Date	Count Time	t Count Flag Values		
K-40	042-5	1.21E+001	1.36E+000	2.54E-001	pCi/G	272.200	G WET	11/12/02 12:00	11/13/02	6,000	Seconds	+	Yes
CS-137	042-5	1.63E-002	2.71E-002	3.50E-002	pCi/G	272.200	G WET	11/12/02 12:00	11/13/02	6,000	Seconds		No
RA-226	042-5	4.96E-001	9.75E-002	6.77E-001	pCi/G	272.200	G WET	11/12/02 12:00	11/13/02	6,000	Seconds		Yes
TH-232	042-5	5.86E-001	1.20E-001	8.21E-002	pCi/G	272.200	G WET	11/12/02 12:00	11/13/02	6,000	Seconds	+	Yes
U-235	042-5	6.68E-001	3.72E-001	2.24E-001	pCi/G	272.200	G WET	11/12/02 12:00	11/13/02	6,000	Seconds	+	Yes
U-238	042-5	1.42E+000	3.62E+000	4.47E+000	pCi/G	272.200	G WET	11/12/02 12:00	11/13/02	6,000	Seconds		No

Comments:

Sample ID:	HEM 6 2FT.	
------------	------------	--

Station:

Description:

LIMS Number: L19691-17

L19691

US Ecology

US607-3EREGFS-02

Collect Start: 11/12/02 0:00

Collect Stop:

Received: 11/12/02 Matrix: Solids (SD)

% Moisture:		(05500)								Volu	me:		
Radionuclide	SOP#	Activity Conc	Uncertainty (2 Sigma)	MDC	Units	Aliquot Volume	Aliquot Units	Reference Date	Count Date	Count Time	Count Time Units	Flag	g Values
K-40	042-5	1.02E+001	1.35E+000	4.85E-001	pCi/G	269.700	G WET	11/12/02 12:00	11/13/02	6,000	Seconds	+	Yes
CS-137	042-5	1.15E-001	6.72E-002	8.24E-002	pCi/G	269.700	G WET	11/12/02 12:00	11/13/02	6,000	Seconds	+	Yes
RA-226	042-5	7.74E-001	9.94E-002	1.78E+000	pCi/G	269.700	G WET	11/12/02 12:00	11/13/02	6,000	Seconds		Yes
TH-232	042-5	5.39E-001	9.30E-002	1.87E-001	pCi/G	269.700	G WET	11/12/02 12:00	11/13/02	6,000	Seconds	+	Yes
U-235	042-5	3.90E+000	5.71E-001	6.21E-001	pCi/G	269.700	G WET	11/12/02 12:00	11/13/02	6,000	Seconds	+	Yes
U-238	042-5	8.45E+000	8.74E+000	5.53E+000	pCi/G	269.700	G WET	11/12/02 12:00	11/13/02	6,000	Seconds		Yes

Comments:

Flag Values

Activity concentration exceeds MDC and 3 sigma and peak identified(gamma only) Peak not identified, but forced activity concentration exceeds MDC and 3 sigma Activity concentration exceeds customer reporting value

High

MDC exceeds customer technical specification Spec

Peak not identified in gamma spectrum No Peak identified in gamma spectrum

Bolded text indicates reportable value.

**** Results are reported on an as received basis unless otherwise noted

11/20/02 10:54:42AM



Collect Start: 11/12/02 0:00 Sample ID: HEM 6 3FT. L19691 Collect Stop: Station: US Ecology Received: 11/12/02 Description: US607-3EREGFS-02 Matrix: Solids (SD) LIMS Number: L19691-18 (83307)Volume: % Moisture: Count Activity Uncertainty Aliquot Aliquot Reference Count Count Flag Values MDC Units Time SOP# Radionuclide Conc (2 Sigma) Volume Units Date Date Time Units NOT RECEIVED SAMPLE

Comments:

Sample ID: HEM 7 1FT. Station:

Description:

LIMS Number: L19691-19

(83308)

1.19691

US Ecology

US607-3EREGFS-02

Collect Start: 11/12/02 0:00

Collect Stop:

Received: 11/12/02 Matrix: Solids (SD)

% Moisture:										Volu	me:		
Radionuclide	SOP#	Activity Conc	Uncertainty (2 Sigma)	MDC	Units	Aliquot Volume	Aliquot Units	Reference Date	Count Date	Count Time	Count Time Units	Fla	g Values
K-40	042-5	9.55E+000	9.81E-001	3.86E-001	pCi/G	350.500	G WET	11/12/02 12:00	11/13/02	6,000	Seconds	+	Yes
CS-137	042-5	9.87E-002	6.16E-002	4.22E-002	pCi/G	350.500	G WET	11/12/02 12:00	11/13/02	6,000	Seconds	+	Yes
RA-226	042-5	8.07E-001	7.09E-002	1.16E+000	pCi/G	350.500	G WET	11/12/02 12:00	11/13/02	6,000	Seconds		Yes
TH-232	042-5	5.86E-001	6.23E-002	1.36E-001	pCi/G	350.500	G WET	11/12/02 12:00	11/13/02	6,000	Seconds	+	Yes
U-235	042-5	3.32E+000	3.49E-001	3.78E-001	pCi/G	350.500	G WET	11/12/02 12:00	11/13/02	6,000	Seconds	+	Yes
U-238	042-5	7.21E+000	5.99E+000	4.69E+000	pCi/G	350.500	G WET	11/12/02 12:00	11/13/02	6,000	Seconds		Yes

Comments:

Sample ID: HEM 7 2FT.

Station:

Description:

LIMS Number: L19691-20

(83309)

L19691

US Ecology

US607-3EREGFS-02

Collect Start: 11/12/02 0:00

Collect Stop:

Received: 11/12/02 Matrix: Solids (SD)

Volume:

% (VIOISTURE:										YOLU	nt.	
Radionuclide	SOP#	Activity Conc	Uncertainty (2 Sigma)	MDC	Units	Aliquot Volume	Aliquot Units	Reference Date	Count Date	Count Time	Count Time Units	Flag Values

Flag Values

Activity concentration exceeds MDC and 3 sigma and peak identified(gamma only)

Peak not identified, but forced activity concentration exceeds MDC and 3 sigma Activity concentration exceeds customer reporting value

High MDC exceeds customer technical specification Spec

Peak not identified in gamma spectrum No Peak identified in gamma spectrum Yes

Bolded text indicates reportable value.

Results are reported on an as received basis unless otherwise noted

11/20/02 10:54:42AM



A Teledyne Technologies Company

Sample ID: HEM 7 2FT.

L19691

Collect Start: 11/12/02 0:00

Station:

US Ecology

Collect Stop: Received: 11/12/02

Description:

LIMS Number: L19691-20 (83309) US607-3EREGFS-02

Matrix: Solids (SD)

% Moisture:		(32277)								Volu	me:		
Radionuclide	SOP#	Activity Conc	Uncertainty (2 Sigma)	MDC	Units	Aliquot Volume	Aliquot Units	Reference Date	Count Date	Count Time	Count Time Units	Flag	Values
K-40	042-5	1.58E+001	1.16E+000	3.87E-001	pCi/G	324.900	G WET	11/12/02 12:00	11/13/02	6,000	Seconds	+	Yes
CS-137	042-5	9.30E-002	3.96E-002	5.53E-002	pCi/G	324.900	G WET	11/12/02 12:00	11/13/02	6,000	Seconds	+	Yes
RA-226	042-5	8.18E-001	7.09E-002	1.18E+000	pCi/G	324.900	G WET	11/12/02 12:00	11/13/02	6,000	Seconds		Yes
TH-232	042-5	8.29E-001	7.90E-002	1.39E-001	pCi/G	324.900	G WET	11/12/02 12:00	11/13/02	6,000	Seconds	+	Yes
U-235	042-5	3.25E+000	3.42E-001	3.80E-001	pCi/G	324.900	G WET	11/12/02 12:00	11/13/02	6,000	Seconds	+	Yes
U-238	042-5	1.14E+001	4.64E+000	5.70E+000	pCi/G	324.900	G WET	11/12/02 12:00	11/13/02	6,000	Seconds	+	Yes
U-233/234 (AS)	062-110	4.42E+001	4.03E+000	4.34E-002	pCi/g	0.593	g		11/17/02	60,003	seconds	+	
U-235 (AS)	062-110	1.59E+000	2.71E-001	1.26E-002	pCi/g	0.593	g .		11/17/02	60,003	seconds	+	
U-238 (AS)	062-110	6.16E+000	6.80E-001	4.34E-002	pCi/g	0.593	g		11/17/02	60,003	seconds	+	<u> </u>

Comments:

Sample ID: H	EM 7	3FT.
--------------	------	------

1.19691

Collect Start: 11/12/02 0:00 Collect Stop:

Station:

US Ecology

Received: 11/12/02

Description:

Matrix: Solids (SD)

LIMS Number: L19691-21 (83310) US607-3EREGFS-02

% Moisture:								·		Volu	me:		
Radionuclide	SOP#	Activity Conc	Uncertainty (2 Sigma)	MDC	Units	Aliquot Volume	Aliquot Units	Reference Date	Count Date	Count Time	Count Time Units	Flag	y Values
K-40	042-5	1.71E+001	1.19E+000	1.79E-001	pCi/G	327.900	G wet	11/12/02 12:00	11/13/02	6,000	Seconds	+	Yes
CS-137	042-5	1.70E-002	2.28E-002	2.84E-002	pCi/G	327.900	G wet	11/12/02 12:00	11/13/02	6,000	Seconds		No_
RA-226	042-5	5.98E-001	6.56E-002	4.60E-001	pCi/G	327.900	G wet	11/12/02 12:00	11/13/02	6,000	Seconds	+	Yes
TH-232	042-5	7.59E-001	7.16E-002	5.93E-002	pCi/G	327.900	G wet	11/12/02 12:00	11/13/02	6,000	Seconds	+	Yes
U-235	042-5	1.41E+000	2.47E-001	1.27E-001	pCi/G	327.900	G wet	11/12/02 12:00	11/13/02	6,000	Seconds	+	Yes

Flag Values

Activity concentration exceeds MDC and 3 sigma and peak identified(gamma only)

Peak not identified, but forced activity concentration exceeds MDC and 3 sigma Activity concentration exceeds customer reporting value High

MDC exceeds customer technical specification Spec

Peak not identified in gamma spectrum Peak identified in gamma spectrum

Bolded text indicates reportable value.

11/20/02 10:54:42AM



Sample ID: HEM 7 3FT. Collect Start: 11/12/02 0:00 L19691 Station: Collect Stop: **US Ecology** Received: 11/12/02 Description: US607-3EREGFS-02 Matrix: Solids (SD) LIMS Number: L19691-21 (83310) % Moisture: Volume: Count Activity Uncertainty Aliquot Aliquot Count Reference Count Flag Values MDC Units Time SOP# Radionuclide Conc (2 Sigma) Volume Units Date Time Date Units U-238 3.58E+000 pCi/G 042-5 3.92E+000 2.62E+000 327,900 G wet 11/13/02 Seconds 11/12/02 12:00 6.000 No U-233/234 (AS) 9.37E-002 062-110 4.18E+001 4.62E+000 pCi/g 0.555 11/17/02 seconds + g 60,004 U-235 (AS) 6.68E-002 pCi/g 3.18E-001 062-110 1.46E+000 0.555 g 11/17/02 60,004 seconds + 6.62E-002 pCi/g U-238 (AS) 062-110 6.87E-001 4.87E+000 0.555 g 11/17/02 60.004 seconds ÷

Comments:

Sample ID: Station: Description: LIMS Number: % Moisture:						τ	1 9691 JS Ecology 7-3EREGFS			Collect Start: 11/12/02 0:00 Collect Stop: Received: 11/12/02 Matrix: Solids (SD) Volume:				
Radionuclide	SOP#	Activity Conc	Uncertainty (2 Sigma)	Sigma) Volume Units Date Date Time Units									, Values	
K-40	042-5	1.63E+001	1.50E+000	3.10E-001	pCi/G	275.500	G WET	11/12/02 12:00	11/13/02	6,000	Seconds	+	Yes	
CS-137	042-5	3.92E-002	3.65E-002	4.54E-002	pCi/G	275.500	G WET	11/12/02 12:00	11/13/02	6,000	Seconds		No	
RA-226	042-5	6.96E-001	9.02E-002	7.76E-001	pCi/G	275.500	G WET	11/12/02 12:00	11/13/02	6,000	Seconds		Yes	
TH-232	042-5	7.40E-001	8.24E-002	9.32E-002	pCi/G	275.500	G WET	11/12/02 12:00	11/13/02	6,000	Seconds	+	Yes	
U-235	042-5	2.82E+000	4.15E-001	2.39E-001	pCi/G	275.500	G WET	11/12/02 12:00	11/13/02	6,000	Seconds	+_	Yes	
U-238	042-5	2.47E+000	3.93E+000	5.08E+000	pCi/G	275.500	G WET	11/12/02 12:00	11/13/02	6,000	Seconds		No	

Comments:

Flag Values

Activity concentration exceeds MDC and 3 sigma and peak identified(gamma only) Peak not identified, but forced activity concentration exceeds MDC and 3 sigma Activity concentration exceeds customer reporting value =

High

MDC exceeds customer technical specification Spec

Peak not identified in gamma spectrum No == = Peak identified in gamma spectrum

Bolded text indicates reportable value.

**** Results are reported on an as received basis unless otherwise noted

11/20/02 10:54:42AM



A Teledyne Technologies Company

Sample ID: HEM 8 2FT.

Station:

Description:

LIMS Number: L19691-23

(83312)

L19691

US Ecology

US607-3EREGFS-02

Collect Start: 11/12/02 0:00

Collect Stop:

Received: 11/12/02 Matrix: Solids (SD)

% Moisture:		(03312)								Volu	me:		
Radionuclide	SOP#	Activity Conc	Uncertainty (2 Sigma)	MDC	Units	Aliquot Volume	Aliquot Units	Reference Date	Count Date	Count Time	Count Time Units	Fla	g Values
K-40	042-5	1.76E+001	1.52E+000	4.87E-001	pCi/G	308.400	G WET	11/12/02 12:00	11/13/02	6,000	Seconds	+	Yes
CS-137	042-5	-2.64E-002	3.85E-002	5.96E-002	pCi/G	308.400	G WET	11/12/02 12:00	11/13/02	6,000	Seconds		No
RA-226	042-5	7.06E-001	8.62E-002	1.25E+000	pCi/G	308.400	G WET	11/12/02 12:00	11/13/02	6,000	Seconds		Yes
TH-232	042-5	1.00E+000	8.65E-002	1.94E-001	pCi/G	308.400	G WET	11/12/02 12:00	11/13/02	6,000	Seconds	+	Yes
U-235	042-5	8.60E-001	3.55E-001	3.67E-001	pCi/G	308.400	G WET	11/12/02 12:00	11/13/02	6,000	Seconds	+	Yes
U-238	042-5	3.88E+000	4.14E+000	7.39E+000	pCi/G	308.400	G WET	11/12/02 12:00	11/13/02	6,000	Seconds		No
U-233/234 (AS)	062-110	1.43E+001	1.85E+000	2.00E-002	pCi/g	0.508	g		11/17/02	60,001	seconds	+	
U-235 (AS)	062-110	5.03E-001	1.92E-001	2.47E-002	pCi/g	0.508	g		11/17/02	60,001	seconds	+	1 1
U-238 (AS)	062-110	1.75E+000	3.67E-001	2.00E-002	pCi/g	0.508	g		11/17/02	60,001	seconds	+	

Comments:

Sample ID:	HEM 8 3FT.
Ctutions	

Station:

Description: LIMS Number: L19691-24

(83313)

L19691

US Ecology

US607-3EREGFS-02

Collect Start: 11/12/02 0:00

Collect Stop:

Received: 11/12/02 Matrix: Solids (SD)

% Moisture:										Volu	me:		
Radionuclide	SOP#	Activity Conc	Uncertainty (2 Sigma)	MDC	Units	Aliquot Volume	Aliquot Units	Reference Date	Count Date	Count Time	Count Time Units	Flag	y Values
K-40	042-5	1.89E+001	1.95E+000	6.97E-001	pCi/G	268.600	G WET	11/12/02 12:00	11/13/02	6,000	Seconds	+	Yes
CS-137	042-5	2.01E-002	5.54E-002	9.43E-002	pCi/G	268.600	G WET	11/12/02 12:00	11/13/02	6,000	Seconds		No
RA-226	042-5	8.29E-001	1.24E-001	1.59E+000	pCi/G	268.600	G WET	11/12/02 12:00	11/13/02	6,000	Seconds		Yes
TH-232	042-5	9.69E-001	1.15E-001	2.35E-001	pCi/G	268.600	G WET	11/12/02 12:00	11/13/02	6,000	Seconds	+	Yes
U-235	042-5	1.15E+000	6.44E-001	5.00E-001	pCi/G	268.600	G WET	11/12/02 12:00	11/13/02	6,000	Seconds	+	Yes

Flag Values

Activity concentration exceeds MDC and 3 sigma and peak identified(gamma only)

Peak not identified, but forced activity concentration exceeds MDC and 3 sigma Activity concentration exceeds customer reporting value High

MDC exceeds customer technical specification Spec

Peak not identified in gamma spectrum No Peak identified in gamma spectrum Yes

Bolded text indicates reportable value.

**** Results are reported on an as received basis unless otherwise noted

11/20/02 10:54:42AM



Seconds

No

Collect Start: 11/12/02 0:00 Sample ID: HEM 8 3FT. L19691 Station: Collect Stop: **US Ecology** Received: 11/12/02 Description: US607-3EREGFS-02 LIMS Number: L19691-24 Matrix: Solids (SD) (83313) % Moisture: Volume: Count Activity Uncertainty Aliquot Count Aliquot Count Reference Flag Values MDC Units Time SOP# Radionuclide Conc (2 Sigma) Volume Units Date Time Date Units

268.600

G WET

11/12/02 12:00

11/13/02

6.000

C	 	nte.

042-5

-9.00E-001

U-238

Sample ID: Station: Description: LIMS Number: % Moisture:						τ	1 9691 JS Ecology 7-3EREGFS			Collect S Receiv	ved: 11/12/0 trix: Solids	02	0
Radionuclide	SOP#	Activity Conc	Uncertainty (2 Sigma)	MDC	Units	Aliquot Volume	Aliquot Units	Reference Date	Count Date	Count Time	Count Time Units	Fla	g Values
K-40	042-5	1.11E+001	1.04E+000	3.97E-001	pCi/G	354.400	G WET	11/12/02 12:00	11/13/02	6,000	Seconds	+	Yes
CS-137	042-5	8.41E-002	4.73E-002	4.96E-002	pCi/G	354.400	G WET	11/12/02 12:00	11/13/02	6,000	Seconds	+	Yes
RA-226	042-5	7.63E-001	7.62E-002	1.27E+000	pCi/G	354.400	G WET	11/12/02 12:00	11/13/02	6,000	Seconds		Yes
TH-232	042-5	5.46E-001	7.41E-002	1.48E-001	pCi/G	354.400	G WET	11/12/02 12:00	11/13/02	6,000	Seconds	+	Yes
U-235	042-5	6.31E+000	4.16E-001	4.36E-001	pCi/G	354.400	G WET	11/12/02 12:00	11/13/02	. 6,000	Seconds	+ .	Yes
U-238	042-5	3.05E+001	6.87E+000	5.22E+000	pCi/G	354.400	G WET	11/12/02 12:00	11/13/02	6,000	Seconds	+	Yes

Comments:

Sample ID: Station: Description: LIMS Number: % Moisture:	HEM 9 2F L19691-26					Į	19691 JS Ecology 7-3EREGFS	-02		Collect St Receiv	top: ved: 11/12/ trix: Solids	
Radionuclide	SOP#	Activity Cone	Uncertainty (2 Sigma)	MDC	Units	Aliquot Volume	Aliquot Units	Reference Date	Count Date	Count Time	Count Time Units	Flag Values

Flag Values

Activity concentration exceeds MDC and 3 sigma and peak identified(gamma only) Peak not identified, but forced activity concentration exceeds MDC and 3 sigma Activity concentration exceeds customer reporting value

5.79E+000

9.47E+000 pCi/G

High

MDC exceeds customer technical specification Spec

Peak not identified in gamma spectrum No

Peak identified in gamma spectrum Yes

Bolded text indicates reportable value.

**** Results are reported on an as received basis unless otherwise noted

11/20/02 10:54:42AM



Sample ID: HEM 9 2FT.

Station:

Description:

LIMS Number: L19691-26

L19691

US Ecology

US607-3EREGFS-02

Collect Start: 11/12/02 0:00

Collect Stop:

Received: 11/12/02 Matrix: Solids (SD)

% Moisture:										Volu	me:		
Radionuclide	SOP#	Activity Conc	Uncertainty (2 Sigma)	MDC	Units	Aliquot Volume	Aliquot Units	Reference Date	Count Date	Count Time	Count Time Units	Flaş	g Values
K-40	042-5	9.84E+000	1.21E+000	2.91E-001	pCi/G	336.300	G WET	11/12/02 12:00	11/13/02	6,000	Seconds	+	Yes
CS-137	042-5	2.41E-002	3.08E-002	3.95E-002	pCi/G	336.300	G WET	11/12/02 12:00	11/13/02	6,000	Seconds		No
RA-226	042-5	7.72E-001	9.53E-002	7.90E-001	pCi/G	336.300	G WET	11/12/02 12:00	11/13/02	6,000	Seconds		l l Yes
TH-232	042-5	5.07E-001	8.24E-002	7.84E-002	pCi/G	336.300	G WET	11/12/02 12:00	11/13/02	6,000	Seconds	4-	Yes
U-235	042-5	6.47E+000	4.83E-001	2.85E-001	pCi/G	336.300	G WET	11/12/02 12:00	11/13/02	6,000	Seconds	+	Yes
U-238	042-5	3.35E+001	7.85E+000	2.53E+000	pCi/G	336.300	G WET	11/12/02 12:00	11/13/02	6,000	Seconds	+	Yes

Comments:

Sample ID: HEM 9 3FT.

Station:

Description:

LIMS Number: L19691-27

L19691

US Ecology

US607-3EREGFS-02

Collect Start: 11/12/02 0:00

Collect Stop:

Received: 11/12/02 Matrix: Solids (SD)

% Moisture:										Volu	me:		
Radionuclide	SOP#	Activity Conc	Uncertainty (2 Sigma)	MDC	Units	Aliquot Volume	Aliquot Units	Reference Date	Count Date	Count Time	Count Time Units	Flag	Values
K-40	042-5	1.55E+001	1.75E+000	6.02E-001	pCi/G	343.400	G WET	11/12/02 12:00	11/13/02	6,000	Seconds	+	Yes
CS-137	042-5	1.96E-003	4.61E-002	7.60E-002	pCi/G	343.400	G WET	11/12/02 12:00	11/13/02	6,000	Seconds		No
RA-226	042-5	9.56E-001	1.04E-001	1.47E+000	pCi/G	343.400	G WET	11/12/02 12:00	11/13/02	6,000	Seconds		Yes
TH-232	042-5	8.17E-001	8.99E-002	1.83E-001	pCi/G	343.400	G WET	11/12/02 12:00		6,000	Seconds	+ 1	Yes
U-235	042-5	6.72E-001	4.00E-001	4.79E-001	pCi/G	343.400	G WET	11/12/02 12:00	11/13/02	6,000	Seconds	+	Yes
U-23 8	042-5	3.75E+000	6.21E+000	6.21E+000	pCi/G	343.400	G WET	11/12/02 12:00		6,000	Seconds		Yes

Comments:

Flag Values

Activity concentration exceeds MDC and 3 sigma and peak identified(gamma only)

Peak not identified, but forced activity concentration exceeds MDC and 3 sigma Activity concentration exceeds customer reporting value High

(83315)

(83316)

Spec MDC exceeds customer technical specification

Peak not identified in gamma spectrum No Peak identified in gamma spectrum Yes

Bolded text indicates reportable value.

**** Results are reported on an as received basis unless otherwise noted

11/20/02 10:54:42AM



Sample ID: HEM 10 1FT.

Station:

Description:

LIMS Number: 1 10601-28

L19691

US Ecology

US607-3EREGFS-02

Collect Start: 11/12/02 0:00

Collect Stop:

Received: 11/12/02 Matrix: Solids (SD)

% Moisture:	L19091-28	(83317)								Volu			
Radionuclide	SOP#	Activity Conc	Uncertainty (2 Sigma)	MDC	Units	Aliquot Volume	Aliquot Units	Reference Date	Count Date	Count Time	Count Time Units	Flag	Values
K-40	042-5	2.42E+000	5.16E-001	2.51E-001	pCi/G	344.600	G WET	11/12/02 12:00	11/13/02	6,000	Seconds	+	Yes
CS-137	042-5	-1.34E-003	2.08E-002	3.44E-002	pCi/G	344.600	G WET	11/12/02 12:00	11/13/02	6,000	Seconds		No
RA-226	042-5	2.21E-001	5.02E-002	8.11E-001	pCi/G	344.600	G WET	11/12/02 12:00	11/13/02	6,000	Seconds		Yes
TH-232	042-5	1.21E-001	4.46E-002	8.61E-002	pCi/G	344.600	G WET	11/12/02 12:00	11/13/02	6,000	Seconds	+	Yes
U-235	042-5	5.86E-001	2.20E-001	2.70E-001	pCi/G	344.600	G WET	11/12/02 12:00	11/13/02	6,000	Seconds	+	Yes
U-238	042-5	6.41E-001	2.32E+000	3.90E+000	pCi/G	344.600	G WET	11/12/02 12:00	11/13/02	6,000	Seconds		No_
U-233/234 (AS)	062-110	5.51E+001	9.85E+000	3.22E-002	pCi/g	0.528	g		11/17/02	60,004	seconds	+	
U-235 (AS)	062-110	2.02E+000	4.64E-001	1.62E-002	pCi/g	0.528	و		11/17/02	60,004	seconds	+	
U-238 (AS)	062-110	3.64E+000	7.38E-001	3.22E-002	pCi/g	0.528	ę		11/17/02	60,004	seconds	+	

Comments:

Sample ID: HEM 10 2FT.	L19691	Collect Start: 11/12/02 0:00
Station:		Collect Stop:
Description:	US Ecology	Received: 11/12/02
LIMS Number: L19691-29 (83318)	US607-3EREGFS-02	Matrix: Solids (SD)

Volumo

% Moisture:										Volu	me:		
Radionuclide	SOP#	Activity Conc	Uncertainty (2 Sigma)	MDC	Units	Aliquot Volume	Aliquot Units	Reference Date	Count Date	Count Time	Count Time Units	Fla	g Values
K-40	042-5	6.68E+000	8.39E-001	3.79E-001	pCi/G	318.800	G WET	11/12/02 12:00	11/13/02	6,000	Seconds	+	Yes
CS-137	042-5	1.18E-001	4.87E-002	4.03E-002	pCi/G	318.800	G WET	11/12/02 12:00	11/13/02	6,000	Seconds	+	Yes
RA-226	042-5	3.63E-001	6.01E-002	1.04E+000	pCi/G	318.800	G WET	11/12/02 12:00	11/13/02	6,000	Seconds		Yes
TH-232	042-5	4.25E-001	5.30E-002	1.10E-001	pCi/G	318.800	G WET	11/12/02 12:00	11/13/02	6,000	Seconds	+	Yes
U-235	042-5	2.59E+000	2.78E-001	3.31E-001	pCi/G	318.800	G WET	11/12/02 12:00	11/13/02	6,000	Seconds	+	Yes

Flag Values

Activity concentration exceeds MDC and 3 sigma and peak identified(gamma only) Peak not identified, but forced activity concentration exceeds MDC and 3 sigma Activity concentration exceeds customer reporting value

High

MDC exceeds customer technical specification Spec

Peak not identified in gamma spectrum No Peak identified in gamma spectrum Yes

Bolded text indicates reportable value.

11/20/02 10:54:42AM



Sample ID: HEM 10 2FT.

L19691

Collect Start: 11/12/02 0:00

Station:

US Ecology

Collect Stop:

Description:

LIMS Number: L19691-29 (83318)

Received: 11/12/02 Matrix: Solids (SD)

Volume:

% Moisture:

042-5

US607-3EREGFS-02

Count

İ	Radionuclide
	U-238

:	SOP#	Activity Conc	U

Incertainty MDC (2 Sigma) 4.89E+000 9.09E+000 4.60E+000

Aliquot Units Volume pCi/G 318,800

Aliquot Units **GWET**

Reference Date

11/12/02 12:00

Count Date

11/13/02

Count Time

6.000

Time Units Flag Values

Yes

Comments:

Sample ID: HEM 10 3FT.

L19691

Collect Start: 11/12/02 0:00

Seconds

Station: Description:

US Ecology

Collect Stop:

Received: 11/12/02 Matrix: Solids (SD)

LIMS Number: L19691-30

(83319)

US607-3EREGFS-02

% Moisture:										Volu	ine:			
Radionuclide	SOP#	Activity Conc	Uncertainty (2 Sigma)	MDC	Units	Aliquot Volume	Aliquot Units	Reference Date	Count Date	Count Time	Count Time Units	Flaş	Values	;
K-40	042-5	1.07E+001	1.07E+000	2.12E-001	pCi/G	314.900	G wet	11/12/02 12:00	11/13/02	6,000	Seconds	+		Yes
CS-137	042-5	6.50E-002	5.25E-002	2.05E-002	pCi/G	314.900	G wet	11/12/02 12:00	11/13/02	6,000	Seconds			Yes
RA-226	042-5	4.66E-001	5.94E-002	4.75E-001	pCi/G	314.900	G wet	11/12/02 12:00	11/13/02	6,000	Seconds			Yes
TH-232	042-5	5.08E-001	6.16E-002	5.47E-002	pCi/G	314.900	G wet	11/12/02 12:00	11/13/02	6,000	Seconds	+		Yes
U-235	042-5	2.00E+000	2.88E-001	1.43E-001	pCi/G	3.14.900	G wet	11/12/02 12:00	11/13/02	6,000	Seconds	+		Yes
U-238	042-5	5.68E+000	4.34E+000	2.35E+000	pCi/G	314.900	G wet	11/12/02 12:00	11/13/02	6,000	Seconds			Yes

Comments:

Sample ID: HEM 11 1FT.

L19691

Collect Start: 11/12/02 0:00

Station:

US Ecology

Collect Stop: Received: 11/12/02

Volume:

Description: LIMS Number: L19691-31

(83320)

US607-3EREGFS-02

Matrix: Solids (SD)

% Moisture:

Radionuclide	SOP#	Activity Conc	Uncertainty (2 Sigma)	MDC	Units	Aliquot Volume	Aliquot Units	Reference Date	Count Date	Count Time	Count Time Units	Flag Values
--------------	------	------------------	--------------------------	-----	-------	-------------------	------------------	-------------------	---------------	---------------	------------------------	-------------

Flag Values

Activity concentration exceeds MDC and 3 sigma and peak identified(gamma only) =

Peak not identified, but forced activity concentration exceeds MDC and 3 sigma Activity concentration exceeds customer reporting value High =

MDC exceeds customer technical specification Spec

Peak not identified in gamma spectrum No = Peak identified in gamma spectrum Yes

Bolded text indicates reportable value.

**** Results are reported on an as received basis unless otherwise noted

11/20/02 10:54:42AM



Sample ID: HEM 11 1FT. Collect Start: 11/12/02 0:00 L19691

Collect Stop: Station: **US Ecology**

Received: 11/12/02 Description: US607-3EREGFS-02 Matrix: Solids (SD) LIMS Number: L19691-31 (83320)

% Moisture: Volume: Count Activity Aliquot Aliquot Count Flag Values Uncertainty Reference Count Time MDC Units SOP# Radionuclide Conc (2 Sigma) Volume Time Units Date Date Units 1.75E-001 K-40 pCi/G 1.35E+000 329.800 **G WET** 11/12/02 12:00 Seconds 042-5 1.68E+001 6,000 11/13/02 Yes CS-137 3.12E-002 4.29E-002 pCi/G 329.800 | G WET 042-5 6.98E-002 11/12/02 12:00 11/13/02 Seconds No 6.000 RA-226 8.10E-002 5.36E-001 pCi/G 042-5 6.52E-001 329.800 | G WET 11/12/02 12:00 11/13/02 6,000 Seconds + Yes TH-232 6.93E-002 7.55E-002 pCi/G 329,800 G WET 042-5 8.06E-001 11/12/02 12:00 Seconds + 11/13/02 6.000 Yes 1.93E-001 pCi/G U-235 3.07E-001 329,800 G WET + 042-5 6.26E-001 11/12/02 12:00 11/13/02 6,000 Seconds Yes U-238 042-5 2.21E+000 | 2.78E+000 | 3.71E+000 pCi/G 329.800 G WET 11/12/02 12:00 Seconds 11/13/02 6.000 No

Comments:

Sample ID: HEM 11 2FT. Collect Start: 11/12/02 0:00 L19691

Station:

Description: LIMS Number: L19691-32

(83321)

US Ecology US607-3EREGFS-02 Collect Stop:

Received: 11/12/02 Matrix: Solids (SD)

% Moisture:							·			Volu	me:		
Radionuclide	SOP#	Activity Conc	Uncertainty (2 Sigma)	MDC	Units	Aliquot Volume	Aliquot Units	Reference Date	Count Date	Count Time	Count Time Units	Flag	g Values
K-40	042-5	1.64E+001	1.42E+000	4.10E-001	pCi/G	329.700	G WET	11/12/02 12:00	11/13/02	6,000	Seconds	+	Yes
CS-137	042-5	1.21E-002	3.94E-002	6.65E-002	pCi/G	329.700	G WET	11/12/02 12:00	11/13/02	6,000	Seconds		No
RA-226	042-5	6.98E-001	8.75E-002	1.06E+000	pCi/G	329.700	G WET	11/12/02 12:00	11/13/02	6,000	Seconds		Yes
TH-232	042-5	9.56E-001	8.62E-002	1.41E-001	pCi/G	329.700	G WET	11/12/02 12:00	11/13/02	6,000	Seconds	+	Yes
U-235	042~5	7.24E-001	6.11E-001	4.51E-001	pCi/G	329.700	G WET	11/12/02 12:00	11/13/02	6,000	Seconds		Yes
U-238	042-5	2.69E+000	4.03E+000	6.98E+000	pCi/G	329.700	G WET	11/12/02 12:00	11/13/02	6,000	Seconds		No

Comments:

Flag Values

Activity concentration exceeds MDC and 3 sigma and peak identified(gamma only)

Peak not identified, but forced activity concentration exceeds MDC and 3 sigma

Activity concentration exceeds customer reporting value High

MDC exceeds customer technical specification Spec

== Peak not identified in gamma spectrum No Peak identified in gamma spectrum Yes

Bolded text indicates reportable value.

**** Results are reported on an as received basis unless otherwise noted

11/20/02 10:54:42AM



A Teledyne Technologies Company

Sample ID: HEM 11 3FT.

Station:

Description:

LIMS Number: L19691-33

(83322)

L19691

US Ecology

US607-3EREGFS-02

Collect Start: 11/12/02 0:00

Collect Stop:

Received: 11/12/02 Matrix: Solids (SD)

% Moisture:	D17071-33	(03322)								Volu			
Radionuclide	SOP#	Activity Conc	Uncertainty (2 Sigma)	MDC	Units	Aliquot Volume	Aliquot Units	Reference Nate	Count Date	Count Time	Count Time Units	Fla	g Values
K-40	042-5	1.39E+001	1.52E+000	4.66E-001	pCi/G	367.200	G WET	11/12/02 12:00	11/13/02	6,000	Seconds	+	Yes
CS-137	042-5	5.00E-002	5.70E-002	7.50E-002	pCi/G	367.200	G WET	11/12/02 12:00	11/13/02	6,000	Seconds		Yes
RA-226	042-5	7.15E-001	9.22E-002	1.32E+000	pCi/G	367.200	G WET	11/12/02 12:00	11/13/02	6,000	Seconds		Yes
ТН-232	042-5	7.45E-001	8.44E-002	1.73E-001	pCi/G	367.200	G WET	11/12/02 12:00	11/13/02	6,000	Seconds	+	Yes
U-235	042-5	1.93E+000	5.50E-001	6.69E-001	pCi/G	367.200	G WET	11/12/02 12:00	11/13/02	6,000	Seconds	+	Yes
U-238	042-5	5.55E+000	5.45E+000	9.81E+000	pCi/G	367.200	G WET	11/12/02 12:00	11/13/02	6,000	Seconds		No
U-233/234 (AS)	062-110	5.51E+001	6.87E+000	7.14E-002	pCi/g	0.538	g		11/17/02	60,001	seconds	+	<u> </u>
U-235 (AS)	062-110	2.20E+000	4.71E-001	2.53E-002	pCi/g	0.538	g		11/17/02	60,001	seconds	+	
U-238 (AS)	062-110	1.24E+001	1.71E+000	5.05E-002	pCi/g	0.538	£		11/17/02	60,001	seconds	+	<u> </u>

Comments:

Sample ID: HEM 12 1FT.

Station:

Description:

LIMS Number: L19691-34

(83323)

L19691

US Ecology

US607-3EREGFS-02

Collect Start: 11/12/02 0:00

Collect Stop:

Received: 11/12/02 Matrix: Solids (SD)

% Moisture: Volume:													
Radionuclide	SOP#	Activity Conc	Uncertainty (2 Sigma)	MDC	Units	Aliquot Volume	Aliquot Units	Reference Date	Count Date	Count Time	Count Time Units	Flag	Values
K-40	042-5	1.23E+001	1.11E+000	3.43E-001	pCi/G	343.200	G WET	11/12/02 12:00	11/13/02	6,000	Seconds	+	Yes
CS-137	042-5	2.43E-002	4.33E-002	5.89E-002	pCi/G	343.200	G WET	11/12/02 12:00	11/13/02	6,000	Seconds		Yes
RA-226	042-5	5.68E-001	7.65E-002	9.99E-001	pCi/G	343.200	G WET	11/12/02 12:00	11/13/02	6,000	Seconds		Yes
TH-232	042-5	6.69E-001	6.76E-002	1.44E-001	pCi/G	343.200	G WET	11/12/02 12:00	11/13/02	6,000	Seconds	+ [Yes
U-235	042-5	7.45E-001	2.41E-001	3.29E-001	pCi/G	343.200	G WET	11/12/02 12:00	11/13/02	6,000	Seconds	+	Yes

Flag Values

Activity concentration exceeds MDC and 3 sigma and peak identified(gamma only)

Peak not identified, but forced activity concentration exceeds MDC and 3 sigma Activity concentration exceeds customer reporting value High

MDC exceeds customer technical specification = Spec

Peak not identified in gamma spectrum No Peak identified in gamma spectrum Yes

Bolded text indicates reportable value.

**** Results are reported on an as received basis unless otherwise noted

11/20/02 10:54:42AM



Seconds

No

6.000

Sample ID: HEM 12 1FT. Collect Start: 11/12/02 0:00 L19691 Collect Stop: Station: **US Ecology** Received: 11/12/02 Description: Matrix: Solids (SD) US607-3EREGFS-02 LIMS Number: L19691-34 (83323)Volume: % Moisture: Count Activity Count Aliquot Aliquot Flag Values Reference Count Uncertainty Time MDC Units SOP# Radionuclide Conc Time Volume Units Date (2 Sigma) Date Units

343.200 | G WET

11/12/02 12:00

11/13/02

Comments:
Comments.

U-238

Sample ID: Station: Description: LIMS Number: % Moisture:					L19691 US Ecology US607-3EREGFS-02					Collect Start: 11/12/02 0:00 Collect Stop: Received: 11/12/02 Matrix: Solids (SD) Volume:				
Radionuclide	SOP#	Activity Conc	Uncertainty (2 Sigma)	MDC	Units	S Aliquot Aliquot Reference Volume Units Date		Count Date	Count Time	Count Time Units	Flag Values			
K-40	042-5	1.21E+001	1.23E+000	3.10E-001	pCi/G	340.800	G WET	11/12/02 12:00	11/13/02	6,000	Seconds	+	Yes	
CS-137	042-5	6.06E-002	5.41E-002	2.99E-002	pCi/G	340.800	G WET	11/12/02 12:00	11/13/02	6,000	Seconds		Yes	
RA-226	042-5	6.70E-001	8.41E-002	6.65E-001	pCi/G	340.800	G-WET	11/12/02 12:00	11/13/02	6,000	Seconds	+	Yes	
TH-232	042-5	6.99E-001	8.38E-002	8.85E-002	pCi/G	340.800	G WET	11/12/02 12:00	11/13/02	6,000	Seconds	+	Yes	
U-235	042-5	7.33E-001	5.31E-001	2.91E-001	pCi/G	340.800	G WET	11/12/02 12:00	11/13/02	6,000	Seconds		Yes	
U-238	042-5	1.99E+000	2.79E+000	3.59E+000	pCi/G	340.800	G WET	11/12/02 12:00	11/13/02	6,000	Seconds		No	

Comments:

Sample ID: Station: Description: LIMS Number: % Moisture:	HEM 12 3					-02		Collect Start: 11/12/02 0:00 Collect Stop: Received: 11/12/02 Matrix: Solids (SD) Volume:				
Radionuclide	SOP#	Activity Cone	Uncertainty (2 Sigma)	MDC	Units	Aliquot Volume	Aliquot Units	Reference Date	Count Date	Count Time	Count Time Units	Flag Values

Flag Values

+ = Activity concentration exceeds MDC and 3 sigma and peak identified(gamma only)

* Peak not identified, but forced activity concentration exceeds MDC and 3 sigma

3.88E+000

2.26E+000

042-5

6.71E+000 pCi/G

High = Activity concentration exceeds customer reporting value

Spec = MDC exceeds customer technical specification

No = Peak not identified in gamma spectrum
Yes = Peak identified in gamma spectrum

Bolded text indicates reportable value.

**** Results are reported on an as received basis unless otherwise noted

11/20/02 10:54:42AM



A Teledyne Technologies Company

Sample ID: HEM 12 3FT.

Station:

Description:

LIMS Number: L19691-36

(83325)

L19691

US Ecology

US607-3EREGFS-02

Collect Start: 11/12/02 0:00

Collect Stop:

Received: 11/12/02 Matrix: Solids (SD)

% Moisture: Volume:													
Radionuclide	SOP#	Activity Conc	Uncertainty (2 Sigma)	MDC	Units	Aliquot Volume	Aliquot Units	Reference Date	Count Date	Count Time	Count Time Units	Fla	g Values
K-40	042-5	6.36E+000	7.62E-001	2.71E-001	pCi/G	372.800	G WET	11/12/02 12:00	11/13/02	6,000	Seconds	+	Yes
CS-137	042-5	4.83E-002	3.18E-002	4.55E-002	pCi/G	372.800	G WET	11/12/02 12:00	11/13/02	6,000	Seconds	+	Yes
RA-226	042-5	3.77E-001	5.13E-002	1.87E+000	pCi/G	372.800	G WET	11/12/02 12:00	11/13/02	6,000	Seconds		Yeş
TH-232	042-5	8.36E-001	7.26E-002	9.44E-002	pCi/G	372.800	G WET	11/12/02 12:00	11/13/02	6,000	Seconds	+	Yes
U-235	042-5	2.28E+001	5.84E-001	6.53E-001	pCi/G	372.800	G WET	11/12/02 12:00	11/13/02	6,000	Seconds	+	Yes
U-238	042-5	9.78E+000	3.61E+000	4.29E+000	pCi/G	372.800	G WET	11/12/02 12:00	11/13/02	6,000	Seconds	+	Yes

Comments:

Flag Values

Activity concentration exceeds MDC and 3 sigma and peak identified(gamma only)

Peak not identified, but forced activity concentration exceeds MDC and 3 sigma Activity concentration exceeds customer reporting value =

MDC exceeds customer technical specification Spec Peak not identified in gamma spectrum

No Peak identified in gamma spectrum Yes

A Teledyne Technologies Company 2508 Quality Lane Knoxville, TN 37931-3133

607 17 2002

US Ecology 109 Flint Road Oak Ridge TN 37830 Attn: Darrel Ray

Report of Analysis/Certificate of Conformance

10/14/02

LIMS #: L19307

Project ID#:

US607-3EREGFS-02

Received:

10/4/02

Delivery Date:

10/14/02

P.O. #:

1099

Release #:

FS-MO-02-06

SDG #:

N/A

This is to certify that Teledyne Brown Engineering - Environmental Services located at 2508 Quality Lane, Knoxville, Tennessee, 37931, has analyzed, tested and documented samples as specified in the applicable purchase order.

This also certifies that requirements of applicable codes, standards and specifications have been fully met and that any quality assurance documentation which verified conformance to the purchase order is on file and may be examined upon request.

I hereby certify that the above statements are true and correct.

Keith Jeter

Operations Manager

Cross Reference Table

Client ID	Laboratory ID	TI#
HEM-8-3FT	L19307-1	80697
HEM-4-3FT	L19307-2	80698
HEM-6-3FT	L19307-3	80699
HEM-5-3FT	L19307-4	80700

10/14/02 7:31:10AM



arrel Ray Collect Start: 09/22/02 0:00 Sample ID: HEM-8-3FT L19307 Collect Stop: Station: US Ecology Received: 10/04/02 Description: US607-3EREGFS-02 Matrix: Solids (SD) IMS Number: L19307-1 (80697)Volume: % Moisture: Count Activity Count Aliquot Uncertainty Aliquot Reference Count Flag Values Time MDC Units SOP# Radionuclide Conc Time Volume (2 Sigma) Units Date Date Units 10/10/02 1.23E+000 pCi/g 60.002 seconds -233/234 (AS) 062-110 0.500 1.60E+001 10/10/02 1.06E-001 seconds + 062-110 pCi/g 0.500 60.002 -235 (AS) 4.18E-001 Q 1.84E-001 10/10/02 + pCi/g 60 002 seconds -238 (AS) 062-110 1.29E+000 0.500 omments: Collect Start: 09/22/02 0:00 Sample ID: HEM-4-3FT L19307 Collect Stop: Station: **US Ecology** Received: 10/04/02 Description: US607-3EREGFS-02 Matrix: Solids (SD) LIMS Number: L19307-2 (80698)Volume: % Moisture: Count Activity Count Aliquot Aliquot Reference Count Uncertainty Time Flag Values MDC Units SOP# Radionuclide Conc Volume Time Units (2 Sigma) Date Date Units 10/10/02 1.16E+000 pCi/g seconds + 062-110 60.003 J-233/234 (AS) 1.42E+001 0.500 10/10/02 1.14E-001 pCi/g 60.003 seconds + 062-110 J-235 (AS) 4.37E-001 0.500 2.78E-001 pCi/g 10/10/02 60.003 seconds + 062-110 0.500 J-238 (AS) 2.28E+000 Comments: Collect Start: 09/22/02 0:00 Sample ID: HEM-6-3FT L19307 Collect Stop: Station: **US Ecology** Received: 10/04/02 Description: US607-3EREGFS-02 Matrix: Solids (SD) LIMS Number: L19307-3 (80699)Volume: % Moisture: 9.17 Count Activity Count Aliquot Aliquot Reference Uncertainty Count Flag Values Time MDC Units SOP# Radionuclide Conc Volume Time (2 Sigma) Units Date Date Units 2.07E-001 10/10/02

Flag Values

BE-7

K-40

Activity concentration exceeds MDC and 3 sigma and peak identified(gamma only) Peak not identified, but forced activity concentration exceeds MDC and 3 sigma

4.90E-001

pCi/G

pCi/G

Activity concentration exceeds customer reporting value High

<

1.04E+001

MDC exceeds customer technical specification Spec Peak not identified in gamma spectrum = No

Peak identified in gamma spectrum Yes

Bolded text indicates reportable value.

042 - 5

042-5

**** Results are reported on an as received basis unless otherwise noted

10/10/02

60,000

60,000

Seconds

Seconds

No

Yes

G

310.300

310.300

09/22/02 12:00

l09/22/02 12:00

10/14/02 7:31:27AM



Sample ID: HEM-6-3FT

Station:

L19307

Collect Start: 09/22/02 0:00

US Ecology

Collect Stop:

Description:

Received: 10/04/02 Matrix: Solids (SD)

IMS Number: L19307-3 (80699) US607-3EREGFS-02

% Moisture: 9.17 Volume:													
Radionuclide	SOP#	Activity Conc	Uncertainty (2 Sigma)	MDC	Units	Aliquot Volume	Aliquot Units	Reference Date	Count Date	Count Time	Count Time Units	Flag	Values
'R-51	042-5	<		2.54E-001	pCi/G	310.300	G	09/22/02 12:00	10/10/02	60,000	Seconds		No
fN-54	042-5	<		2.19E-002	pCi/G	310.300	G	09/22/02 12:00	10/10/02	60,000	Seconds		No
:O-57	042-5	9.92E-002	2.51E-002		pCi/G	310.300	G	09/22/02 12:00	10/10/02	60,000	Seconds	+	Ye
O-58	042-5	<		2.26E-002	pCi/G	310.300	G	09/22/02 12:00	10/10/02	60,000	Seconds		No
E-59	042-5	<		5.45E-002	pCi/G	310.300	G	09/22/02 12:00	10/10/02	60,000	Seconds		No
CO-60	042-5	<		1.74E-002	pCi/G	310.300	G	09/22/02 12:00	10/10/02	60,000	Seconds]	No
N-65	042-5	<		4.78E-002	pCi/G	310.300	G	09/22/02 12:00	10/10/02	60,000	Seconds		No
E-75	042-5	<		2.80E-002	pCi/G	310.300	G	09/22/02 12:00	10/10/02	60,000	Seconds		No
R-85	042-5	<		2.86E-002	pCi/G	310.300	G	09/22/02 12:00	10/10/02	60,000	Seconds	*	No
7-88	042-5	<		2.00E-002	pCi/G	310.300	G	09/22/02 12:00	10/10/02	60,000	Seconds		N
NB-94	042-5	<		1.94E-002	pCi/G	310.300	G	09/22/02 12:00	10/10/02	60,000	Seconds		N.
NB-95	042-5	<		3.62E-002	pCi/G	310.300	G	09/22/02 12:00	10/10/02	60,000	Seconds	*	N
ZR-95	042-5	<		4.22E-002	pCi/G	310.300	G	09/22/02 12:00	10/10/02	60,000	Seconds		N
4O-99	042-5	< .		2.58E+000	pCi/G	310.300	G	09/22/02 12:00	10/10/02	60,000	Seconds		N
RU-103	042-5	<		2.52E-002	pCi/G	310.300	G	09/22/02 12:00	10/10/02	60,000	Seconds		N
RU-106	042-5	<		1.83E-001	pCi/G	310.300	G	09/22/02 12:00	10/10/02	60,000	Seconds		N
CD-109	042-5	<		9.30E-001	pCi/G	310.300	G	09/22/02 12:00	10/10/02	60,000	Seconds		N
AG-110M	042-5	<		2.08E-002	pCi/G	310.300	G	09/22/02 12:00	10/10/02	60,000	Seconds		N
SN-113	042-5	<		2.81E-002	pCi/G	310.300	G	09/22/02 12:00	10/10/02	60,000	Seconds		N
SB-124	042-5	<		2.35E-002	pCi/G	310.300	1	09/22/02 12:00	10/10/02	60,000	Seconds		N
SB-125	042-5	<	1	5.57E-002	pCi/G	310.300	G	09/22/02 12:00	10/10/02	60,000	Seconds		N
TE-129M	042-5	<		3.15E-001	pCi/G	310.300	T	09/22/02 12:00	10/10/02	60,000	Seconds		N
I-131	042-5	<	1	8.90E-002	pCi/G	310.300	G	09/22/02 12:00	10/10/02	60,000	Seconds		·N

Flag Values

Activity concentration exceeds MDC and 3 sigma and peak identified(gamma only) =

Peak not identified, but forced activity concentration exceeds MDC and 3 sigma Activity concentration exceeds customer reporting value = High

MDC exceeds customer technical specification Spec

No = Peak not identified in gamma spectrum Peak identified in gamma spectrum Yes

Bolded text indicates reportable value.

Keport of Almysis

10/14/02 7:31:27AM



Sample ID: HEM-6-3FT

Station:

L19307

Collect Start: 09/22/02 0:00

Description:

US Ecology

Collect Stop: Received: 10/04/02

LIMS Number: L19307-3

(80699)

US607-3EREGFS-02

Matrix: Solids (SD)

% Moisture:	9.17	(000))		· · · · · · · · · · · · · · · · · · ·						Volume:					
Radionuclide	SOP#	Activity Conc	Uncertainty (2 Sigma)	MDC	Units	Aliquot Volume	Aliquot Units	Reference Date	Count Date	Count Time	Count Time Units	Flag	y Values		
3A-133	042-5	<.		2.56E-002	pCi/G	310.300	G	09/22/02 12:00	10/10/02	60,000	Seconds		No		
CS-134	042-5	<		1.88E-002	pCi/G	310.300	G	09/22/02 12:00	10/10/02	60,000	Seconds	!	No		
CS-136	042-5	<		4.77E-002	pCi/G	310.300	G	09/22/02 12:00	10/10/02	60,000	Seconds		No		
CS-137	042-5	1.12E-001	2.05E-002		pCi/G	310.300	G	09/22/02 12:00	10/10/02	60,000	Seconds	+	Yes		
CE-139	042-5	<		3.16E-002	pCi/G	310.300	G	09/22/02 12:00	10/10/02	60,000	Seconds	*	No		
BA-140	042-5	<		1.71E-001	pCi/G	310.300	G	09/22/02 12:00	10/10/02	60,000	Seconds		No		
LA-140	042-5	<		4.76E-002	pCi/G	310.300	G	09/22/02 12:00	10/10/02	60,000	Seconds		No		
CE-141	042-5	<		1.07E-001	pCi/G	310.300	G	09/22/02 12:00	10/10/02	60,000	Seconds	*	No		
CE-144	042-5	<		2.09E-001	pCi/G	310.300	G	09/22/02 12:00	10/10/02	60,000	Seconds		No		
EU-152	042-5	<		5.92E-002	pCi/G	310.300	G	09/22/02 12:00	10/10/02	60,000	Seconds		No		
EU-154	042-5	<		5.91E-002	pCi/G	310.300	G	09/22/02 12:00	10/10/02	60,000	Seconds	*	No		
HG-203	042-5	<		2.68E-002	pCi/G	310.300	G	09/22/02 12:00	10/10/02	60,000	Seconds		No		
RA-226	042-5	6.66E-001	3.56E-002		pCi/G	310.300	G	09/22/02 12:00	10/10/02	60,000	Seconds	+	Yes		
AC-228	042-5	6.17E-001	8.67E-002		pCi/G	310.300	G	09/22/02 12:00	10/10/02	60,000	Seconds	+	Yes		
TH-228	042-5	5.64E-001	7.78E-002		pCi/G	310.300	G	09/22/02 12:00	10/10/02	60,000	Seconds	+	Yes		
TH-232	042-5	5.59E-001	3.78E-002		pCi/G	310.300	G	09/22/02 12:00	10/10/02	60,000	Seconds	+	Yes		
U-235	042-5	6.49E+000	1.71E-001		pCi/G	310.300	G	09/22/02 12:00	10/10/02	60,000	Seconds	+	Yes		
U-238	042-5	2.28E+001	3.43E+000		pCi/G	310.300	G	09/22/02 12:00	10/10/02	60,000	Seconds	+	Yes		
NP-239	042-5	<		2.67E+001	pCi/G	310.300	l _G	09/22/02 12:00	10/10/02	60,000	Seconds	*	No		

Comments:

Flag Values

Activity concentration exceeds MDC and 3 sigma and peak identified(gamma only)

Peak not identified, but forced activity concentration exceeds MDC and 3 sigma Activity concentration exceeds customer reporting value High

MDC exceeds customer technical specification Spec =

Peak not identified in gamma spectrum No == Peak identified in gamma spectrum Yes

Bolded text indicates reportable value.

**** Results are reported on an as received basis unless otherwise noted

hopore of Ahmysis

10/14/02 7:31:27AM



Sample ID: HEM-5-3FT

Station:

L19307 US Ecology Collect Start: 09/22/02 0:00

Collect Stop: Received: 10/04/02

Matrix: Solids (SD)

Volume

Description:

LIMS Number: L19307-4

(80700)

US607-3EREGFS-02

% Moisture:	8.51							·		Volu			
Radionuclide	SOP#	Activity Conc	Uncertainty (2 Sigma)	MDC	Units	Aliquot Volume	Aliquot Units	Reference Date	Count Date	Count Time	Count Time Units	Flag	y Values
3E-7	042-5	<		1.50E-001	pCi/G	303.100	G	09/22/02 12:00	10/10/02	60,000	Seconds		No
<-40	042-5	1.15E+001	3.79E-001		pCi/G	303.100	G	09/22/02 12:00	10/10/02	60,000	Seconds	+	Yes
CR-51	042-5	<		1.72E-001	pCi/G	303.100	G	09/22/02 12:00	10/10/02	60,000	Seconds		No
MN-54	042-5	<		1.60E-002	pCi/G	303.100	G	09/22/02 12:00	10/10/02	60,000	Seconds		No
CO-57	042-5	4.20E-002	1.38E-002		pCi/G	303.100	G	09/22/02 12:00	10/10/02	60,000	Seconds	+	Yes
CO-58	042-5	<		1.67E-002	pCi/G	303.100	G	09/22/02 12:00	10/10/02	60,000	Seconds		No
FE-59	042-5	<		3.85E-002	pCi/G	303.100	G	09/22/02 12:00	10/10/02	60,000	Seconds		No
CO-60	042-5	<		1.52E-002	pCi/G	303.100	G	09/22/02 12:00	10/10/02	60,000	Seconds		No
ZN-65	042-5	<		3.50E-002	pCi/G	303.100	G	09/22/02 12:00	10/10/02	60,000	Seconds		No
SE-75	042-5	<		2.03E-002	pCi/G	303.100	G	09/22/02 12:00	10/10/02	60,000	Seconds		No
SR-85	042-5	<		2.05E-002	pCi/G	303.100	G	09/22/02 12:00	10/10/02	60,000	Seconds	*	No
Y-88	042-5	<		1.50E-002	pCi/G	303.100	G	09/22/02 12:00	10/10/02	60,000	Seconds		No
NB-94	042-5	<		1.38E-002	pCi/G	303.100	G	09/22/02 12:00	10/10/02	60,000	Seconds		No
NB-95	042-5	<		2.01E-002	pCi/G	303.100	G	09/22/02 12:00	10/10/02	60,000	Seconds	*	No
ZR-95	042-5	<		3.17E-002	pCi/G	303.100	G	09/22/02 12:00	10/10/02	60,000	Seconds		No
MO-99	042-5	<		1.63E+000	pCi/G	303.100	G	09/22/02 12:00	10/10/02	60,000	Seconds		No
RU-103	042-5	<		1.88E-002	pCi/G	303.100	G	09/22/02 12:00	10/10/02	60,000	Seconds		No
RU-106	042-5	<		1.30E-001	pCi/G	303.100	G	09/22/02 12:00	10/10/02	60,000	Seconds		No
CD-109	042-5	<		5.59E-001	pCi/G	303.100	G	09/22/02 12:00	10/10/02	60,000	Seconds	*	No
AG-110M	042-5	<		1.42E-002	pCi/G	303.100	G	09/22/02 12:00	10/10/02	60,000	Seconds		No
SN-113	042-5	<		1.97E-002	pCi/G	303.100	G	09/22/02 12:00	10/10/02	60,000	Seconds		No
SB-124	042-5	<		1.56E-002	pCi/G	303.100	G	09/22/02 12:00	10/10/02	60,000	Seconds		No
SB-125	042-5	<		3.93E-002	pCi/G	303.100		09/22/02 12:00	10/10/02	60,000	Seconds		No

Flag Values

Activity concentration exceeds MDC and 3 sigma and peak identified(gamma only)

Peak not identified, but forced activity concentration exceeds MDC and 3 sigma Activity concentration exceeds customer reporting value

High

MDC exceeds customer technical specification Spec

Peak not identified in gamma spectrum No Yes Peak identified in gamma spectrum

Bolded text indicates reportable value.

10/14/02 7:31:27AM



Sample ID: HEM-5-3FT

L19307

Collect Start: 09/22/02 0:00

Station:

Collect Stop:

Description:

US Ecology

Received: 10/04/02 Matrix: Solids (SD)

LIMS Number: L19307-4

(80700)

US607-3EREGFS-02

% Moisture:		(80700)		Volum									me:				
Radionuclide	SOP#	Activity Conc	Uncertainty (2 Sigma)	MDC	Units	Aliquot Volume	Aliquot Units	Reference Date	Count Date	Count Time	Count Time Units	Flag	y Values				
TE-129M	042-5	<		2.22E-001	pCi/G	303.100	G	09/22/02 12:00	10/10/02	60,000	Seconds		No				
I-131	042-5	<.		6.46E-002	pCi/G	303.100	G	09/22/02 12:00	10/10/02	60,000	Seconds		No				
BA-133	042-5	<		1.83E-002	pCi/G	303.100	G	09/22/02 12:00	10/10/02	60,000	Seconds		No				
CS-134	042-5	<		1.34E-002	pCi/G	303.100	G	09/22/02 12:00	10/10/02	60,000	Seconds		No				
CS-136	042-5	<		3.31E-002	pCi/G	303.100	G	09/22/02 12:00	10/10/02	60,000	Seconds		No				
CS-137	042-5	6.80E-002	1.47E-002		pCi/G	303.100	G	09/22/02 12:00	10/10/02	60,000	Seconds	+	Yes				
CE-139	042-5	<		1.88E-002	pCi/G	303.100	G	09/22/02 12:00	10/10/02	60,000	Seconds	*	No				
BA-140	042-5	<		1.28E-001	pCi/G	303.100	G	09/22/02 12:00	10/10/02	60,000	Seconds		No				
LA-140	042-5	<		4.20E-002	pCi/G	303.100	G	09/22/02 12:00	10/10/02	60,000	Seconds	*	No				
CE-141	042-5	<		6.15E-002	pCi/G	303.100	G	09/22/02 12:00	10/10/02	60,000	Seconds	*	No				
CE-144	042-5	<		1.35E-001	pCi/G	303,100	G	09/22/02 12:00	10/10/02	60,000	Seconds		No				
EU-152	042-5	<		4.20E-002	pCi/G	303.100	G	09/22/02 12:00	10/10/02	60,000	Seconds		No				
EU-154	042-5	<		3.61E-002	pCi/G	303.100	G	09/22/02 12:00	10/10/02	60,000	Seconds		No				
HG-203	042-5	<		1.96E-002	pCi/G	303.100	G	09/22/02 12:00	10/10/02	60,000	Seconds		No				
RA-226	042-5	5.83E-001	2.74E-002		pCi/G	303.100	G	09/22/02 12:00	10/10/02	60,000	Seconds	+	Yes				
AC-228	042-5	1.03E+000	1.51E-001		pCi/G	303.100	G	09/22/02 12:00	10/10/02	60,000	Seconds	+	Yes				
TH-228	042-5	6.03E-001	5.85E-002		pCi/G	303.100	G	09/22/02 12:00	10/10/02	60,000	Seconds	+	Yes				
TH-232	042-5	5.67E-001	2.87E-002		pCi/G	303.100	G	09/22/02 12:00	10/10/02	60,000	Seconds	+	Yes				
U-235	042-5	3.19E+000	1.03E-001		pCi/G	303.100	G	09/22/02 12:00	10/10/02	60,000	Seconds	+	Yes				
U-238	042-5	4.34E+000	1.93E+000		pCi/G	303.100	G	09/22/02 12:00	10/10/02	60,000	Seconds	+	Yes				
NP-239	042-5	<		1.63E+001	pCi/G	303,100	G	09/22/02 12:00	10/10/02	60,000	Seconds	*	No				

Comments:

Flag Values

Activity concentration exceeds MDC and 3 sigma and peak identified(gamma only)

Peak not identified, but forced activity concentration exceeds MDC and 3 sigma Activity concentration exceeds customer reporting value

High

MDC exceeds customer technical specification Spec No = Peak not identified in gamma spectrum


Peak identified in gamma spectrum Yes

Bolded text indicates reportable value.



BROWN ENGINEERING, INC

A Teledyne Technologies Company 2508 Quality Lane Knoxville, TN 37931-3133



US Ecology 109 Flint Road Oak Ridge TN 37830 Attn: Darrel Ray

Report of Analysis/Certificate of Conformance

11/6/02

LIMS #: L19473

Project ID#: US607

US607-3EREGFS-02

Received:

10/22/02

Delivery Date:

11/6/02 1099

P.O. #:

Release #: FS-MO-02-06

SDG #:

N/A

This is to certify that Teledyne Brown Engineering - Environmental Services located at 2508 Quality Lane, Knoxville, Tennessee, 37931, has analyzed, tested and documented samples as specified in the applicable purchase order.

This also certifies that requirements of applicable codes, standards and specifications have been fully met and that any quality assurance documentation which verified conformance to the purchase order is on file and may be examined upon request.

I hereby certify that the above statements are true and correct.

Keith Jeter

Operations Manager

Cross Reference Table

Client ID	Laboratory ID	TI#
BKG-1	L19473-1	81808

11/6/02 11:03:57AM



Darrel Ray

Sample ID: BKG-1

Station:

Description:

LIMS Number: L19473-1

(81808)

L19473

US Ecology

US607-3EREGFS-02

Collect Start:

Collect Stop:

Received: 10/22/02 Matrix: Soil (S)

% Moisture:						Volume:									
Radionuclide	SOP#	Activity Conc	Uncertainty (2 Sigma)	MDC	Units	Aliquot Volume	Aliquot Units	Reference Date	Count Date	Count Time	Count Time Units	Flag Valı	ies		
U-233/234 (AS)	062-110	5.92E-001	2.17E-001		pCi/g	0.600	g		11/05/02	60,001	seconds	+			
U-235 (AS)	062-110	<<		2.95E-002	pCi/g	0.600	g		11/05/02	60,001	seconds				
U-238 (AS)	062-110	7.70E-001	2.51E-001		pCi/g	0.600	g		11/05/02	60,001	seconds	+	}		

Comments:

Flag Values

Activity concentration exceeds MDC and 3 sigma and peak identified(gamma only)

Peak not identified, but forced activity concentration exceeds MDC and 3 sigma Activity concentration exceeds customer reporting value High

MDC exceeds customer technical specification Spec

Peak not identified in gamma spectrum No Peak identified in gamma spectrum Yes

Bolded text indicates reportable value.

**** Results are reported on an as received basis unless otherwise noted



P - 10CFR61, 10CFR50, Other high level:

E - Environmental:

Turn-around-time

Purchase order:

Special Instructions:

Analysis Request Chain of Custody

LIMS #:

Kook

Client name: US Ecology / Field Service

Client address: 10 9 Flint Rol

Dok Ridge TV 37830

i			
	Phone	Number	865

865-220-5238

Fax Number: 865-220-5365

Variance Report:

(for lab use)

Project Number:

	<u> </u>		Project Nu	mper:				Contact:	Rob Miller
T.L. Number (för lab use)	Client Sample ID	Description	Station	Collection Start	Date/Time Stop	Volume	Units	Matrix or type	Analysis Request
(for lab use)	BKG-1-81808	501							Tsotopic Uranium
<u>l</u>			l	<u> </u>	<u> </u>	<u> </u>			

Relinquished by:	Date:	Relinquished by:	Date:	Relinquished by:	Date:	
Received by: MONUT Jack	24 Date: (0/22/0)	Received by:	Date:	Received by:	Date:	

10/14/02 7:31:10AM



Darrel Ray

Sample ID: HEM-8-3FT

L19307

Collect Start: 09/22/02 0:00

Station:

US Ecology

Collect Stop:

Description:

00 200.00

Received: 10/04/02 Matrix: Solids (SD)

LIMS Number: L19307-1

US607-3EREGFS-02

Volume:

l % Moisture:										4 010	mic.			
Radionuclide	SOP#	Activity Cone	Uncertainty (2 Sigma)	MDC	Units	Aliquot Volume	Aliquot Units	Reference Date	Count Date	Count Time	Count Time Units	Flag Values		\$
U-233/234 (AS)	062-110	1.60E+001	1.23E+000		pCVg	0.500	e		10/10/02	60,002	seconds	+		
U-235 (AS)	062-110	4.18E-001	1.06E-001		pCi/g	0.500	2		10/10/02	60,002	seconds	+		
U-238 (AS)	062-110	1.29E+000	1.84E-001		pCi/g	0.500	g	ĺ	10/10/02	60,002	seconds	+		

Comments:

Sample ID: HEM-4-3FT

L19307

Collect Start: 09/22/02 0:00

Station:

US Ecology

Collect Stop: Received: 10/04/02

Description: LIMS Number: L19307-2

(80698)

(80697)

US607-3EREGFS-02

Matrix: Solids (SD)
Volume:

% Moisture:

% Moistire:													
Radionuclide	SOP#	Activity Cone	Uncertainty (2 Sigma)	MDC	Units	Aliquot Volume	Aliquot Units	Reference Date	Count Date	Count Time	Count Time Units	Flag Values	
U-233/234 (AS)	062-110	1.42E+001	1.16E+000		pCi/g	0.500	-g		10/10/02	60,003	seconds	+	
U-235 (AS)		4.37E-001	1.14E-001		pCi/g	0.500	g		10/10/02	60,003	seconds	+	
U-238 (AS)	062-110	2.28E+060	2.78E-001		pCi/g	0.500	g		10/10/02	60,003	seconds	+	

Comments:

Sample ID: HEM-6-3FT

L19307

Collect Start: 09/22/02 0:00

Station:

US Ecology

Collect Stop:

Description:

US Eco

Received: 10/04/02 Matrix: Solids (SD)

LIMS Number: L19307-3

(80699)

US607-3EREGFS-02

Volume

% Moisture:	9.17	, ,			Volume:									
Radionuclide	SOP#	Activity Cone	Uncertainty (2 Sigma)	MDC	Units	Aliquot Volume	Aliquot Units	Reference Date	Count Date	Count Time	Count Time Units	Fla	Flag Values	
BE-7	042-5	<		2.07E-001	pCi/G	310.300	G	09/22/02 12:00	10/10/02	60,000	Seconds			No
K-40	042-5	1.04E+001	4.90E-001		pCi/G	310,300	G	09/22/02 12:00	10/10/02	60,000	Seconds	+		Yes

Flag Values

Activity concentration exceeds MDC and 3 sigma and peak identified(gamma only)

Peak not identified, but forced activity concentration exceeds MDC and 3 sigma

High = Activity concentration exceeds customer reporting value

Spec = MDC exceeds customer technical specification

No = Peak not identified in gamma spectrum
Yes = Peak identified in gamma spectrum

Bolded text indicates reportable value.

**** Results are reported on an as received basis unless otherwise noted

10/14/02 7:31:27AM



Sample ID: HEM-6-3FT

L19307

Collect Start: 09/22/02 0:00

Station:

US Ecology

Collect Stop:

Description: LIMS Number: L19307-3

US607-3EREGFS-02

Received: 10/04/02 Matrix: Solids (SD)

(80699)

% Moisture:	9.17	(000/3)			Volume:								
Radionuclide	SOP#	P # Activity Conc	Uncertainty (2 Sigma)	MDC	Units	Aliquot Volume	Aliquot Units	Reference Date	Count Date	Count Time	Count Time Units	Flag	Values
CR-51	042-5			2.54E-001	pCi/G	310,300	G	09/22/02 12:00	10/10/02	60,000	Seconds		No
MN-54	042-5	<		2.19E-002	pCi/G	310.300	G	09/22/02 12:00	10/10/02	60,000	Seconds		No
CO-57	042-5	9.92E-002	2.51E-002		pCi/G	310.300	G	09/22/02 12:00	10/10/02	60,000	Seconds	+	Yes
CO-58	042-5	<		2.26E-002	pCi/G	310.300	G	09/22/02 12:00	10/10/02	60,000	Seconds		No
FE-59	042-5	<		5.45E-002	pCi/G	310.300	G	09/22/02 12:00	10/10/02	60,000	Seconds		No
CO-60	042-5	<		1.74E-002	pCi/G	310.300	G	09/22/02 12:00	10/10/02	60,000	Seconds		No
ZN-65	042-5	<		4.78E-002	pCi/G	310.300	l G	09/22/02 12:00	10/10/02	60,000	Seconds		No
SE-75	042-5	<		2.80E-002	pCi/G	310.300	G	09/22/02 12:00	10/10/02	60,000	Seconda		No
SR-85	042-5	<		2.86E-002	pCi/G	310.300	G	09/22/02 12:00	10/10/02	60,000	Seconds	*	No
Y-88	042-5	<		2.00E-002	pCi/G	310.300	G	09/22/02 12:00	10/10/02	60,000	Seconds		No
NB-94	042-5	<		1.94E-002	pCi/G	310,300	G	09/22/02 12:00	10/10/02	60,000	Seconds		No
NB-95	042-5	<		3.62E-002	pCi/G	310.300	G	09/22/02 12:00	10/10/02	60,000	Seconds	*	No
ZR-95	042-5	<		4.22E-602	pCi/G	310,300	G	09/22/02 12:00	10/10/02	60,000	Seconda		No
MO-99	042-5	<		2.58E+000	pCi/G	310,300	G	09/22/02 12:00	10/10/02	60,000	Seconds		No
RU-103	042-5	<		2.52E-002	pCi/G	310.300	G	09/22/02 12:00	10/10/02	60,000	Seconds		No
RU-106	042-5	<		1.83E-001	pCi/G	310.300	G	09/22/02 12:00	10/10/02	60,000	Seconds		No
CD-109	042-5	<		9.30E-001	pCi/G	310.300	G	09/22/02 12:00	10/10/02	60,000	Seconds		No
AG-110M	042-5	 		2.08E-002	pCi/G	310,300	G	09/22/02 12:00	10/10/02	60,000	Seconds		No
SN-113	042-5	<		2.81E-002		310.300	G	09/22/02 12:00	10/10/02	60,000	Seconds		No
SB-124	042-5	<		2.35E-002		310.300	G	09/22/02 12:00	10/10/02	60,000	Seconds		No
SB-125	042-5	<		5.57E-002	pCi/G	310.300	G	09/22/02 12:00	10/10/02	60,000	Seconds		No
TE-129M	042-5	<		3.15E-001	15	310.300	<u> </u>	09/22/02 12:00	10/10/02	60,000	Seconds		No
1-131	042-5	<	1	8.90E-002	pCi/G	310.300	G	09/22/02 12:00	10/10/02	60,000	Seconds		No

Flag Vatues

Activity concentration exceeds MDC and 3 sigma and peak identified(gamma only)

Peak not identified, but forced activity concentration exceeds MDC and 3 sigma

Activity concentration exceeds customer reporting value Hìgh

MDC exceeds customer technical specification Spec

Peak not identified in gamma spectrum No Peak identified in gamma spectrum Yes

Boided text indicates reportable value.





Sample ID: HEM-6-3FT

Station:

L19307 **US Ecology** Collect Start: 09/22/02 0:00

Collect Stop:

Received: 10/04/02 Matrix: Solids (SD)

Description: LIMS Number: L19307-3

(20800)

US607-3EREGFS-02

% Moisture:		(80099)		•					Volume:								
Radionuclide	SOP#	SOP # Activity Cone					Uncertainty (2 Sigma)	MDC	Units	Aliquot Volume	Aliquot Units	Reference Date	Count Date	Count Time	Count Time Units	Flag Va	ilues
BA-133	042-5			2.56E-002	pCi/G	310.300	G	09/22/02 12:00	10/10/02	60,000	Seconds		No				
CS-134	042-5	<		1.88E-002	pCi/G	310.300	G	09/22/02 12:00	10/10/02	60,000	Seconds		No				
CS-136	042-5	<		4.77E-002	pCi/G	310.300	G	09/22/02 12:00	10/10/02	60,000	Seconds		No				
CS-137	042-5	1.12E-001	2.05E-002		pCi/G	310.300	G	09/22/02 12:00	10/10/02	60,000	Seconds	+	Yes				
CE-139	042-5	<		3.16E-002	pCi/G	310.300	G	09/22/02 12:00	10/10/02	60,000	Seconds	*	No				
BA-140	042-5	<		1.71E-001	pCi/G	310.300	G	09/22/02 12:00	10/10/02	60,000	Seconds		No				
LA-140	042-5	<		4.76E-002	pCi/G	310.300	G	09/22/02 12:00	10/10/02	60,000	Seconds		No				
CE-141	042-5	<		1.07E-001	pCi/G	310.300	G	09/22/02 12:00	10/10/02	60,000	Seconds	*	No				
CE-144	042-5	<		2.09E-001	pCi/G	310.300	G	09/22/02 12:00	10/10/02	60,000	Seconds		No				
EU-152	042-5	/ <		5.92E-002	pCi/G	310.300	G	09/22/02 12:00	10/10/02	60,000	Seconds		No				
EU-154	042-5	<		5.91E-002	pCi/G	310.300	G	09/22/02 12:00	10/10/02	60,000	Seconds	*	No				
HG-203	042-5	<		2.68E-002	pCi/G	310.300	G	09/22/02 12:00	10/10/02	60,000	Seconds		No				
RA-226	042-5	6.66E-001	3.56E-002		pCi/G	310.300	G	09/22/02 12:00	10/10/02	60,000	Seconds	+	Yes				
AC-228	042-5	6.17E-001	8.67E-002		pCVG	310.300	G	09/22/02 12:00	10/10/02	60,000	Seconds	+	Yes				
TH-228	042-5	5.64E-001	7.78E-002		pCi/G	310.300	G	09/22/02 12:00	10/10/02	60,000	Seconds	+	Yes				
TH-232	042-5	5.59E-001	3.78E-002		pCi/G	310.300	G	09/22/02 12:00	10/10/02	60,000	Seconds	+	Yes				
U-235	042-5	6.49E+000	1.71E-001		pCi/G	310.300	G	09/22/02 12:00	10/10/02	60,000	Seconds	+	Yes				
U-238	042-5	2,28E+001	3.43E+000		pCi/G	310.300	G	09/22/02 12:00	10/10/02	60,000	Seconds	+	Yes				
NP-239	042-5	<		2.67E+001	pCi/G	310.300	G	09/22/02 12:00	10/10/02	60,000	Seconds	*	No				

Comments:

Flag Values

Activity concentration exceeds MDC and 3 sigms and peak identified(gamma only)

Peak not identified, but forced activity concentration exceeds MDC and 3 sigma Activity concentration exceeds customer reporting value

High

MDC exceeds customer technical specification Spec

Peak not identified in gamma spectrum No Yes Peak identified in gamma spectrum

Bolded text indicates reportable value.

**** Results are reported on an as received basis unless otherwise noted

7007 / b T / B T

L19307

US607-3EREGFS-02

Sample ID: HEM-5-3FT

Station: Description: **US Ecology**

Collect Start: 09/22/02 0:00

Collect Stop:

Received: 10/04/02 Matrix: Solids (SD)

Volume:

LIMS Number: L19307-4 % Moisture: 8.51

% Moisture:	וניים									VOLUME:			
Radionuclide	SOP#	Activity Cone	Uncertainty (2 Sigma)	MDC	Units	Aliquot Volume	Aliquot Units	Reference Date	Count Date	Count Time	Count Time Units	Fla	g Values
BE-7	042-5	<		1.50E-001	pCi/G	303.100	G	09/22/02 12:00	10/10/02	60,000	Seconds		No
K-40	042-5	1.15E+001	3.79E-001		pCi/G	303.100	G	09/22/02 12:00	10/10/02	60,000	Seconds	+	Yes
CR-51	042-5	<		1.72E-001	pCi/G	303.100	G	09/22/02 12:00	10/10/02	60,000	Seconds		No
MN-54	042-5	<		1.60E-002	pCi/G	303.100	G	09/22/02 12:00	10/10/02	60,000	Seconds		No
CO-57	042-5	4.20E-002	1.38E-002		pCi/G	303.100	G	09/22/02 12:00	10/10/02	60,000	Seconds	+	Yes
CO-58	042-5	<		1.67E-002	pCi/G	303.100	G	09/22/02 12:00	10/10/02	60,000	Seconds		_ No
FE-59	042-5	<		3.85E-002	pCi/G	303.100	G	09/22/02 12:00	10/10/02	60,000	Seconds		No
CO-60	042-5	<		1.52E-002	pCi/G	303.100	G	09/22/02 12:00	10/10/02	60,000	Seconds		No
ZN-65	042-5	<		3.50E-002	pCi/G	303,100	G	09/22/02 12:00	10/10/02	60,000	Seconds		No
SE-75	042-5	<	1	2.03E-002	pCVG	303.100	G	09/22/02 12:00	10/10/02	60,000	Seconds		No
SR-85	042-5	<		2,05E-002	pCVG	303.100	G	09/22/02 12:00	10/10/02	60,000	Seconds	*	No
Y-88	042-5	<		1.50E-002	pCVG	303.100	G	09/22/02 12:00	10/10/02	60,000	Seconds		No
NB-94	042-5	<		1.38E-002	pCi/G	303.100	G	09/22/02 12:00	10/10/02	60,000	Seconds		No
NB-95	042-5	<		2.01E-082	pCi/G	303.100	G	09/22/02 12:00	10/10/02	60,000	Seconds	*	No
ZR-95	042-5	<		3.17E-002	pCi/G	303,100	G	09/22/02 12:00	10/10/02	60,000	Seconds		No
MO-99	042-5	<		1.63E+000	pCi/G	303.100	G	09/22/02 12:00	10/10/02	60,000	Seconds		No
RU-103	042-5	<		1.88E-992	pCi∕G	303.100	G	09/22/02 12:00	10/10/02	60,000	Seconds		No
RU-106	042-5	 <		1,30E-001	pCi/G	303.100	G	09/22/02 12:00	10/10/02	60,000	Seconds		No
CD-109	042-5	<		5.59E-001	pCi/G	303.100	G	09/22/02 12:00	10/10/02	60,000	Seconds	*	No
AG-110M	042-5	<		1.42E-002	pCi/G	303.100	G	09/22/02 12:00	10/10/02	60,000	Seconds		No
SN-113	042-5	<		1.97E-602	pCi/G	303.100	G	09/22/02 12:00	10/10/02	60,000	Seconds		No
SB-124	042-5	<		1.56E-002	pCVG	303.100	G	09/22/02 12:00	10/10/02	60,000	Seconds		No
SB-125	042-5	<	1	3.93E-002	pCi/G	303.100	G	09/22/02 12:00	10/10/02	60,000	Seconds		No

Flag Values

Activity concentration exceeds MDC and 3 sigma and peak identified(gamma only)

Peak not identified, but forced activity concentration exceeds MDC and 3 sigma Activity concentration exceeds customer reporting value

High

(80700)

MDC exceeds customer technical specification Spec

Peak not identified in gamma spectrum No Yes Peak identified in gamma spectrum

Boided text indicates reportable value.

**** Results are reported on an as received basis unless otherwise noted



A Teledyne Technologies Company

Sample ID: HEM-S-3FT

Station:

L19307

Collect Start: 09/22/02 0:00 Collect Stop:

Description:

US Ecology

Received: 10/04/02

LIMS Number: 1.19307-4

(20700)

US607-3EREGFS-02

Matrix: Solids (SD)

% Moisture:		(80700)				05007		··-	Wattix: South (SD) Volume:					
Radionuciide	SOP#	Activity Cone	Uncertainty (2 Sigma)	MDC	Unita	Aliquot Volume	Aliquot Units	Reference Date	Count Date	Count Time	Count Time Units	Flag V	alues	
TE-129M	042-5	<		2.22E-001	pCi/G	303.100	G	09/22/02 12:00	10/10/02	60,000	Seconds		No	
1-131	042-5	<		6.46E-002	pCi/G	303.100	G	09/22/02 12:00	10/10/02	60,000	Seconds		No	
BA-133	042-5	<		1.83E-002	pCi/G	303.100	G	09/22/02 12:00	10/10/02	60,000	Seconds		No	
CS-134	042-5	<		1.34E-002	pCi/G	303.100	G	09/22/02 12:00	10/10/02	60,000	Seconds	<u>-</u>	No	
CS-136	042-5	<		3.31E-002	pCi/G	303.100	G	09/22/02 12:00	10/10/02	60,000	Seconds		No	
CS-137	042-5	6.80E-002	1.47E-002	·	pCi/G	303.100	G	09/22/02 12:00	10/10/02	60,000	Seconds	+	Yes	
CE-139	042-5	<		1.88E-002	pCi/G	303.100	G	09/22/02 12:00	10/10/02	60,000	Seconds	*	No	
BA-140	042-5	<		1.28E-001	pCi/G	303.100	G	09/22/02 12:00	10/10/02	60,000	Seconds		No	
LA-140	042-5	<		4.20E-002	pCi/G	303,100	G	09/22/02 12:00	10/10/02	60.000	Seconds	*	No	
CE-141	042-5	<		6.15E-002	pCi/G	303.100	G	09/22/02 12:00	10/10/02	60,000	Seconds	*	No	
CE-144	042-5	<		1.35E-001	pCi/G	303.100	G	09/22/02 12:00	10/10/02	60,000	Seconds	<u>`</u>	No	
EU-152	042-5	. <		4.20E-002	pCi/G	303.100	G	09/22/02 12:00	10/10/02	60.000	Seconds		No	
EU-154	042-5	<		3.61E-002	pCi/G	303.100	G	09/22/02 12:00	10/10/02	60,000	Seconds		No	
HG-203	042-5	<		1.96E-002	pCi/G	303.100	G	09/22/02 12:00	10/10/02	60,000	Seconds		No	
RA-226	042-5	5.83E-001	2.74E-002		pCi/G	303,100	G	09/22/02 12:00	10/10/02	60,000	Seconds	+	Yes	
AC-228	042-5	1.03E+000	1.51E-001		pCi/G	303.100	G	09/22/02 12:00	10/10/02	60,000	Seconds	+	Yes	
TH-228	042-5	6.03E-001	5.85E-002		pCi/G	303.100	G	09/22/02 12:00	10/10/02	60,000	Seconds	+	Yes	
TH-232	042-5	5.67E-001	2.87E-002		pCi/G	303.100	G	09/22/02 12:00	10/10/02	60,000	Seconds	+	Yes	
U-235	042-5	3.19E+000	1.03E-001		pCi/G	303.100	G	09/22/02 12:00	10/10/02	60,000	Seconds	+	Yes	
U-238	042-5	4.34E+000	1.93E+000		pCi/G	303.100	G	09/22/02 12:00	10/10/02	60,000	Seconds	+	Yes	
NP-239	042-5	<		1.63E+001	p€i/G	303.100	G	09/22/02 12:00	10/10/02	60,000	Seconds	*	No	

Comments:

Flag Values

Activity concentration exceeds MDC and 3 sigma and peak identified(gamma only) =

Peak not identified, but forced activity concentration exceeds MDC and 3 sigma Activity concentration exceeds customer reporting value High

Spec = MDC exceeds customer technical specification

Peak not identified in gamma spectrum No Yes Peak identified in gamma spectrum


Bolded text indicates reportable value.



Appendix C Contractor Soil Sample Location Map

EE/CA for Response Action at Deul's Mountain

WESTINGHOUSE-HEMATITE SOIL SAMPLE PLOTS



X - MARKS THE HOLE LOCATION